

Delaware Coastal Programs 100 W. Water Street, Ste. 7B Dover, Delaware 19904

Re: Delaware Coastal Management Program Consistency Review for the Construction of one (1) Unit in Milton, DE for Affordable Homeownership Built by Sussex County Habitat for Humanity (Project Partially Funded Economic Development Initiative Community Project Funds)

AZ-RI Consultants is completing an Environmental Review for the proposed construction of one residential home in Milton, DE on behalf of Sussex County Habitat For Humanity (SCHFH).

SCHFH is a recipient of a Economic Development Initiative/Community Project Funding award from the U.S. Department of Housing and Urban Development (HUD), which will be used to help build this single-family home for low-income homeownership in Milton, Delaware.

Project Description:

SCHFH will build this home in Milton, DE for affordable homeownership. The home will be targeted to low-income Sussex County residents making at or below 60% of area median income. This project will stabilize a household by providing the opportunity to build and purchase an affordable home.

Construction of the home will take place entirely within the property lines of the lot. The lot is on public water and sewer. SCHFH installs hookups for utilities towards the end of the construction process for each home. SCHFH may also install or repair sidewalks on the property, in accordance with housing codes.

Building Methods:

For new construction projects, SCHFH builds conventional stick framed houses on concrete block foundations with a crawl space. Stick framing means essentially all parts of the framed building structure, from roofs to trusses to walls, are constructed on-site from loose lumber delivered to the construction site. The organization may build a ranch-style or two-story home depending on the needs of the Habitat partner family. With few exceptions, SCHFH properties also receive a new shed, landscaping, asphalt driveways, and (when applicable) concrete pavement sidewalks. The majority of new SCHFH homes, including the home outlined in this consultation, are built in pre-existing



residential areas. As a result, they are connected to local utilities (rather than utilizing or digging wells).

For SCHFH properties, Sussex County Habitat for Humanity digs foundations that are 2-3 feet deep. All parcels require minor leveling of a few inches, with no major changes to the topography. Backfill will be used as necessary- areas will be filled in, as needed, with soil that has been shifted from other areas of the parcel.

SCHFH fully complies with all applicable local building codes and other legal requirements. All materials and equipment are kept on the property. SCHFH's Construction Department oversees all work onsite, and home construction is carried out by SCHFH employees, local contractors, volunteers, and Habitat partner families as part of their sweat equity requirements. Homes are built with affordability in mind, so energy efficiency is accounted for in home design and appliance choices. SCHFH also works to limit material waste, maximize durability, and implement environmentally friendly practices.

The final floor plan for each Habitat home is determined based on the features of each lot as well as the needs of each partner family. SCHFH finalizes the plan for each home prior to the start of construction. Please find four sample floor plans attached for a general view of how the home might look.

- 1. 3 Bedroom Ranch 25'6" x 44'
- 2. 5 Bedroom Ranch 29'4" x 50'
- 3. 4 Bedroom Two-Story 32' x 28'
- 4. 4 Bedroom Two-Story 15' x 50'

Property for Coastal Consistency Review:

28292 Fisherman Drive, Milton, DE 19968 Parcel ID: 334-10.00-206.00

AZ-RI has reviewed the above-reference project and has determined it to be consistent with the Delaware Coastal Management Program. This determination is based upon the following findings: the project is located in an existing neighborhood in the City of Milton, DE, will connect to municipal sewer and water, and is located in an area with ready access to stores, transportation, schools, healthcare, and other services.



We are requesting your review and concurrence with our determination for this new construction project pursuant to Coastal Zone Management Act regulations (15 CFR-Part 930). We look forward to working with your office during this consultation. Please do not hesitate to reach out with any questions.


Sincerely,

W

Hannah Wertz AZ-RI Consultants

Attachments:

- 1. Subject Property Description Map with Subject Property Photos
- 2. Sample of Potential Floor Plans
- 3. Sample of Recently Completed SCHFH Homes





1 Subject Property Boundaries (Sussex County, DE Property Records Map Data 12/08/23)





2 Subject Property Vicinity (Sussex County, DE Property Records Map Data 12/08/23)





ROOF PLAN






_c[\mathbf{O}

Ш



NOTE: THE FOLLOWING DESIGNS ARE BASED ON 2012 IRC

M.R. Designs, Inc. 26342 BROADKILL RD. MILTON, DE 19968 (302) 684-8082 www.mrdesignsinc.com ~ www.facebook.com/mrdesignsinc	3BR Ranch - 25'6" x 44' 422 NORTH STREET SEAFORD	- Porch Left DE 19973	
NOTE: THESE PLANS, DESIGNS & SUBJECT MATTER ARE BASED ON INFORMATION SUPPLIED BY THE OWNER AND/OR CONTRACTOR. DRAFTER, THEREFORE, TAKES NO RESPONSIBILITY FOR THEIR ACCURACY OR INTEGRITY. DRAWINGS ARE FOR DESIGN PURPOSES ONLY. ALL SPECIFICATIONS, DIMENSIONS & CONDITIONS SHOULD BE VERIFIED PRIOR TO COMMENCING CONSTRUCTION. THIS DRAWING, THE DESIGN & CONSTRUCTION FEATURES DISCLOSED ARE PROPERTY OF M.R. DESIGNS, INC. & SHOULD NOT BE COPIED IN PART OR WHOLE, WITHOUT THE EXPRESSED WRITTEN CONSENT OF M.R. DESIGNS, INC.	DRAWN BY: M. DOTTERER	PAGE: 2	
	SCALE: 1/4" = 1'-0"		
	DATE: Monday, March 28, 2022	FLOOR & FOUNDATION PLANS	



-	Į	29'-4"		
	(3)2×10 SPF BUILT-UP GIRDER 16"×16" PIERS & 24"×24" FOURE CONC FOOTERS @ 3500 PS	ALL PILASTERS (&"x16")TO BE KEYED IN TO THE FOUNDATION WALL		= =
			[¬] , <u>-</u> ++	
			- <u>9</u> -0-	
FOUNDATION ACCESS DOOR - IRC R408.3 MIN. OPENING (18" × 24")				
			i∔	
				====
X16" BLOCK PIERS W(1) VERT. 5 REBAR HOOKED INTO FTG EBARS. GROUT PIER SOLID. 0LT P.T. WOOD PLATE TO 1/2 5/8" DIAX & A' ANCHOR OLTS SET IN TOP OF PIER				(2)2" × 4 TOP PLATE
OLT P.T. WOOD PLATE TO V2 5/8" DIA × 8" ANCHOR OLTS SET IN TOP OF PIER			FOUNDATION ACCESS DOOR - IRC R408.3 MIN. OPENING (18" × 24")	
(2)2×∂ P.T.				
				= = = =
0.122×6 1				
	X ' 13'-9 3/4"	<u></u>		
┶ <mark>┻╤╤╤╤╤╤╤</mark>				
2×12 PLT. STRINGERS				= = =
(2) #5 REBARS EACH WAY				====
2" × 8" P.T. SILL PLATE		INSIDE GRADE TO BE LEVELED CLEAR OF DEBRIS, VEGETATION & ORGANIC MATERIAL A 6-MIL POLY VAPOR BARRIER MUST THEN BE INSTALLED THROUGHOUT. IRC R408.4		
			54'-0"	====
				====
TO BE INSTALLED ON CRAWL IALLS WHEN CRANL SPACE IS DTO OUTSIDE AIR EXPOSED CRAWL SPACE FOUNDATIONS COVERED WI A CONTINUOUS VAPOR BARRIER. NI-102.T.				
				<u> </u>
BAND JOIST			10":20" CONC FOOTING BOTTOM OF FOOTING FOOTING TO BE 26" BELOW GRADE AS PER SUSSEX COUNTY	
			BELOW GRADE AS PER SUSPEX COUNTY	
				====
		ALL PILASTERS (8'x16")TO BE KEYED		
ļ				
I				
סאלד	260 P.T. JØ15T5 @ 16" O.C.			(2)2"×ð" = = =
× 24" CONC FOOTING 5 REBARS EACH WAY				
W (1) VERT. #5 REBAR REBAR5. GROUT PIER PLATE TO (2) 5/8" DIA. S SET IN TOP OF PIER	(2)2×8 P.T.			
S SET IN TOP OF PIER				
	1'-4" 2'-8" 1'-4" 3'-4" 1'-4"			
			¦	
		14'-8"	_ '	
	FOUNDATION / F	LOOR FRAMING PLAN		
	SCA	LE: 1/4" = 1' - <i>0</i> "		•


PROJECT DESCRIPTION


TOTAL CONDITIONED AREA: 1,434 SQ. FT. COVERED PORCH AREA: 84 SQ. FT. HVAC SYSTEMS, SPECIFICATIONS & LOCATIONS TO BE DESIGNED BY HVAC CONTRACTOR ALL WINDOWS ARE SPECIFIED AS ANDERSEN 400 SERIES


ALL HEADER SIZES: 2×4 WALLS: (2) 2×12 SPF, UNLESS OTHERWISE NOTED 2×6 WALLS: (3) 2×12 SPF, UNLESS OTHERWISE NOTED ALL INTERIOR DIMENSIONS ARE TO FINISHED WALLS

EXTERIOR WALL CONSTRUCTION: 2×4 SPF WOOD STUDS 1ST FLOOR FINISHED CEILING HEIGHT 8' - 0"

ROOF VENTILATION TO COMPLY WITH IRC R806







HYAC SYSTEM(S), SPECIFICATIONS 4 LOCATIONS TO DETERMINED BY HVAC CONTRACTOR

FRONT PORCH AREA: 32.5 SQFT.


ALL INTERIOR DIMENSIONS ARE TO UNFINISHED WALLS (WITHOUT GYPSUM)

NOTE: ALL WINDOW NUMBERS REPRESENT INCHES (EXAMPLE: 3648 = 36"W. x 48"H.)


ALL HEADER SIZES: 2x4 WALLS: (2) 2x12 SPF, UNLESS NOTED OTHERWISE 2×6 WALLS: (3) 2×12 SPF, UNLESS NOTED OTHERWISE

- AND TO INCLUDE BATTERY BACK-UP AND INTER-CONNECTED, IRC R-315
- ALL WINDOWS LABELED 'EGRESS' TO HAVE MIN, 5,7 SQ FT OF CLEAR OPENING AS PER R-310









ROOF FRAMING PLAN

NOTE: THE FOLLOWING DESIGNS ARE BASED ON 2012 IRC

M.R. Designs, Inc. 26342 BROADKILL RD. MILTON, DE 19968 (302) 684-8082 www.mrdesignsinc.com ~ www.facebook.com/mrdesignsinc	HOPE HILL- 4 BEDROOM 308 WEST FRONT STREET LAUREL	(SOOKLALL) DE	19956	
NOTE: THESE PLANS, DESIGNS & SUBJECT MATTER ARE BASED ON INFORMATION SUPPLIED BY THE OWNER AND/OR CONTRACTOR. DRAFTER, THEREFORE, TAKES NO RESPONSIBILITY FOR THEIR ACCURACY OR INTEGRITY. DRAWINGS ARE FOR DESIGN PURPOSES ONLY. ALL SPECIFICATIONS, DIMENSIONS & CONDITIONS SHOULD BE VERIFIED PRIOR TO COMMENCING CONSTRUCTION. THIS DRAWING, THE DESIGN & CONSTRUCTION FEATURES DISCLOSED ARE PROPERTY OF M.R. DESIGNS, INC. & SHOULD NOT BE COPIED IN PART OR WHOLE, WITHOUT THE EXPRESSED WRITTEN CONSENT OF M.R. DESIGNS, INC.	DRAWN BY: FOREST DOTTERER	PAGE:		
	SCALE: 1/4" = 1'-0"	2		
	DATE: Friday, May 13, 2022	FLOOR PLANS		

Sample of Recently Completed SCHFH Homes







