GEO-TECHNOLOGY ASSOCIATES, INC.

GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS





August 28, 2025

Delaware Department of Natural Resources and Environmental Control Delaware Coastal Programs 100 West Water Street, Suite 7B Dover, Delaware 19904

Re: Coastal Zone Management Act Federal Consistency

Route 40 Replacement project

New Castle County, Delaware

To Whom It May Concern:

On behalf of Eastern Shore Natural Gas (Applicant), Geo-Technology Associates, Inc. (GTA) is submitting this application for natural gas connector line and rupture mitigation valve installation, filed as part of Federal Energy Regulatory Commission's (FERC) Annual Certificate Report (Form No. 537) under Section 157.208 – Construction, Acquisition, Operation, Replacement & Miscellaneous Rearrangement of Facilities.

Ground disturbance will take place to replace piping and valves, construct fence and install stone within the fenced areas. No direct impact to wetlands or waterbodies are proposed. To facilitate the Application's review, GTA is submitting the following information for your review and processing:

- 1. Completed Coastal Zone Management Act Federal Consistency Form;
- Site Location Map;
- 3. USGS Topographic Map; and,
- 4. Route 40 Replacement 30% Plans, Prepared by Morris & Ritchie Associates, Inc.

The proposed project site is an approximately 800 foot pipeline installation route located along Route 40 in the Glasgow area of New Castle County, Delaware.

Delaware Department of Natural Resources and Environmental Control

Re: ESNG Route 40 Replacement Project

August 28, 2025

Page 2

GTA is confident that the enclosed information for the ESNG Route 40 Replacement project satisfies the general and regional conditions for the Coastal Zone Management Act. Should you have any questions or need additional information, please contact this office at (410) 515 9446.

Sincerely,

GEO-TECHNOLOGY ASSOCIATES, INC.

Joshua Riding

Senior Project Scientist

T. Andy Stansfield Jr.

Vice President

KJS/JSR/MAJ 23289

L:\Shared\Project Files\2025\23289 - Route 40 Replacement Project\WET\Reports - Permitting\CZM\23289 CZM Cover Letter.doc

Completed Coastal Zone Management Act Federal Consistency Form

Delaware Department of Natural Resources and Environmental Control Delaware Coastal Management Program



| InitialReview: | |
|----------------|----------|
| Updated On: | |
| Complete: | |
| | Use Only |

Coastal Zone Management Act Federal Consistency Form

This document provides the Delaware Coastal Management Program (DCMP) with a Federal Consistency Determination or Certification for activities regulated under the Coastal Zone Management Act of 1972, as amended, and NOAA's Federal Consistency Regulations, 15 C.F.R. Part 930. Federal agencies and other applicants for federal consistency are not required to use this form; it is provided to applicants to facilitate the submission of a Consistency Determination or Consistency Certification. In addition, federal agencies and applicants are only required to provide the information required by NOAA's Federal Consistency Regulations.

| Proje | ect/Activity Name: | | | | | |
|------------|---|----------------------------|---|--|--|--|
| I. Cont | Federal Agency or Non-Federal Applicant Contact Information: Contact Name/Title: | | | | | |
| Fede | eral Agency Contractor Nam | ne (if applicable): | | | | |
| (eith | eral Agency: er the federal agency propo stance to a non-federal appl | | leral agency issuing a federal license/permit or financial | | | |
| Maili | ng Address: | | | | | |
| City: | | State: | Zip Code: | | | |
| E-ma | ail: | | Telephone #: | | | |
| II. | Federal Consistency Ca | tegory: | | | | |
| | Federal Activity or Develop (15 C.F.R. Part 930, Subp | | Federal License or Permit Activity (15 C.F.R. Part 930, Subpart D) | | | |
| | Outer Continental Shelf Ac (15 C.F.R. Part 930, Subpa | | Federal License or Permit Activity which occurs wholly in another state (interstate consistency | | | |
| | Federal Financial Assistar (15 C.F.R. Part 930, Subp | | activities identified in DCMP's Policy document) | | | |
| III. | Detailed Project Descrip | otion (attach additional s | heets if necessary): | | | |
| | | | | | | |

| / . | General Analysis of Coastal Effects (attach additional sheets if flecessary). |
|------------|---|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | Detailed Analysis of Consistency with DCMP Enforceable Policies (attach additional sheets if necessary): |
| ۰, | licy 5.1: Wetlands Management |
| _ | incy 5.1. Wettanus Management |
| | |
| | |
| | |
| _ | licy 5.2: Beach Management |
| _ | ilcy 3.2. Deach Management |
| | |
| | |
| | |
| | lieu F. 2. Constal Matero Management (includes wells, water supply, and stormwater management. Attach additional shoots if necess |
| _ | licy 5.3: Coastal Waters Management (includes wells, water supply, and stormwater management. Attach additional sheets if necess |
| | |
| | |
| | |
| | |
| 0 | licy 5.4: Subaqueous Land and Coastal Strip Management |
| | |
| | |
| | |
| | |
| 0 | licy 5.5: Public Lands Management |
| | |
| | |
| | |
| | |


| Policy 5.6: Natural Lands Management |
|---|
| |
| |
| |
| |
| |
| Policy 5.7: Flood Hazard Areas Management |
| Folicy 3.7. Flood Hazard Areas Management |
| |
| |
| |
| |
| |
| Policy 5.8: Port of Wilmington |
| |
| |
| |
| |
| |
| |
| Policy 5.9: Woodlands and Agricultural Lands Management |
| |
| |
| |
| |
| |
| |
| Policy 5.10: Historic and Cultural Areas Management |
| |
| |
| |
| |
| |
| Policy 5.11: Living Resources |
| Tolloy of the Enviring Recognition |
| |
| |
| |
| |
| |
| Policy 5.12 Mineral Resources Management |
| |
| |
| |
| |
| |

| Policy 5.13: State Owned Coastal Recreation and Conservation |
|--|
| |
| Policy 5.14: Public Trust Doctrine |
| |
| Policy 5.15: Energy Facilities |
| |
| Policy 5.16: Public Investment |
| |
| Policy 5.17: Recreation and Tourism |
| |
| Policy 5.18: National Defense and Aerospace Facilities |
| |
| Policy 5.19: Transportation Facilities |
| |


| Poli | icy 5.20: Air Quality Management | : | |
|-------|-------------------------------------|------------------|--|
| | | | |
| | | | |
| | | | |
| | | | |
| Polic | icy 5.21: Water Supply Manageme | ent | |
| | | | |
| | | | |
| | | | |
| | | | |
| Polic | cy 5.22: Waste Disposal Manager | ment | |
| | | | |
| | | | |
| | | | |
| | | | |
| Poli | cy 5.23: Development | | |
| | | | |
| | | | |
| | | | |
| | | | |
| Poli | cy 5.24: Pollution Prevention | | |
| | | | |
| | | | |
| | | | |
| | | | |
| Poli | icy 5.25: Coastal Management Co | ordination | |
| | | | |
| | | | |
| | | | |
| | | | |
| VI. | JPP and RAS Review (Check a | ull that apply): | |
| | | | ng and/or Regulatory Advisory Service meeting? |
| | <u></u> | _ | _ |
| | ☐ JPP I | RAS | None |
| | *If ves. provide the date of the me | eetina(s): | |

attach details)

| VII. | I. Statement of Certification/Determination and Signature (Check one and sign below): | | | | | | |
|----------------------|--|---|-----------------------------|-------------------------------------|--|---------------------------------------|--|
| | FEDERAL AGENCY CONSISTENCY DETERMINATION. Based upon the information, data, and analysis included herein, the federal agency, or its contracted agent, listed in (I) above, finds that this proposed activity is consistent to the maximum extent practicable with the enforceable policies of the Delaware Coastal Management Program. | | | | | | |
| | OR | | | | | | |
| | FEDERAL AGENCY NEGATIVE DETERMINATION. Based upon the information, data, and analysis included herein, the federal agency, or its contracted agent, listed in (I) above, finds that this proposed activity will not have any reasonably foreseeable effects on Delaware's coastal uses or resources (Negative Determination) and is therefore consistent with the enforceable policies of the Delaware Coastal Management Program. | | | | | | |
| | OR | | | | | | |
| | analysis in agency ap | icluded herein, the r oplying for federal full e policies of the Dela | non-federal unding, lis | l applicant for a ted in (I) abo | a federal license ve, finds that t | e or permit, or his proposed | ne information, data, and state or local government activity complies with the sted in a manner consistent |
| | Signature: | | | | | | |
| Print | ted Name: | | | | | Date: | |
| or ob belov | ojection to w. Concurre | | ermination ed if the sta | or consistenc | y certification in | n accordance | de its concurrence with with the deadlines listed wable timeframe. |
| | | or Development Proje 930, Subpart C) | ect | | | tion to extend an C.F.R. § 930.41) | additional 15 days or |
| | eral License C.F.R. Part 9 | or Permit 930, Subpart D) | | | | eriod can be stay | it three months. The six red by mutual agreement. |
| | Outer Continental Shelf Activity (15 C.F.R. Part 930, Subpart E) Six months, with a status letter at three months. If three month status letter not issued, then concurrence presumed. The six month review period can be stayed by mutual agreement. (15 C.F.R. § 930.78) | | | | en concurrence v period can be stayed | | |
| 1 | | al Assistance to State 930, Subpart F) | or Local G | Governments | State (| Clearinghouse so | chedule |
| OFFI | CIAL USE (| ONLY: | | | | | |
| Revi | ewed By: | | | Fed Con ID: | | Date Receive | ed: |
| Publi | ic notice da | tes: | to | | Comments Re | ceived: N | O YES [attach comments] |
| Decis (objections | sion type: | | | | _ Decisior | Date: | |











GEO-TECHNOLOGY ASSOCIATES, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS

3445-A BOX HILL CORPORATE CENTER DRIVE ABINGDON, MARYLAND 21009 PHONE: 410-515-9446 FAX: 410-515-4895 WWW.GTAENG.COM


© GEO-TECHNOLOGY ASSOCIATES, INC.

SITE LOCATION MAP ESNG ROUTE 40 REPLACEMENT PROJECT

NEW CASTLE COUNTY, DELAWARE


JOB NO. 23289 SCALE: 1"=2,000' DATE: AUGUST 01, 2025 DRAWN BY: KJS REVIEW BY: MAJ FIGURE: 1





SOURCE: UNITED STATES GEOLOGICAL SURVEY (USGS), ELKTON, MD AND SAINT GEORGES, DE QUADRANGLES, 7.5 MINUTE TOPOGRAPHIC MAP SERIES, BOTH DATED 2023.





MAJ



GEO-TECHNOLOGY ASSOCIATES, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS

3445-A BOX HILL CORPORATE CENTER DRIVE ABINGDON, MARYLAND 21009 PHONE: 410-515-9446 FAX: 410-515-4895


WWW.GTAENG.COM
© GEO-TECHNOLOGY ASSOCIATES, INC.

USGS TOPOGRAPHIC MAP
ESNG ROUTE 40 REPLACEMENT
PROJECT

NEW CASTLE COUNTY, DELAWARE

JOB NO. 23289 SCALE: 1"=2,000' DATE: AUGUST 01, 2025 DRAWN BY: KJS REVIEW BY:

FIGURE:



DRAWING INDEX

EASTERN SHORE NATURAL GAS COMPANY

ROUTE 40 REPLACEMENT

COVER SHEET

2 EROSION & SEDIMENT CONTROL GENERAL NOTES

EROSION & SEDIMENT CONTROL DETAILS

6 TRAFFIC CONTROL DETAILS

7 WEST TIE-IN 8 EAST TIE-IN

7 - 10 CONSTRUCTION DETAILS

II EXISTING MAINLINE PIPING AND INSTRUMENTATION DETAILS

PROPOSED MAINLINE PIPING AND INSTRUMENTATION DETAILS

13 - 14 P&ID SYMBOLS AND LEGENDS15 RMV PIPING & INSTRUMENTATION PLAN

16 PLAN & PROFILE

PROPOSED 0.14± MILES OF 8" NATURAL GAS PIPELINE NEW CASTLE COUNTY, DELAWARE PROJECT NUMBER: ES XXXX

MOC: XXXX-XX

MATERIAL NOTES AND SPECIFICATIONS

1) COMMODITY DESCRIPTION:

NATURAL GAS

2) MAXIMUM OPERATING PRESSURE:

XXX PSIG

3) PIPE AND MATERIAL GRADE:

X-52

4) MATERIAL SPECIFICATION:

API-5L

5) SEAM TYPE: ELECTRIC RESISTANCE WELDED (ERW)

6) SPECIFIED MINIMUM YIELD STRENGTH: XX,XXX PSI

7) PERCENTAGE OF MAX ALLOWABLE

HOOP STRESS AT MAOP: XXXXXX (XXX PSIG)

6) PIPE OUTSIDE DIAMETER:

9.625"

9) WALL THICKNESS:

10) MINIMUM FITTING RATING:

ANSI XXX

11) CATHODIC PROTECTION:

MPRESSED CURRENT

12) AC MITIGATION RISK LEVEL: XX


I3) PROTECTIVE COATING:
 I4) DESIGN PRESSURE:
 I5) TEST PRESSURE:
 MIN = XXXX PSIG

MAX = XXXX PSIG

NOTE: FINAL TEST PRESSURE WILL BE DETERMINED

PRIOR TO ACCEPTANCE OF CONTRACTOR'S TESTING PROCEDURE

16) DESIGN CLASS X




NO. DATE

DESCRIPTION




ROUTE 40 REPLACEMENT PROJECT LOCATION



EASTERN SHORE

500 ENERGY LANE, SUITE 200 DOVER, DE 19901 TELEPHONE (302) 734-6710 - FAX (302) 734-6745



COVER SHEET

8" PROPOSED PIPELINE
ROUTE 40 REPLACEMENT
NEW CASTLE COUNTY, DE

ESNG PROJ. CODE: DATE: 8/19/2025

MRA PROJECT NO: 23289 SCALE: AS SHOWN

DESIGN/CHECK BY: JTH/CWB SHEET: 1 OF 16



GENERAL ENVIRONMENTAL NOTES

- I. EROSION/SEDIMENTATION CONTROL STRUCTURES TO BE INSTALLED AND MAINTAINED AS NECESSARY DURING CONSTRUCTION TO AVOID/MINIMIZE IMPACT TO WETLANDS AND WATERBODIES, THESE BARRIERS WILL REMAIN IN PLACE UNTIL REVEGETATION AND RESTORATION ARE DEEMED SUCCESSFUL.
- 2. ANY TRENCH DEWATERING TO BE DIRECTED TO SEDIMENT FILTER BAG AND/OR DEWATERING STRUCTURE IN AN UPLAND AREA TO ENSURE THAT NO EROSION OR SEDIMENTATION OCCURS TO WETLANDS/WATERBODIES.
- 3. PRE-CONSTRUCTION CONTOURS TO BE RE-ESTABLISHED FOR ALL DISTURBED AREAS UNLESS OTHERWISE NOTED ON THE PLANS, ALL DISTURBED AREAS TO BE RESTORED AND/OR REVEGETATED AS APPLICABLE.
- 4. ALL DISTURBED AREAS TO BE RESTORED AND/OR REVEGETATED AS APPLICABLE. SEED, FERTILIZER, LIME AND MULCH TO BE APPLIED IN ACCORDANCE WITH RECOMMENDATIONS FROM LOCAL NATURAL RESOURCES CONSERVATION SERVICE (NRCS), AND LANDOWNER REQUIREMENTS (AGRICULTURAL AREAS). SEE SHEET 4 OF 16 FOR MULCH APPLICATION REQUIREMENTS.
- 5. FOR NON-ROADWAY AREAS, UPLAND RE-SEEDING TO BE PERFORMED IN ACCORDANCE WITH THE VEGETATIVE STABILIZATION DETAILS (SEE SHEET 5 OF 16).
- 6. CONSTRUCTION TO BE PERFORMED IN ACCORDANCE WITH REQUIREMENTS IN FERC UPLAND EROSION CONTROL, REVEGETATION AND MAINTENANCE PLAN AND FERC WETLAND AND WATERBODY CONSTRUCTION AND MITIGATION PROCEDURES.
- 7. THE NEW CASTLE CONSERVATION DISTRICT SEDIMENT AND STORMWATER MANAGEMENT PROGRAM MUST BE NOTIFIED IN WRITING FIVE (5) DAYS PRIOR TO COMMENCEMENT OF CONSTRUCTION. FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLAN.
- 8. REVIEW AND/OR APPROVAL OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN SHALL NOT RELIEVE THE CONTRACTOR FROM HIS OR HER RESPONSIBILITIES FOR COMPLIANCE WITH THE REQUIREMENTS OF THE SEDIMENT AND STORMWATER REGULATIONS, NOR SHALL IT RELIEVE THE CONTRACTOR FROM ERRORS OR OMISSIONS IN THE APPROVED PLAN.
- 9. IF THE APPROVED PLAN NEEDS TO BE MODIFIED, ADDITIONAL SEDIMENT AND STORMWATER CONTROL MEASURES MAY BE REQUIRED AS DEEMED NECESSARY BY THE NEW CASTLE
- IO. FOLLOWING SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN 14 CALENDAR DAYS AS TO THE SURFACE OF ALL PERIMETER SEDIMENT CONTROLS, SOIL STOCKPILES, AND ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.
- II. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN AND REPAIR ALL EROSION AND SEDIMENT CONTROL AND STORMWATER MANAGEMENT PRACTICES DURING CONSTRUCTION, THIS WILL BE MONITORED BY THE EASTERN SHORE NATURAL GAS (ESNG) ENVIRONMENTAL INSPECTOR, FOLLOWING CONSTRUCTION, ESNG WILL CONTINUE TO MONITOR THE EROSION AND SEDIMENT CONTROL AND STORMWATER MANAGEMENT MEASURES, UNTIL REVEGETATION AND RESTORATION ARE DEEMED SUCCESSFUL. DURING THIS TIMEFRAME, ESNG WILL ARRANGE FOR ANY NECESSARY REPAIRS AND MAINTENANCE TO SUCH STRUCTURES AND MEASURES, ESNG WILL ALSO ARRANGE FOR ANY AND ALL NECESSARY ADDITIONAL REVEGETATION AND/OR RESTORATION MEASURES DURING THIS TIMEFRAME.
- 12. REFER TO TYPICAL TOPSOIL SEGREGATION DETAIL FOR SUBSOIL/TOPSOIL PILE INFORMATION ON SHEET 3 OF 16.
- 3. ALL STONE, WITH THE EXCEPTION OF CHECK DAMS, MUST BE UNDERLAIN WITH A GEOTEXTILE FABRIC (E.G., TEMPORARY CONSTRUCTION ENTRANCES OFF PUBLIC ROADWAYS). GEOTEXTILE FABRIC SPECIFICATIONS WILL BE PROVIDED FOR VARIOUS APPLICATIONS.
- 14. EROSION CONTROL MATTING IS REQUIRED FOR RESTORATION ON SLOPES OF 3:1 OR GREATER.
- 15. CONTRACTOR SHALL USE STREET SMEEPER AS REQUIRED TO MINIMIZE DUST AND SOIL ON ROADWAYS. IF DUST IN NON-ROADWAY AREAS BECOMES A PROBLEM, CONTRACTOR TO APPLY WATER TO CONSTRUCTION RIGHT-OF-WAY TO PROVIDE DUST CONTROL.
- 16. TEMPORARY CONSTRUCTION ENTRANCES (ROCK AND GEOTEXTILE FABRIC) TO BE INSTALLED FOR ACCESS FROM PUBLIC ROADS TO TEMPORARY CONSTRUCTION WORK AREAS ADJACENT TO PUBLIC ROADS (SEE TEMPORARY CONSTRUCTION ENTRANCE DETAIL). CULVERT PIPES TO BE INSTALLED WHERE NECESSARY FOR ACCESS ACROSS DITCHES OR SWALES, TO MAINTAIN EXISTING DRAINAGE PATTERNS.
- 17. UNLESS NOTED IN THE CONSTRUCTION LINE LIST, TOPSOIL SHALL BE STRIPPED AND SEGREGATED PRIOR TO TRENCHING IN AGRICULTURAL AREAS (MAX. DEPTH 12 INCHES). AFTER COMPLETION OF SUBSOIL BACKFILL, TOPSOIL TO BE RETURNED TO REQUIRED AREAS AND GRADED. TOPSOIL SHALL ALSO BE SEGREGATED IN ALL TEMPORARY CONSTRUCTION WORKSPACE AREAS IN AGRICULTURAL AREAS, TOPSOIL SHALL ALSO BE SEGREGATED IN ALL AREAS WHERE THE PROPOSED PIPELINE IS INSTALLED IN UNPAYED ROAD RIGHT OF WAY AREAS. IF TOPSOIL IS NOT SEGREGATED IN THESE AREAS, THEN CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING NEW TOPSOIL TO ACTUAL DEPTH OF EXISTING TOPSOIL (MIN. 6" DEPTH/MAX. 12" DEPTH).

STABILIZATION NOTES

- I. FOR ROADWAY AREAS REFER TO DELDOT NOTES ON SHEET 6 OF 16.
- 2. FOR NON-ROADWAY AREAS, REFER TO NOTES AND DETAILS ON RESTORATION SEEDING AND MULCHING. RESTORATION IN NON-ROADWAY AREAS (UPLANDS AND WETLANDS) WILL BE PERFORMED WITHIN 7 DAYS OF BACKFILL. IN STREAM AREAS, RESTORATION WILL BE PERFORMED WITHIN ONE TO TWO DAYS OF PIPELINE INSTALLATION AND BACKFILL. ALL DISTURBED SOIL SHALL BE STABILIZED AS THE CONTRACTOR PROGRESSES WITHIN 5 WORKING DAYS OF DISTURBANCE.

CONSTRUCTION NOTES AND SEQUENCING

NOTIFICATION:

THE NEW CASTLE CONSERVATION DISTRICT SEDIMENT AND STORMWATER MANAGEMENT PROGRAM MUST BE NOTIFIED IN WRITING FIVE (5) DAYS PRIOR TO COMMENCEMENT OF CONSTRUCTION. FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLAN. PRIOR TO ANY CLEARING, INSTALLATION OF SEDIMENT CONTROL MEASURES OR GRADING, A PRE-CONSTRUCTION MEETING MUST BE SCHEDULED AND CONDUCTED WITH THE AGENCY CONSTRUCTION SITE REVIEWER. THE LANDOWNER/DEVELOPER, CONTRACTOR, AND CERTIFIED CONSTRUCTION REVIEWER ARE REQUIRED TO BE IN ATTENDANCE AT THE PRE-CONSTRUCTION MEETING; THE DESIGNER IS RECOMMENDED TO ATTEND.

WORK AREAS:

CONSTRUCTION WORK AREAS TO BE CONFINED TO THE LIMITS SHOWN ON THE DRAWINGS. CONTRACTOR SHALL USE MATTING WHEN WORKING OVER EXISTING EASTERN SHORE FACILITIES AT NO ADDITIONAL COST TO EASTERN SHORE. CONTRACTOR SHALL TEST HOLE AND VERIFY EXISTING PIPELINE DEPTH PRIOR TO WORKING OVER EXISTING FACILITIES. CONTRACTOR SHALL PROVIDE BEARING CALCULATIONS TO DETERMINE NEED FOR MATTING OR LOW PRESSURE GROUND TRACKING EQUIPMENT AND CONFIRM WITH EASTERN SHORE THE METHODOLOGY PRIOR TO WORKING IN THAT AREA. ANY DAMAGE TO EXISTING EASTERN SHORE FACILITIES WILL BE REPAIRED AND/OR REPLACED AT THE CONTRACTORS EXPENSE.

MATERIALS:

All PIPELINE COATING MATERIAL SHALL BE PROVIDED, STORED AND APPLIED BY CONTRACTOR PER ESNG CONSTRUCTION STANDARDS MANUAL AND APPROVED MATERIAL LIST.

EROSION AND SEDIMENTATION CONTROLS:

ALL PERIMETER CONTROLS ARE TO BE REVIEWED BY THE AGENCY CONSTRUCTION SITE REVIEWER AND APPROVED PRIOR TO PROCEEDING WITH FURTHER SITE DISTURBANCE OR CONSTRUCTION. THE CONTRACTOR SHALL AT ALL TIMES PROTECT AGAINST SEDIMENT OR DEBRIS LADEN RUNOFF OR WIND FROM LEAVING THE SITE. PERIMETER CONTROLS SHOULD BE CHECKED DAILY AND ADJUSTED AND/OR REPAIRED TO FULLY CONTAIN AND CONTROL SEDIMENTATION ON THE SITE. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED HALF OF THE EFFECTIVE CAPACITY OF THE CONTROL. IN ADDITION, THE CONTRACTOR MAY NEED TO ADJUST OR REPAIR MEASURES IN TIMES OF ADVERSE WEATHER CONDITIONS, OR AS DIRECTED BY THE AGENCY CONSTRUCTION SITE REVIEWER. EROSION AND SEDIMENTATION CONTROL BARRIERS (SILT FENCE) WILL BE INSTALLED AND MAINTAINED PRIOR TO EARTH DISTURBANCE TO AVOID/MINIMIZE IMPACT TO WETLANDS AND WATERBODIES. EROSION/SEDIMENT CONTROL BARRIERS ARE SHOWN ON THE DRAWINGS. ACTUAL SILT FENCE LOCATIONS SHALL BE FIELD DETERMINED BASED ON SITE CONDITIONS, AND SHALL BE AGREED TO/APPROVED BY ESNG CONSTRUCTION INSPECTION REPRESENTATIVES. THESE BARRIERS WILL REMAIN IN PLACE UNTIL REVEGETATION AND RESTORATION ARE DEEMED SUCCESSFUL (SEE GENERAL ENVIRONMENTAL NOTES THIS SHEET). EROSION AND SEDIMENT CONTROL DEVICES SHOULD BE REMOVED ONLY AFTER WORK IN AN AREA HAS BEEN COMPLETED AND STABILIZED, WITH WRITTEN APPROVAL FROM THE AGENCY CONSTRUCTION SITE REVIEWER.

CLEARING OF VEGETATION:

TREE CLEARING WILL BE LIMITED TO THE MINIMUM NEEDED TO CONSTRUCT THE PIPELINE. ALL WOODED AREAS CLEARED FOR TEMPORARY WORK SPACE WILL BE ALLOWED TO NATURALLY REGENERATE.

PIPELINE INSTALLATIONS BENEATH ROADWAY CULVERTS:

THE HDD CROSSINGS ARE PROPOSED TO BE PERFORMED WITHIN THE ROAD R.O.W. OR PERMANENT EASEMENT AND WILL BE DESIGNED TO MEET ALL REQUIREMENTS AND SPECIFICATIONS OF DELAWARE DEPARTMENT OF TRANSPORTATION (DELDOT). THE DESIGNS WILL BE PERFORMED TO ENSURE THE COMPLETE STRUCTURAL INTEGRITY OF THE ROADWAY AND ADJACENT AREAS, WHILE ALSO MAINTAINING SUFFICIENT CLEARANCE UNDER UTILITIES, CULVERT STRUCTURES AND FOOTINGS. EROSION/SEDIMENT CONTROLS WILL BE INSTALLED AND MAINTAINED THROUGHOUT CONSTRUCTION TO ENSURE THAT NO SEDIMENTATION OCCURS TO WETLANDS OR WATERBODIES OUTSIDE THE ROADWAY. UPON COMPLETION OF CONSTRUCTION, ALL PITS AND OTHER AREAS WILL BE BACKFILLED AND COMPACTED TO ENSURE THE INTEGRITY OF THE STRUCTURES AND ROADWAY.

TRENCH EXCAVATION AND BACKFILLING:

THE TRENCH REQUIRED FOR THE PIPELINE INSTALLATION WILL BE EXCAVATED TO ENSURE THE REQUIRED DEPTH OF COVER. IN GENERAL, A MINIMUM OF 4 FEET OF COVER WILL BE PLACED OVER THE PIPELINE, BACKFILLING WITH COMPACTED MATERIAL MEETING THE REQUIREMENTS OF DELDOT. IN PAYED AREAS TRENCHLINE IS TO BE SAWCUT, AND PAYEMENT WILL BE DISPOSED OF AT AN APPROVED FACILITY. UPON COMPLETION OF THE PIPELINE INSTALLATION ACTIVITIES, THE GROUND SURFACE WILL BE GRADED TO PRE-CONSTRUCTION CONDITIONS. TRENCH WATER OR OTHER FORMS OF TURBID WATER WILL NOT BE DIRECTLY DISCHARGED ONTO EXPOSED SOIL SURFACES OR INTO ANY WETLAND OR STREAMS. GROUNDWATER SEEPAGE WILL BE PUMPED OUT OF THE TRENCH AND DIRECTED TO A PRE-MANUFACTURED FILTER BAG (OR EQUIVALENT) SIZED FOR THE EXPECTED VOLUME OF EFFLUENT, WHICH WILL BE PLACED IN AN UPLAND AREA, SURROUNDED BY A HAY BALE ENCLOSURE IF NECESSARY. SILT AND SEDIMENT WILL COLLECT IN THE FILTER BAG WHILE ALLOWING NON-TURBID WATER TO LEACH OUT AND INFILTRATE INTO THE GROUND. THE COLLECTED SILT, SEDIMENT, AND USED FILTER BAG WILL BE PROPERLY DISPOSED OFF-SITE.

HORIZONTAL DIRECTIONAL DRILLING:

CONTRACTOR SHALL UTILIZE A BENDING MACHINE PER COMPANY STANDARDS TO ACHIEVE PROPER COVER AND BREAK-OVER AT HORIZONTAL DIRECTIONAL DRILL ENTRY AND EXIT LOCATIONS. ADDITIONAL FITTINGS SHALL BE UTILIZED AT CONTRACTOR'S EXPENSE.

HYDROSTATIC TESTING OF THE PROPOSED PIPELINE:

IN COMPLIANCE WITH U.S. DEPARTMENT OF TRANSPORTATION PIPELINE SAFETY AND INTEGRITY REGULATIONS, EASTERN SHORE NATURAL GAS WILL HYDROSTATICALLY TEST THE PROPOSED NATURAL GAS PIPELINE PRIOR TO PLACING THE PROPOSED PIPELINE IN SERVICE. THE SOURCE OF WATER FOR THE HYDROSTATIC TEST WILL BE DETERMINED BEFORE THE TEST.

HYDROSTATIC PRESSURE TESTING WATER THAT IS RELEASED TO AN UPLAND SILT FENCE AND HAY BALE CONTAINMENT AREA WILL BE DONE USING WORKSPACE IN AN UPLAND AREA AT THE BEGINNING OR ENDING LOCATION OF EACH SEGMENT (NO TREE CLEARING WILL BE INVOLVED IN THE HYDROSTATIC TEST WATER DISCHARGE). A SPLASH PLATE WILL BE USED TO DIFFUSE THE IMPACT OF THE RELEASED WATER, EASTERN SHORE NATURAL GAS WILL ENSURE THAT NO EROSION OR WATERBODY/WETLAND SEDIMENTATION OCCURS FROM THE TEST WATER RELEASE ACTIVITIES. THE RELEASE RATE WILL BE 500 - 1,500 GALLONS PER MINUTE, OR AT A RATE SO AS NOT TO CAUSE ANY SCOURING.

PERMIT TERMINATION:

THE TERMINATION OF THE CONSTRUCTION GENERAL PERMIT WILL REQUIRE SUBMISSION AND ACCEPTANCE OF THE POST CONSTRUCTION VERIFICATION DOCUMENTS, INCLUDING FINAL STABILIZATION THROUGHOUT THE SITE, ALL ELEMENTS OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN IMPLEMENTED, AND ACCEPTANCE OF THE FINAL OPERATION AND MAINTENANCE PLAN.

GENERAL:

- I. THE CONTRACTOR SHALL CONTACT MISS UTILITY OF DELMARVA AT I-800-282-8555 FOR UTILITY LOCATIONS WITHIN AND SURROUNDING CONSTRUCTION AREAS NOT LESS THAN 3 DAYS BEFORE PERFORMING ANY EXCAVATION.
- 2. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER OR THE ARCHITECT/ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO ACCURACY. COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION SHOWN, THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND TYPE OF MATERIALS OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH UTILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE OWNER OF HIS OPERATIONAL PLANS. IN THE EVENT OF AN UNEXPECTED UTILITY INTERFERENCE DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE.
- 3 PRIOR TO PERFORMING ANY EXCAVATION GREATER THAN 6 INCHES. THE CONTRACTOR SHALL COORDINATE WITH SOUTH DISTRICT PUBLIC WORKS AND ALL PRIVATE UTILITY COMPANIES TO DETERMINE THE LOCATION OF UNDERGROUND UTILITY LINES, THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH ALL ORGANIZATIONS THAT CONTROL EXISTING UNDERGROUND UTILITIES IN THE CONSTRUCTION AREA OR WOULD BE AFFECTED BY CONSTRUCTION WORK AROUND THE EXISTING
- 4. THE CONTRACTOR SHALL NOT START EXCAVATION UNTIL ALL UTILITY LINE LOCATIONS HAVE BEEN STAKED OR OTHERWISE CLEARLY MARKED AND DOCUMENTATION FURNISHED TO THE OWNER. ALL MARKINGS SHALL BE CONSIDERED APPROXIMATE, AND UTILITIES OTHER THAN THOSE SHOWN SHALL BE CONSIDERED TO EXIST
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DEFINITE LOCATION OF EACH UTILITY WITHIN THE WORK AREA, CARE SHOULD BE EXERCISED DURING EXCAVATION WORK TO AVOID DAMAGING OR DISRUPTING UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING (AT CONTRACTOR'S EXPENSE) DAMAGE TO ANY UTILITY CAUSED BY THE CONTRACTOR'S WORK.
- 6. WHERE EXISTING UNDERGROUND UTILITIES OR OTHER CONSTRUCTION ARE EXPECTED TO BE IN PROXIMITY TO PROPOSED CONSTRUCTION. OR WHEN APPROACHING EXISTING UTILITIES OR STRUCTURES FOR CONNECTIONS. THE CONTRACTOR SHALL DIG TEST PITS TO DETERMINE THE EXACT LOCATION AND INVERTS OF THE EXISTING UTILITY TO ALLOW FOR POSSIBLE CHANGES TO THE PROPOSED UTILITY IN LINE AND/OR GRADE. THE CONTRACTOR SHALL ALSO DIG TEST PITS IN THE LOCATION OF THE PROPOSED CONNECTIONS TO EXISTING UTILITIES AND SHALL MAKE ALL MEASUREMENTS NECESSARY TO ENSURE PROPER CONNECTION. ANY NECESSARY CHANGES IN LINE OR GRADE OF WORK CAUSED BY FAILURE TO TAKE SUCH PRECAUTIONS SHALL BE AT THE EXPENSE OF THE CONTRACTOR.
- 7. WHEN IT IS NECESSARY TO EXCAVATE NEAR OR INTERFERE WITH ANY SEWER LINE, WATER SERVICES, DRAIN PIPE, CATCH BASIN, CULVERT, OR OTHER STRUCTURES, THE CONTRACTOR SHALL MAINTAIN THE SAME IN WORKING ORDER AND SHALL REPAIR AND MAKE GOOD ANY DAMAGE DONE DURING THE PROGRESS OF THE WORK.
- 8. WHERE EXISTING UTILITIES CROSS THE TRENCH EXCAVATION, THEY SHALL BE ADEQUATELY SUPPORTED AND PROTECTED FROM DAMAGE DUE TO CONSTRUCTION. ALL METHODS FOR SUPPORTING AND MAINTAINING THESE UTILITIES SHALL BE SUBJECT TO REVIEW BY OWNER. CARE SHALL BE TAKEN TO ENSURE THAT THE EXISTING UTILITY GRADES AND ALIGNMENT ARE MAINTAINED AND THE PIPE JOINTS ARE NOT DISTURBED. BACKFILL SHALL BE CAREFULLY PLACED AND TAMPED TO PREVENT DAMAGE OR FUTURE SETTLEMENT. ANY DAMAGE OR MISALIGNMENT OF THE UTILITIES DUE TO CONSTRUCTION OR SETTLEMENT SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S EXPENSE.
- 9. ANY UNPROTECTED CABLE (DIRECT BURIED) ENCOUNTERED THAT IS VERIFIED AS NOT ABANDONED IN PLACE SHALL BE PROTECTED. THE UTILITY OWNER MAY DIRECT THE CABLE BE PLACED IN SPLIT DUCT OF APPROPRIATE SIZE AND CONCRETE ENCASED THROUGH THE AREA OF CONSTRUCTION. CONTRACTOR SHALL TAKE ALL REASONABLE MEASURES TO AVOID HAVING TO CUT AND SPLICE DIRECT BURIED CABLE. THE CONTRACTOR SHALL NOTE SPLIT DUCT PORTIONS ON AS-BUILTS.
- 10. SHORING MAY BE REQUIRED TO PROTECT THE INTEGRITY OF THE ROADWAY IF TRENCH ENCROACHES WITHIN 5' OF PAVEMENT OR IF UNDERMINING OCCURS.

CONSTRUCTION SCHEDULE

CONSTRUCTION IS SCHEDULED TO BEGIN IN FALL 2025. CONSTRUCTION IS SCHEDULED TO BE COMPLETED IN WINTER 2026, IN ACCORDANCE WITH ESNG SCHEDULE. WORK WILL CONSIST OF THE FOLLOWING SEQUENTIAL OR CONCURRENT ACTIVITIES:

- I. THE NEW CASTLE CONSERVATION DISTRICT SEDIMENT AND STORMWATER MANAGEMENT PROGRAM MUST BE NOTIFIED IN WRITING FIVE (5) DAYS PRIOR TO COMMENCEMENT OF CONSTRUCTION, FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLAN.
- 2. PRIOR TO ANY CLEARING, INSTALLATION OF SEDIMENT CONTROL MEASURE OR GRADING, A PRE-CONSTRUCTION MEETING SHALL BE SCHEDULED AND CONDUCTED WITH THE AGENCY CONSTRUCTION SITE REVIEWER. THE LANDOWNER / DEVELOPER, CONTRACTOR AND CERTIFIED CONSTRUCTION REVIEWER ARE REQUIRED TO BE IN ATTENDANCE AT THE PRE-CONSTRUCTION MEETING; THE DESIGNER IS RECOMMENDED TO ATTEND.
- 3. ALL PERIMETER CONTROLS ARE TO BE REVIEWED BY THE AGENCY CONSTRUCTION SITE REVIEWER AND APPROVED PRIOR TO PROCEEDING WITH FURTHER SITE DISTURBANCE OR CONSTRUCTION.
- 4. EROSION AND SEDIMENTATION CONTROL STRUCTURES WILL BE INSTALLED AND MAINTAINED AS NECESSARY (SEE ENVIRONMENTAL NOTES).
- 5. TOPSOIL STRIPPING AND SEGREGATION WILL BE PERFORMED IN REQUIRED AREAS. 6. CLEARING, GRADING AND GRUBBING WILL BE PERFORMED IN NON-ROADWAY AREAS, AS APPLICABLE.

NO. DATE

- TRENCHING/DITCHING WILL BE PERFORMED TO ENSURE REQUIRED DEPTH OF COVER OVER PIPELINE PER THE DRAWINGS, (SUBSOIL WILL BE STOCKPILED WITHIN THE WORK AREA SEPARATE FROM TOPSOIL AS APPLICABLE).
- 8. IN PAVED AREAS TRENCHLINE IS TO BE SAWCUT, AND PAVEMENT WILL BE DISPOSED OF AT AN APPROVED FACILITY. 9. BENDING, WELDING, AND COATING OF THE PIPELINE ALONG THE EDGE OF THE TRENCH.
- IO. LOMERING THE PIPE INTO THE DITCH, PADDING, BACKFILL AND COMPACTION INCLUDING ROAD SUB-BASE IN PAVED ROADWAY AREAS), AS WELL AS CLEANUP AND RESTORATION. II. FILLING THE PIPE WITH WATER, HYDROSTATIC PRESSURE TESTING OF THE PIPE AND DEWATERING INTO THE UPLAND AREA.
- 12. FINAL TIE-IN OF THE PIPELINE AT BOTH ENDS, FINAL CLEANUP AND GRADING, ROAD RESURFACING WHERE APPLICABLE, AND SEEDING AND MULCHING WHERE APPLICABLE. SEE "STABILIZATION NOTES" FOR REQUIREMENTS RELATED TO STABILIZATION OF ROADWAY AND NON-ROADWAY AREAS.
- 13. EROSION/SEDIMENT CONTROL BARRIERS SHALL REMAIN IN PLACE UNTIL FINAL REVEGETATION AND RESTORATION ARE DEEMED SUCCESSFUL AND AUTHORIZED FOR REMOVAL BY THE NEW CASTLE CONSERVATION DISTRICT SEDIMENT & STORMWATER PROGRAM.
- 14. THE TERMINATION OF THE CONSTRUCTION GENERAL PERMIT WILL REQUIRE SUBMISSION AND ACCEPTANCE OF THE POST CONSTRUCTION VERIFICATION DOCUMENTS, INCLUDING FINAL STABILIZATION THROUGHOUT THE SITE, ALL ELEMENTS OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN IMPLEMENTED, AND ACCEPTANCE OF THE FINAL OPERATION AND MAINTENANCE PLAN.

LEGEND PROPOSED PIPELINE 3+00 STATION LABELS M.P. MILE MARKER PERMANENT EASEMENT _____ ___ _ _ TWS ___ _ TEMPORARY WORKSPACE (TWS) LIMITS OF DISTURBANCE ____LOD ____LOD ____ LIMITS OF DISTURBANCE / TWS APPROXIMATE LOCATION OF PROPOSED EROSION/SEDIMENT CONTROL STRUCTURES — SF — SF — SF — SILT FENCE - TO BE INSTALLED AS REQUIRED (SEE ENVIRONMENTAL NOTES AND PLAN & PROFILE SHEETS) PROPERTY LINE RIGHT-OF-WAY LINE EXISTING CONTOUR (MAJOR) — — — -40- — — EXISTING CONTOUR (MINOR) EXISTING EDGE OF PAVEMENT _ _ _ _ _ _ _ _ _ _ _ EXISTING TREELINE EXISTING GUIDERAIL . 0 0 0 0 EXISTING CHAINLINK FENCE __x__x__x__x__x___x___ EXISTING STORM SEWER EXISTING WATER LINE _____W____W___ EXISTING SANITARY SEWER ------ SAN ------- SAN ------EXISTING E.S.N.G. NATURAL GAS PIPELINE ----- ESNG-G-----EXISTING GAS PIPELINE (OTHERS) ——— UG ——— UG ——— OVERHEAD ELECTRIC TRANSMISSION LINE ----- OHE------ OHE-----WATERS OF U.S. ____US___US___ METLAND AREA EXISTING GAS METER EXISTING WATER VALVE EXISTING GAS VALVE EXISTING ELECTRIC TRANSFORMER ☐ Elec. Transf. \circ EXISTING UTILITY MANHOLE EXISTING CABLE/TELEPHONE PEDESTAL EXISTING DRAINAGE STRUCTURE EXISTING LIGHT STANDARD EXISTING UTILITY POLE EXISTING FIRE HYDRANT EXISTING WELL (PRIVATE) EXISTING MAILBOX EXISTING STREET SIGN ______ EXISTING BUILDING/STRUCTURE _____ PROPOSED H.D.D. ENTRY / EXIT LOCATION

COORDINATE SYSTEM AND VERTICAL DATUM


HORIZONTAL COORDINATE SYSTEM:

DELAWARE STATE PLANE, NORTH AMERICAN DATUM OF 1983 (NAD 83),

YERTICAL DATUM:

U.S. SURVEY FOOT

NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88), U.S. SURVEY FOOT



EROSION & SEDIMENT CONTROL GENERAL NOTES

REVISIONS MORRIS & RITCHIE ASSOCIATES, INC ENGINEERS, PLANNERS, SURVEYORS AND DESCRIPTION LANDSCAPE ARCHITECTS 111 RUTHAR DRIVE NEWARK, DE 19711 (302) 326-2200

© 2025 MORRIS & RITCHIE ASSOCIATES INC

500 ENERGY LANE, SUITE 200 DOVER, DE 19901 TELEPHONE (302) 734-6710 - FAX (302) 734-6745 MRAGTA.COM

ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE ESNG PROJ. CODE:

8/19/2025 MRA PROJECT NO: 23289 SCALE: N/A DESIGN/CHECK BY: JTH/CWB SHEET: 2 OF 16

8" PROPOSED PIPELINE

NICK HAMMOND, ENGINEER II EASTERN SHORE NATURAL GAS 500 ENERGY LANE, SUITE 200 DOVER, DE 19901

EMAIL - NHAMMONDOCHPK.COM


"I, NICK HAMMOND, CERTIFY THAT ALL LAND CLEARING, CONSTRUCTION AND DEVELOPMENT SHALL BE DONE PURSUANT TO THE APPROVED PLAN AND THAT RESPONSIBLE PERSONNEL (I.E., BLUE CARD HOLDER) INVOLVED IN THE LAND DISTURBANCE WILL HAVE A CERTIFICATION OF TRAINING PRIOR TO INITIATION OF THE PROJECT, AT A DIREC SPONSORED OR APPROVED TRAINING COURSE FOR THE CONTROL OF

EROSION AND SEDIMENT DURING CONSTRUCTION, IN ADDITION, I GRANT THE DNREC SEDIMENT AND STORMWATER PROGRAM AND/OR THE RELEVANT DELEGATED AGENCY THE RIGHT TO CONDUCT ON-SITE REVIEWS, AND I UNDERSTAND MY RESPONSIBILITIES UNDER THE NPDES


PHONE - (302) 593-1929

CONSTRUCTION GENERAL PERMIT, AS REFERENCED ON THIS COVERSHEET."

OWNER'S CERTIFICATION:



Standard Detail & Specifications Silt Fence



Method for joining continuous sections

Construction Notes:

- 1. Geosynthetic fabric to be fastened securely to fence posts with wire ties or staples.
- 2. When two sections of filter cloth adjoin each other they shall be overlapped by six
- 3. Maintenance shall be performed as needed and material removed when "bulges" develop in the silt fence


Materials:


- Stakes: Steel (either T or U) or 2" x 2" hardwood
- 2. Geosynthetic Fabric: Type GD-I
- 3. Reinforcing strip: Wooden lath or plastic strip

| ource: | Symbol: | Detail No. |
|---|-----------|---|
| Adapted from MD Stds. & Specs. for ESC | —— SF ——— | DE-ESC-3.1.2.1 Sheet 2 of 2 Effective July 2023 |

Standard Detail & Specifications

Stabilized Construction Entrance






Section A-A (Std.)

Source: Symbol: SCE Adapted from VA ESC Handbook

Detail No. **DE-ESC-3.4.7** Sheet 1 of 2 Effective July 2023

Standard Detail & Specifications

Stabilized Construction Entrance



Metal bars set in reinforced conc. Provide space for drainage (traffic bearing grates, timber mats or other approved equiv. may be substituted)

Section A-A (Opt.)

Construction Notes:

1. Stone size - Use DE #3 stone.

Source:

- 2. Length As required, but not less than 50 feet (except on a single residence lot where a 30 foot minimum length would apply).
- 3. Thickness Not less than size (6) inches.
- 4. Width Ten (10) foot minimum, but not less than the full width at points where ingress or egress occurs.
- 5. Geotextile Type GS-I; placed over the entire area prior to placing of stone.
- 6. Surface Water All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 5:1 slopes will be permitted.
- Maintenance The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights-of-way must be removed immediately.
- Washing Vehicle wheels shall be cleaned to remove sediment prior to entrance onto public rightsof-way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device.
- 9. Inspection Periodic inspection and needed maintenance shall be provided after each rain.


Adapted from VA ESC Handbook

SCE

Detail No. DE-ESC-3.4.7 Sheet 2 of 2 Effective July 2023

Standard Detail & Specifications

Compost Filter Log



| Source: | Symbol: | Detail No. |
|--|-----------|---|
| Adapted from MD Stds & Specs for ESC & Filtrexx™ International | —— CFL —— | DE-ESC-3.1.7 Sheet 1 of 2 Effective July 2023 |

NOTE: Manufacturer's recommendations supersede any

installation details shown for this practice

Standard Detail & Specifications

Compost Filter Log

Construction Notes:

- . Prior to installation, clear bedding area of obstructions including rocks or debris larger than 1 inch and fill in any sharp depression areas.
- 2. If socks are prepared on-site, fill the sock fabric using a pneumatic blower so that the logs are rigid and do not deform. Terminate at the desired length.
- 3. For trenched applications, excavate 2 to 4 inches below grade along the width and length of the compost filter log.
- 4. Install the compost filter logs perpendicular to the flow direction and parallel to the slope with the beginning and end of the installation pointing up the slope a minimum of 1 foot elevation difference. On sites where this is not possible, upturn at a minimum length of 10' at a 30 degree angle to prevent runoff bypass.
- 5. For untrenched applications, blow or hand pack soil, mulch, or compost on the upslope side of the log, filling the bottom void area.
- 6. Stake the filled log every 10 feet maximum through the center of the sock for trenched applications, or every 8 feet for untrenched. The stake shall be a 2" by 2" hardwood. It should extend 12" below grade and protrude at least 3" above the top of the sock. If located on a slope greater than 8:1, the stake shall be angled downslope at a 45 degree angle to prevent the force of the water from dislodging to log.
- When the length of the compost filter log needed exceeds the available compost filter sock length, the next sock shall be overlapped a minimum of 12" before being filled, and a stake placed through both socks at the overlap.
- 8. Remove accumulated sediment when it has reached half of the effective height of the log.
- 9. Inspect weekly and after rain event. If sock is degrading or the sock is failing, vegetate to secure the compost, replace the log, or reinforce with an additional log. If the log has been crushed due to construction equipment, it can be "fluffed" back to its effective height. If the effective height can no longer be restored, the log shall be replaced or reinforced with an additional compost filter log.

| Source: | Symbol: | Detail No. |
|--|-----------|---|
| Adapted from MD Stds & Specs for ESC & Filtrexx™ International | —— CFL —— | DE-ESC-3.1.7 Sheet 2 of 2 Effective July 2023 |

Standard Detail & Specifications

Topsoiling

Construction Notes:

1. Site Preparation (Where Topsoil is to be added)

Note: When topsoiling, maintain needed erosion and sediment control practices such as diversions, grade stabilization structures, berms, dikes, waterways and sediment basins.

- a. Grading Grades on the areas to be topsoiled which have been previously established shall be maintained.
- b. Liming Where the topsoil is either highly acid or composed of heavy clays, ground limestone shall be spread at the rate of 4-8 tons/acre (200-400 pounds per 1,000 square feet). Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures.
- c. Tilling After the areas to be topsoiled have been brought to grade, and immediately prior to dumping and spreading the topsoil, the subgrade shall be loosened by discing or by scarifying to a depth of a least 3 inches to permit bonding of the topsoil to the subsoil. Pack by passing a bulldozer up and down over the entire surface area of the slope to create horizontal erosion check slots to prevent topsoil from sliding down the slope.
- 2. Topsoil Material and Application

NO. DATE

Note: Topsoil salvaged from the existing site may often be used but it should meet the same standards as set forth in these specifications. The depth of topsoil to be salvaged shall be no more than the depth described as a representative profile for that particular soil type as described in the soil survey published by USDA-SCS in cooperation with Delaware Agricultural Experimental Station.

| Source: | Symbol: | Detail No. |
|-------------|---------|---------------------|
| | | DE-ESC-3.4.1 |
| USDA - NRCS | | Sheet 1 of 2 |
| | | Effective July 2023 |
| | | |

Standard Detail & Specifications Topsoiling

Construction Notes (cont.)

a. Materials - Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand or other soil as approved by an agronomist or soil scientist. It shall not have a mixture of contrasting textured subsoil and contain no more than 5 percent by volume of cinders, stones, slag, coarse fragment, gravel, sticks, roots, trash or other extraneous materials larger than 1-1/2 inches in diameter. Topsoil must be free of plants or plant parts of bermudagrass, quackgrass, Johnsongrass, nutsedge, poison ivy, thistles, or others as specified. All topsoil shall be tested by a reputable laboratory for organic matter content, pH and soluble salts. A pH of 6.0 to 7.5 and an organic content of not less than 1.5 percent by weight is required. If pH value is less than 6.0 lime shall be applied and incorporated with the topsoil to adjust the pH to 6.5 or higher. Topsoil containing soluble salts greater than 500 parts per million shall not be used.

Note: No sod or seed shall be placed on soil which has been treated with soil sterilant or chemicals used for weed control until sufficient time has elapsed to permit dissipation of toxic materials.

b. Grading - The topsoil shall be uniformly distributed and compacted to a minimum of four (4) inches. Spreading shall be performed in such a manner that sodding or seeding can proceed with a minimum of additional soil preparation and tillage. Any irregularities in the surface resulting from topsoiling or other operations shall be corrected in order to prevent the formation of depressions or water pockets. Topsoil shall not be placed while in a frozen or muddy condition, when the subgrade is excessively wet, or in a condition that may otherwise be detrimental to proper grading and seedbed preparation.

Note: Topsoil substitutes or amendments as approved by a qualified agronomist or soil scientist, may be used in lieu of natural topsoil. Compost material used to improve the percentage of organic matter shall be provided by a certified supplier.

Compost amendments that are intended to meet specific post-construction stormwater management goals shall further meet the requirements of Appendix 3.06.2 Post Construction Stormwater Management BMP Standards and Specifications, Section 14.0 Soil Amend-

Symbol: Detail No. Source: **DE-ESC-3.4.1 USDA - NRCS** Sheet 2 of 2 Effective July 2023

> **EROSION & SEDIMENT** CONTROL DETAILS

8" PROPOSED PIPELINE ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE

| 11 - 11 | OASTEL OO | <u> </u> | |
|------------------|-----------|----------|-----------|
| ESNG PROJ. CODE: | | DATE: | 8/19/2025 |
| MRA PROJECT NO: | 23289 | SCALE: | N/A |
| DESIGN/CHECK BY: | JTH/CWB | SHEET: | 3 OF 16 |

REVISIONS MORRIS & RITCHIE ASSOCIATES, INC. DESCRIPTION ENGINEERS, PLANNERS, SURVEYORS ÁND EASTERN SHORE LANDSCAPE ARCHITECTS 111 RUTHAR DRIVE NEWARK, DE 19711 (302) 326-2200 500 ENERGY LANE, SUITE 200 DOVER, DE 19901 TELEPHONE (302) 734-6710 - FAX (302) 734-6745 MRAGTA.COM

© 2025 MORRIS & RITCHIE ASSOCIATES IN

Construction Site Pollution Prevention

Delaware NPDES Discharge Permit General Permit for Discharge of Stormwater from Construction Activities

((Project Name))

((NOI Permit Number))

((Agency Plan Approval ID))

((Contact Name & Number for Additional Site Information))

((Contact Name & Number to Obtain Copy of Approved Plan))

If you observe indicators of stormwater pollutants in the discharge or in the receiving waterbody, call the DNREC Spill Notification 24 HR Hotline at

1-800-662-8802

Example Construction General Permit (CGP) Signage

NOTES:

- 1. Minimum sign size 2' x 2'
- 2. Minimum text size 1"
- 3. Sign must be posted at a safe, publicly accessible location close to construction site
- 4. Sign must be visible from the public road nearest the active construction site
 5. Signs posted within a DelDOT or other public road right-of-way (ROW) must be in accordance
- with all local and/or State requirements in regards to safety, location, orientation, etc.

| Source: | Symbol: | Detail No. |
|-----------------------|---------|---------------------|
| | | DE-ESC-3.6.1 |
| Delaware ESC Handbook | | Sheet 1 of 4 |
| | | Effective July 2023 |

Standard Detail & Specifications

Construction Site Pollution Prevention

Notes:

The Construction Site Pollution Prevention Plan includes the following elements:

- 1. Material Inventory
- Document the storage and use of the following materials:
- a. Concrete
- b. Detergents
- c. Paints (enamel and latex)
- d. Cleaning solvents
- e. Pesticides
- f. Wood scraps
- g. Fertilizers
- h. Petroleum based products
- 2. Good housekeeping practicesa. Store only enough product required to do the job.
- b. Store all materials in a neat, orderly manner in their original labeled containers and
- c. Do not mix different substances.
- d. When possible, use all of a product prior to disposal of the container.
- e. Manufacturers' instructions for disposal should be strictly adhered to.
- f. Designate someone to inspect all BMPs daily.

3. Waste management practices

- Collect and store all waste materials in securely lidded dumpsters in a location that does not drain to a waterbody.
- b. Salvage and/or recycle waste materials whenever possible.
- c. The dumpsters shall be emptied a minimum of twice per week, or more if necessary. The licensed trash hauler is responsible for cleaning out dumpsters.

| ource: | Symbol: | Detail No. |
|---|---------|-------------------------------------|
| Adapted from USEPA Pub. 840-B-92-002 | | DE-ESC-3.6.1 Sheet 2 of 4 |
| | | Effective July 2023 |

Standard Detail & Specifications

Construction Site Pollution Prevention

Notes (cont.)

- d. Dispose of all trash in accordance with all applicable Delaware laws.
- e. Littering is strictly prohibited. Trash cans should be placed at all lunch spots and recycle bins should be placed near the construction trailer.
- f. If fertilizer bags can not be stored in a weather-proof location, they should be kept on a pallet and covered with plastic sheeting which is overlapped and anchored.

4. Equipment maintenance practices

- a. If possible, equipment should be taken to off-site commercial facilities for washing and
- b. If performed on-site, wash vehicles with high-pressure water spray without detergents in an area contained by an impervious berm.
- c. Use drip pans for all equipment maintenance.
- d. Inspect equipment for leaks on a daily basis.
- e. Direct washout from concrete trucks into a temporary pit for hardening and proper disposal.
- f. Equip fuel nozzles with automatic shut-off valves.
- g. Dispose of all used products such as oil, antifreeze, solvents and tires in accordance with manufacturers' recommendations and local, state and federal laws and regulations.

5. Spill prevention practices

ဍ ပံ

NO. DATE

- a. Identify potential spill areas and contain them in covered areas with no connection to the storm drain system.
- b. Post warning signs in hazardous material storage areas.
- c. Perform preventive maintenance on all tanks, valves, pumps, pipes and other equipment as necessary.
- d. Prioritize low or non-toxic substances for use.

| Source: | Symbol: | Detail No. |
|--------------------|---------|---------------------|
| Adapted from USEPA | | DE-ESC-3.6.1 |
| Pub. 840-B-92-002 | | Sheet 3 of 4 |
| | | Effective July 2023 |
| | | |

Standard Detail & Specifications

Construction Site Pollution Prevention

Notes (cont.)

e. Prominently post contact information for reporting spills through the DNREC 24-Hour Toll Free Number.

6. Education

- a. Include Best Management Practices (BMPs) for construction site pollution control as part of regular progress meetings.
- b. Information regarding waste management, equipment maintenance and spill prevention should be prominently posted in the construction trailer.

CONTACT INFORMATION

| DNREC 24-Hour Toll Free Number | 800-662-8802 |
|--|--------------|
| DNREC Solid & Hazardous Waste Management Section | 302-739-9403 |

Source:

Adapted from USEPA
Pub. 840-B-92-002

Symbol:

Detail No.

DE-ESC-3.6.1
Sheet 4 of 4
Effective July 2023

Standard Detail & Specifications Mulching

1. Materials and Amounts

- a. Straw Straw shall be unrotted small grain straw applied at the rate of 1-1/2 to 2 tons per acre, or 70 to 90 pounds (two bales) per 1,000 square feet. Mulch materials shall be relatively free of weeds and shall be free of noxious weeds such as; thistles, Johnsongrass, and quackgrass. Spread mulch uniformly by hand or mechanically. For uniform distribution of hand spread mulch, divide area into approximately 1,000 square feet sections and place 70-90 pounds (two bales) of mulch in each section.
- b. Wood chips Apply at the rate of approximately 6 tons per acre or 275 pounds per 1,000 square feet when available and when feasible. These are particularly well suited for utility and road rights-of-way. If wood chips are used, increase the application rate of nitrogen fertilizer by 20 pounds of N per acre (200 pounds of 10-10-10 or 66 pounds of 30-0-0 per acre).
- c. *Hydraulically applied mulch* -The following conditions apply to hydraulically applied mulch:
- i. Definitions:
 - a. Wood fiber mulch shall consist of specially prepared wood that has been processed to a uniform state, is packaged for sale as a hydraulic mulch for use with hydraulic seeding equipment, and consists of a minimum of 70% virgin or recycled wood fiber combined with 30% paper fiber and additives.
 - b. Blended fiber mulch shall consist of any hydraulic mulch that contains greater than 30% paper fiber. The paper component must consist of specially prepared paper that has been processed to a uniform fibrous state and is packaged for sale as a hydraulic mulch for use with hydraulic seeding equipment.
 - c. A bonded fiber matrix (BFM) consists of long strand, specially prepared wood fibers that have been processed to a uniform state held together by a water resistant bonding agent. BFMs shall contain no paper (cellulose) mulch but may contain small percentages of synthetic fibers to enhance performance.
 - d. Refer to **Figure 3.4.5a** for conditions and limitations of use for each of the above categories of hydraulic mulch.
- ii. All components of the hydraulically applied mulches shall be pre-packaged by the manufacturer to assure material performance. Field mixing of the mulch components is acceptable, but must be done per manufacturers recommendations to ensure the proper results.
- iii. Hydraulic mulches shall be applied with a viable seed and at manufacturer's recommended rates. Increased rates may be necessary based on site conditions.
- iv. Hydraulically applied mulches and additives shall be mixed according to manufacturers recommendations.
- iv. Materials within this category shall only be used when hydraulically applied mulch has been specified for use on the approved Sediment and Stormwater Plan, or supplemental approval from the plan approval agency has been obtained in writing for a specific area.

| Source: | Symbol: | Detail No. |
|--|---------|---------------------|
| | | DE-ESC-3.4.5 |
| Delaware ESC Handbook & Filtrexx™ International | | Sheet 1 of 3 |
| | | Effective July 2023 |

Standard Detail & Specifications Mulching

v. Application:

- Application:

 a. Apply product to geotechnically stable slopes that have been designed and constructed to divert runoff away from the face of the slope.
- b. Do not apply to saturated soils, or if precipitation is anticipated within 24-48 hours.
 c. During the spring (March 1 to May 31) and fall (September 1 to November 30) seasons, hydraulic mulches may be applied in a one-step process where all components are mixed

together in single-tank loads. It is recommended that the product be applied from opposing

- directions to achieve optimum soil coverage.
 d. During the summer (June 1 to August 31) and winter (December 1 to February 28) seasons, the following two-step process is required:
 Step One— Mix and apply seed and soil amendments with a small amount of mulch for
 - visual metering.

 <u>Step Two</u> Mix and apply mulch at manufacturers recommended rates over freshly seeded surfaces. Apply from opposing directions to achieve optimum soil
- e. Minimum curing temperature is 40°F (4°C). The best results and more rapid curing are achieved at temperatures exceeding 60°F (15°C). Curing times may be accelerated in high
- temperature, low humidity conditions on dry soils.

 vi. Recommended application rates are for informational purposes only. Conformance with this standard and specification shall be performance-based and requires 100% soil coverage. Any
- areas with bare soil showing shall be top dressed until full coverage is achieved.
 d. Compost blanket (CB) Loosely applied with a pneumatic blower so that a 1" compost blanket uniformly covers the soil with 100% coverage. This application can be used with seed to promote germination by applying the approved seed mix directly into the loosely blown compost. The compost blanket performs best on slopes less than 2:1 and requires no mulch anchoring.
- 2. Anchoring mulch Mulch must be anchored immediately to minimize loss by wind or water. This may be done by one of the following methods, depending upon size of area, erosion hazard, and cost.
- a. Crimping A crimper is a tractor drawn implement designed to punch and anchor mulch into the top two (2) inches of soil. This practice affords maximum erosion control but is limited to flatter slopes where equipment can operate safely. On sloping land, crimping should be done on the contour whenever possible.
- b. Tracking Tracking is the process of cutting mulch (usually straw) into the soil using a bulldozer or other equipment that runs on cleated tracks. Tracking is used primarily on slopes 3:1 or steeper and should be done up and down the slope with cleat marks running across the slope.
 c. Liquid mulch binders Applications of liquid mulch binders should be heavier at edges, in valleys, and
- c. Liquid mulch binders Applications of liquid mulch binders should be heavier at edges, in valleys, and at crests of banks and other areas where the mulch will be moved by wind or water. All other areas should have a uniform application of binder. The use of synthetic binders is the preferred method of mulch binding and should be applied at the rates recommended by the manufacturer.
 d. Paper fiber The fiber binder shall be applied at a net dry weight of 750 lbs/ac. The wood cellulose fiber
- shall be mixed with water, and the mixture shall contain a maximum of 50 lbs. of wood cellulose fiber per 100 gallons.

 e. Nettings Biodegradable nettings may be used to secure straw mulch. Install and secure according to

| | the manufacturer's recomm | mendations. Photodegradable or synthe | tic nettings are not acceptable. |
|--|--|---------------------------------------|---|
| | Source: | Symbol: | Detail No. |
| | Delaware ESC Handbook & Filtrexx™ International | | DE-ESC-3.4.5 Sheet 2 of 3 Effective July 2023 |

MULCHING MATERIAL SELECTION GUIDE Shard and Percent Slope Type of Mulch / App. Rate* Dec. 1 to Feb. 28(29) March 1 to May 31 June 1 to Aug. 31 Sept. 1 to Nov. 30 ended Fiber @ 2000 lbs/ac. minimur Deta Vood Fiber @ 2000 lbs/ac. min. 3FM @ 3000 lbs/ac. min. Straw @ 2 Tons/ac. Min. Stabilization Matting** Compost Blanket (CB) Wood Fiber @ 2000 lbs/ac. min. BFM @ 3000-3500 lbs/ac. min Straw @ 2 Tons/ac. min. Stabilization Matting** Compost Blanket (CB) 6% to 10.9% Wood Fiber @ 2000-2500 lbs/ac. min. BFM @ 3500-4000 lbs/ac. min. Straw @ 2 Tons/ac. min. Stabilization Matting** 1" Compost Blanket (CB) Wood Fiber @ 2500-3000 lbs/ac. min. BFM @ 3500-4000 lbs/ac. min. Straw @ 2 Tons/ac. min. Stabilization Matting** I" Compost Blanket (CB) Wood Fiber @ 2500-3000 lbs/ac. min. BFM @ 4000 lbs/ac. min. Straw @ 2 Tons/ac. min. Stabilization Matting** I" Compost Blanket (CB) BFM @ 4000-4500 lbs/ac. min. Straw @ 2 Tons/ac. min.*** Stabilization Matting**

* Note: Manufacturers Recommended Rates for informational purposes only. Performance standard requires 100% soil coverage.

* Note: Stabilization Matting must be applied in accordance with Section 3.4.6 of the Delaware ESC Handbook.

***Note: Straw applied on slopes greater than 33% must be netted (this does not apply to topsoil stockpiles).

OK = Acceptable to use during this time period.

xxx = Not acceptable to use during this time period.

All application rates are minimums

EROSION & SEDIMENT CONTROL DETAILS

MORRIS & RITCHIE ASSOCIATES, INC.

DESCRIPTION
BY

HORRIS & RITCHIE ASSOCIATES, INC.
ENGINEERS, PLANNERS, SURVEYORS AND
LANDSCAPE ARCHITECTS

111 RUTHAR DRIVE
NEWARK, DE 19711
(302) 326-2200

MRAGTA.COM

MRAGTA.COM

MRAGTA.COM

© 2025 MORRIS & RITCHIE ASSOCIATES IN

8" PROPOSED PIPELINE
ROUTE 40 REPLACEMENT
NEW CASTLE COUNTY, DE

ESNG PROJ. CODE: DATE: 8/19/2025

23289

JTH/CWB

SCALE:

SHEET:

N/A

4 OF 16

MRA PROJECT NO:

DESIGN/CHECK BY:

Standard Detail & Specifications

Vegetative Stabilization

TEMPORARY SEEDING BY RATES, DEPTHS AND DATES Optimum Seeding Dates 1 O = Optimum Planting Period; A = Acceptable Planting Planting Depth Seeding Rate Certified Seed Perennial Ryegrass Annual Ryegrass /inter Wheat 2-3" sandy soils oxtail Millet 0.5 inches 1-2" sandy soils 0.5 inches 1-2" sandy soils

- 1. Winter seeding requires 3 tons per acre of straw mulch for proper stabilization.
- 2. May be planted throughout summer if soil moisture is adequate or seeded area can be irrigated.
- 3. Applicable on slopes 3:1 or less.
- 4. Use varieties currently recommended for Delaware. Contact a County Extension Office for information. 5. Warm season grasses such as Millet may be used between 5/1 and 9/1 if desired. Seed at 3-5 lbs.
- per acre. Good on low fertility and acid areas. Seed after frost through summer at a depth of 0.5".

NOTE: Alternative seed mixes may be used with prior approval from the Department or Delegated Agency.

* PREFERRED SEED MIX

| ource: | Symbol: | Detail No. |
|-----------------------|---------|---|
| Delaware ESC Handbook | | DE-ESC-3.4.3 Sheet 1 of 4 Effective July 2023 |

Standard Detail & Specifications

Vegetative Stabilization

| | Optimum Seeding Dates ² | | | | | | | | | | | |
|--------------------|---|---------------------------------|--|--------------|----------------|----------------|--------------|----------------|---------------|--------------------------------------|---|--|
| Seeding Mixtures S | | | g Rate ¹ | | | | timum Pla | Remarks | | | | |
| Mix No. | Certified Seed ³ | No. Certified Seed ³ | | | Coa | astal P | lain | Р | iedmo | nt | All ⁴ | |
| | Well Drained Soils | lb/Ac | lb/1000 sq.ft. | 2/1- 4/30 | 5/1- 8/14 | 8/15- 10/31 | 3/1- 4/30 | 5/1- 7/31 | 8/1- 10/31 | 10/31-2/1 | | |
| 1 | Tall Fescue Canada Wild Rye | 140 10 | 3.2 0.23 | Α | 0 | А | Α | 0 | Α | Add 100 lbs./ac Winter Rve | Good erosion control mix Tolerant of low fertility soils Good for droughty sites | |
| 2 | Deertongue Sheep Fescue White Clover | 30 30 10 | 0.69 0.69 0.35 | А | 0 | А | Α | 0 | А | Add 100 lbs./ac Winter Rye | Good erosion control mix Tolerant of low fertility soils Legume that fixes atmospheric N into soil | |
| 3 | Tall Fescue (Turf-type) or Strong Creeping Red Fescue or Perennial Ryegrass plus Flatpea ⁵ | 50 50 50 | 1.15 1.15 1.15 0.34 | 0 | A ⁴ | 0 | 0 | A ⁴ | 0 | Add 100 lbs./ac. Winter Rye | Good erosion control mix Tall Fescue for droughty conditions. Creeping Red Fescue for heavy shade. Flatpea to suppress woody vegetation. | |
| 4 | Strong Creeping Red Fescue Kentucky Bluegrass Perennial Ryegrass or Redtop plus White Clover ⁵ | 100 70 15 5 | 2.3 1.61 0.35 0.11 | 0 | A ⁴ | 0 | 0 | A ⁴ | 0 | Add 100 lbs./ac. Winter Rye | Suitable waterway mix. Canada Bluegrass more drought tolerant. Use Redtop for increased drought tolerance. | |
| 5 | Switchgrass ^{6,7} or Coastal Panicgrass Big Bluestem Little Bluestem Indian Grass | 10 10 5 5 | 0.23 0.23 0.11 0.11 0.1 | | 0 | | | 0 | | | Native warm-season mixture. Tolerant of low fertility soils. Drought tolerant. Poor shade tolerance. N fertilizer discouraged - weeds | |
| 6 | Tall Fescue (turf-type) (Blend of 3 cultivars) | 150 | 3.5 | 0 | A ⁴ | 0 | 0 | A ⁴ | 0 | | Managed filter strip for nutrient uptake. | |
| 7 | Tall Fescue Ky. Bluegrass (Blend) Perennial Ryegrass | 150 20 20 | 3.5 0.46 0.46 | 0 | A ⁴ | 0 | 0 | A ⁴ | 0 | | Three cultivars of Kentucky Bluegrass. Traffic tolerant. | |
| 8 | Big Bluestem ⁷ Indian Grass ⁷ Little Bluestem ⁷ Creeping Red Fescue plus one of: Partridge Pea Bush Clover | 10 10 8 30 5 3 | 0.23 0.23 0.18 0.69 0.11 0.07 | 0 | A ⁴ | | 0 | A ⁴ | | | All species are native. Indian Grass and Bluestem have fluffy seeds. Plant with a specialized native seed drill. Creeping Red Fescue will provide erosion protection while | |
| | Wild Indigo Showy Tick-Trefoil | 3 2 | 0.07 0.05 | | | | | | | | the warm season grasses get established. | |

NOTE: Alternative seed mixes may be used with prior approval from the Department or Delegated Agency.

| Source: | Symbol: | Detail No. |
|-----------------------|---------|-------------------------------------|
| Delaware ESC Handbook | | DE-ESC-3.4.3 |
| | | Sheet 2 of 4 Effective July 2023 |

Standard Detail & Specifications

Vegetative Stabilization

| | Seeding Mixtures | Seeding Rate ¹ | | Optimum Seeding Dates ² eeding Rate ¹ O = Optimum Planting Period A = Acceptable Planting Period | | | | | | | Remarks |
|---------|---|---------------------------|----------------------------|---|----------------|----------------|--------------|----------------|---------------|--------------------------------------|---|
| Mix No. | Certified Seed ³ | | | | astal P | lain | Р | iedmo | nt | All ⁴ | |
| | Poorly Drained Soils | lb/Ac | lb/1000 sq.ft. | 2/1- 4/30 | 5/1- 8/14 | 8/15- 10/31 | 3/1- 4/30 | 5/1- 7/31 | 8/1- 10/31 | 10/31-2/1 | |
| 9 | Redtop Creeping Bentgrass Sheep Fescue Rough Bluegrass | 75 35 30 45 | 1.72 0.8 0.69 1 | 0 | A ⁴ | 0 | 0 | A ⁴ | 0 | Add 100 lbs./ac. Winter Rye | Quick stabilization of disturbed sites and waterways |
| 10 | Switchgrass ⁶ | 10 | 0.23 | Α | | 0 | Α | | 0 | | Good erosion control, wildlife cover and wetland revegetation |
| | Residential Lawns | 1 400 | | | - 4 | | _ | | | | |
| 11 | Tall Fescue Perennial Ryegrass Kentucky Bluegrass Blend | 100 25 30 | 2.3 0.57 0.69 | 0 | A ⁴ | 0 | 0 | A ⁴ | 0 | | High value, high maintenance, light traffic, irrigation necessary Well drained soils, full sun. |
| 12 | Tall Fescue Perennial Ryegrass Sheep Fescue | 100 25 25 | 2.3 0.57 0.57 | 0 | Α ⁴ | 0 | 0 | Α ⁴ | 0 | | Moderate value, low maintenance, traffic tolerant |
| 13 | Creeping Red Fescue Chewings Fescue Rough Bluegrass Kentucky Bluegrass | 50 50 20 20 | 1.15 1.15 0.4 0.4 | 0 | A ⁴ | 0 | 0 | A ⁴ | 0 | | Shade tolerant, moderate traffic tolerance, moderate maintenance. |
| 14 | Creeping Red Fescue Rough Bluegrass or Chewings Fescue | 50 90 | 1.15 2.1 | 0 | A ⁴ | 0 | 0 | A ⁴ | 0 | | Shade tolerant, moisture tolerant. |
| 15 | K-31 Tall Fescue | 150 | 3.5 | 0 | A ⁴ | 0 | 0 | A ⁴ | 0 | | Monoculture, but performs well alone in lawns. Discouraged. |

1. When hydroseeding is the chosen method of application, the total rate of seed should be increased by 25%. 2. Winter seeding requires 3 tons per acre of straw mulch. Planting dates listed above are average for Delaware. These dates may require

- 3. All seed shall meet the minimum purity and minimum germination percentages recommended by the Delaware Department of Agriculture. The maximum % of weed seeds shall be in accordance with Chapter 15, Title 3 of the Delaware Code. 4. Turf-type species may be planted throughout summer if soil moisture is adequate or seeded area can be irrigated. 5. It is recommended that all leguminous seed be inoculated.
- 6. Warm season grass mix and Switchgrass cannot be mowed more than 4 times per year. 7. Warm season grasses require a soil temperature of at least 50 degrees in order to germinate and will remain dormant until then.

NOTE: Alternative seed mixes may be used with prior approval from the Department or Delegated Agency. * PREFERRED SEED MIX

| Source: | Symbol: | Detail No. |
|-----------------------|---------|---------------------|
| Delaware ESC Handbook | | DE-ESC-3.4.3 |
| | | Sheet 3 of 4 |
| | | Effective July 2023 |

Standard Detail & Specifications

Vegetative Stabilization

Construction Notes:

- 1. Site Preparation
- a. Prior to seeding, install needed erosion and sediment control practices such as diversions, grade stabilization structures, berms, dikes, grassed waterways, and sediment basins.
- b. Final grading and shaping is not necessary for temporary seedings.

2. Seedbed Preparation

It is important to prepare a good seedbed to ensure the success of establishing vegetation. The seedbed should be well prepared, loose, uniform, and free of large clods, rocks, and other objectionable material. The soil surface should not be compacted or crusted.

3. Soil Amendments

- a. Lime Apply liming materials based on the recommendations of a soil test in accordance with the approved nutrient management plan. If a nutrient management plan is not required, apply dolomitic limestone at the rate of 1 to 2 tons per acre. Apply limestone uniformly and incorporate into the top 4 to 6 inches of soil.
- b. Fertilizer Apply fertilizer based on the recommendations of a soil test in accordance with the approved nutrient management plan. If a nutrient management plan is not required, apply a formulation of 10-10-10 at the rate of 600 pounds per acre. Apply fertilizer uniformly and incorporate into the top 4 to 6 inches of soils.

4. Seeding

- a. For temporary stabilization, select a mixture from Sheet 1. For a permanent stabilization, select a mixture from **Sheet 2** or **Sheet 3** depending on the conditions. Alternative seed mixes may be used with prior approval from the Department or Delegated Agency.
- b. Apply seed uniformly with a broadcast seeder, drill, cultipacker seeder or hydroseeder. All seed will be applied at the recommended rate and planting depth.
- c. Seed that has been broadcast should be covered by raking or dragging and then <u>lightly</u> tamped into place using a roller or cultipacker. If hydroseeding is used and the seed and fertilizer is mixed, they will be mixed on site and the seeding shall be done immediately and without interruption.


Mulching

All mulching shall be done in accordance with detail DE-ESC-3.4.5.

| Source: | Symbol: | Detail No. |
|-----------------------|---------|---|
| Delaware ESC Handbook | | DE-ESC-3.4.3 Sheet 4 of 4 Effective July 2023 |

Standard Detail & Specifications

Inlet Protection - Type 2



Symbol:

Source:

Adapted from

ACF Products, Inc.

NOTE: Pre-manufactured products

installed in accordance with

manufacturer's recommendations

may be used as an equivalent

substitute with Departmental

<u>Perspective</u> Detail No.

approval.

DE-ESC-3.1.5.2 Sheet 1 of 2 Effective July 2023

Standard Detail & Specifications

Inlet Protection - Type 2

Notes:

- 1. This practice shall only be used in situations in which Inlet Protection Type 1 cannot be used due to site constraints. These include, but are not limited to partially completed parking areas, streets, roads, etc.
- 2. It may be necessary to transition from Type 1 to Type 2 Inlet Protection as construction
- 3. For areas where there is a concern for oil run-off or spills, insert shall meet one of the above specifications with an oil-absorbant pillow or shall be made completely from an oilabsorbant material with a woven pillow.

Materials:

Source:

Adapted from

ACF Products, Inc.

The geotextile inlet insert shall meet or exceed the specifications of Type GD-III geotextile in accordance with Appendix A-3 of the Delaware Erosion & Sediment Control Handbook.

> Detail No. Symbol: DE-ESC-3.1.5.2 IP-2 Sheet 2 of 2 Effective July 2023

TYPICAL CONSTRUCTION RIGHT-OF-WAY (REFER TO ALIGNMENT SHEETS FOR ACTUAL DIMENSIONS) REFER TO ENVIRONMENTAL NOTES FOR DETAILED ENVIRONMENTAL PROTECTION MEASURES **TOPSOIL** SUBSOIL **TOPSOIL** PROPOSED TYPICAL CONSTRUCTION WORKSPACE LIMITS

TYPICAL RIGHT-OF-WAY DETAIL NOT TO SCALE

- I. RIGHT OF WAY CONFIGURATION VARIES, SEE PLAN AND PROFILE SHEETS
- 2. CONFIGURATION DOES NOT INCLUDE ADDITIONAL TEMPORARY WORKSPACE FOR STAGING, CROSSINGS AND PIPE STORAGE.


NOTES:

THE CONTRACTOR SHALL PERFORM SOIL BORES AND/OR TEST PITS AS REQUIRED TO ASSURE THE FEASIBILITY OF DRILLING OPERATIONS. ONCE FEASIBILITY HAS BEEN DETERMINED, THE CONTRACTOR ASSUMES RESPONSIBILITY FOR ANY ADDITIONAL EXPENSES DUE TO UNFORESEEN SOIL OR BEDROCK CONDITIONS.

NO WETLAND OR WATERBODY SHALL BE IMPACTED BY A HORIZONTAL DIRECTIONAL DRILLING (HDD) OPERATION.

ALL DRILLING MUD IS TO BE CONTAINED DURING CONSTRUCTION WITH BERMS, MUD PITS AND EROSION AND SEDIMENTATION CONTROLS DEEMED APPROPRIATE FOR THE SITE. ALL

THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING TRAFFIC CONTROL DEVICES FOR THE MAINTENANCE AND PROTECTION OF TRAFFIC, WHILE SEGREGATING TRAVEL LANES FROM WORK AREAS UTILIZED FOR HDD OPERATIONS.



EROSION & SEDIMENT CONTROL DETAILS

8" PROPOSED PIPELINE



© 2025 MORRIS & RITCHIE ASSOCIATES IN

ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE ESNG PROJ. CODE: DATE: 8/19/2025 MRA PROJECT NO: SCALE: 23289 N/A

JTH/CWB

SHEET:

DESIGN/CHECK BY:

5 OF 16

DELDOT UTILITY PLAN GENERAL NOTES

- PLANS ARE REVIEWED FOR GENERAL CONFORMITY. DELDOT IS NOT RESPONSIBLE FOR ERRORS OR OMISSIONS WITHIN THE PLAN SET. THE UTILITY OWNER IS RESPONSIBLE TO ENSURE ACCURACY OF PLANS AND CONFORMANCE WITH DELDOT STANDARDS.
- 2. ALL BACKFILL MATERIAL IN EXISTING/PROPOSED ROADWAY SHALL CONFORM TO TYPE "C" BORROW. ALL BORROW BACKFILL SHALL BE COMPACTED TO 95% USING AASHTO T99 STANDARD FOR TESTING.
- 3. GABC PLACED SHALL BE COMPACTED TO 98%.
- 4. COMPACTION TESTING SHALL BE PERFORMED EVERY 100' AND TESTING SHALL BE TAKEN ON EACH LIFT OF MATERIAL PLACED. (WHEN UTILITY IS IN THE ROADWAY)

CONSTRUCTION, SUPPLEMENTAL SPECIFICATIONS, STANDARD CONSTRUCTION DETAILS, UTILITY MANUAL, SPECIAL PROVISIONS AND DESIGN MEMORANDUMS.

WORK IS COMPLETED AND A STAND OF GRASS HAS BEEN ESTABLISHED TO DELDOT STANDARDS AND A ACCEPTANCE LETTER HAS BEEN ISSUED.

- 5. TAR CHIP/HOT MIXES ROADS: TRAVEL WAY PAVEMENT DISTURBED SHALL BE RESTORED AT THE END OF THE DAY PRIOR TO REOPENING TO TRAFFIC. HOT MIX SHALL BE PLACE PER TEMP PATCHING DETAIL 6" GABC AND 2" TYPE "C"
- 6. TAR CHIP/HOT MIXES SHOULDERS: SHOULDERS DISTURBED MAY BE LEFT IN GABC TO FINISH GRADE OVERNIGHT BUT SHALL BE CLOSED USING APPROPRIATE SIGNING AND DRUMS. TEMP PAVEMENT SHALL BE PLACED FOR SHOULDERS
- 1. IF THE REMAINING PORTION OF HOTMIX BETWEEN THE PIPE TRENCH EXCAVATION AND EDGE OF PAVEMENT IS LESS THAN 3' THE REMAINING SECTION SHALL BE REMOVED AND REPAVED AS PART OF THE FULL DEPTH PAVING
- 8. ALL AREAS DISTURBED OUTSIDE OF THE PAVEMENT SHALL BE GRADED EACH DAY TO ENSURE POSITIVE DRAINAGE AND SHALL BE PERMANENTLY RESTORED AT THE END OF EACH WEEK.
- 9. ALL TEMPORARY HOT MIX SHALL BE PLACED TO PROVIDE A SMOOTH RIDABLE SURFACE TO DELDOT STANDARDS.
- IO. A SAFETY EDGE IS REQUIRED ON ALL HOT MIX PLACED.
- II. ANY STRIPING DISTURBED SHALL BE PLACED AT THE END OF THE DAY PRIOR TO OPENING TO TRAFFIC.
- 12. PROOF ROLL OF GABC SHALL BE PERFORMED USING A LOADED IO WHEELER PRIOR TO PLACEMENT OF HOT MIX
- 13. ALL MATERIALS AND WORKMANSHIP WITHIN THE STATE R/W SHALL BE COMPLETED IN ACCORDANCE WITH CURRENT STATE OF DELAWARE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATION FOR ROAD AND BRIDGE
- 14. THERE IS A ONE YEAR WARRANTY ON ALL EARTH WORK AND CONCRETE. A THREE YEAR WARRANTY ON ALL HOT MIX INCLUDING SUBBASE/SUBGRADE ISSUES WITHIN THE PAVEMENT AREAS, WARRANTY DOES NOT START UNTIL ALL
- 15. ALL DISTURBED AREAS WITHIN THE STATE RIGHT-OF-WAY, BUT NOT IN THE PAVEMENT, SHALL BE TOP-SOILED (6" MINIMUM), FERTILIZED, SEEDED AND MULCHED. IF SOD IS USED NEXT TO SIDEWALK OR SHARED-USE PATH, CONTRACTOR SHALL GRADE TOPSOIL ADJACENT TO THE SIDEWALK OR SHARED-USE PATH TO AVOID WATER PONDING ON THE SIDEWALK OR SHARED-USE PATH.
- 16. A 72-HOUR (MINIMUM) NOTICE SHALL BE GIVEN TO THE DELDOT DISTRICT PERMIT SUPERVISOR PRIOR TO STARTING UTILITY CONSTRUCTION.
- 17. A 48 HOUR NOTICE IS REQUIRED TO BE GIVEN TO THE DELDOT INSPECTOR PRIOR TO MATERIAL RELEASES.
- 18. ALL CONCRETE/HOT MIX MATERIALS SHALL BE RELEASED BY THE INSPECTOR PRIOR TO PLACEMENT.
- 19. MISS UTILITY OF DELAWARE SHALL BE NOTIFIED THREE (3) CONSECUTIVE WORKING DAYS PRIOR TO EXCAVATION, AT 1-800-282-8555.
- 20. ALL SIGNING, STRIPING AND MAINTENANCE OF TRAFFIC IS THE CONTRACTOR'S RESPONSIBILITY AND SHALL FOLLOW THE GUIDELINES SHOWN IN THE DELAWARE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (DE MUTCD) FOR STREETS AND HIGHWAYS (LATEST EDITION). THE OWNER OR MAINTENANCE CORPORATION SHALL BE RESPONSIBLE FOR MAINTENANCE OF ALL SIGNS INSTALLED AS PART OF THIS PROJECT.
- 21. A COPY OF THE UP TO DATE APPROVED CONSTRUCTION DOCUMENTS AND DELDOT APPROVAL LETTERS SHALL BE MAINTAINED ON THE PROJECT SITE AT ALL TIMES AND BE AVAILABLE FOR INSPECTION BY DELDOT PERSONNEL.
- 22. EXISTING UTILITIES ARE SHOWN IN ACCORDANCE WITH THE BEST AVAILABLE INFORMATION, COMPLETENESS OR CORRECTNESS THEREOF IS NOT GUARANTEED, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE UTILITY COMPANIES INVOLVED IN ORDER TO SECURE THE MOST ACCURATE INFORMATION AVAILABLE AS TO UTILITY LOCATION AND ELEVATION, NO CONSTRUCTION AROUND OR ADJACENT TO UTILITIES SHALL BEGIN WITHOUT NOTIFYING THEIR OWNERS AT LEAST 48-HOURS IN ADVANCE, THE CONTRACTOR SHALL TAKE THE NECESSARY PRECAUTIONS TO PROTECT THE EXISTING UTILITIES AND MAINTAIN UNINTERRUPTED SERVICE AND ANY DAMAGE DONE TO THEM DUE TO HIS/HER NEGLIGENCE SHALL BE IMMEDIATELY AND COMPLETELY REPAIRED AT THE CONTRACTOR'S EXPENSE. TO LOCATE EXISTING UTILITIES IN THE FIELD PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CONTACT MISS UTILITY OF DELAWARE (SEE NOTE #5).
- 23. SHOULD UTILITY RELOCATION BE REQUIRED, THE DEVELOPER MUST SUBMIT A UTILITY RELOCATION PLAN FOR DELDOT REVIEW, ALONG WITH CORRESPONDENCE FROM THE UTILITY COMPANIES STATING PRELIMINARY APPROVAL TO THE RELOCATION AND DESIGN OF THE UTILITIES PRIOR TO THE DELDOT PRE-CONSTRUCTION MEETING. NO PHYSICAL CONSTRUCTION CAN OCCUR UNTIL THE UTILITY PLANS ARE APPROVED, THE INDIVIDUAL UTILITY COMPANIES ISSUE FINAL APPROVAL, AND A DELDOT UTILITY PERMIT IS ISSUED TO THE UTILITY COMPANY.
- 24. DESIGN AND INSTALLATION OF ALL PAVEMENT MARKINGS AND STRIPING SHALL BE AS OUTLINED IN THE LATEST VERSION OF THE DE MUTCD. FOR FINAL PERMANENT PAVEMENT MARKINGS EPOXY RESIN PAINT SHALL BE REQUIRED FOR LONG LINE STRIPING, I.E. SYMBOLS/LEGENDS, PERMANENT PAVEMENT MARKING TAPE (PER DELDOT APPROVED MATERIALS LIST) WILL BE REQUIRED ON CONCRETE SURFACES, FOR SHORT LINE STRIPING, I.E. SYMBOLS/LEGENDS.
- 25. BREAKAWAY POSTS SHALL BE USED WHEN INSTALLING ALL SIGNS. REFERENCE DELDOT STANDARD CONSTRUCTION DETAIL T-15.
- 26. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSURE THAT PAVING WITHIN THE STATE OF DELAWARE RIGHT-OF-WAY IS INSTALLED TO THE ELEVATIONS SHOWN AND THAT NO PONDING OF WATER EXISTS AFTER PAVING IS COMPLETE.
- 27. ALL PERSONS WORKING WITHIN THE STATE RIGHT-OF-WAY SHALL WEAR A MINIMUM OF AN ANSI CLASS II SAFETY VEST MEETING OR EXCEEDING THE ANSI 107-2004 REQUIREMENTS, AS SPECIFIED IN THE DELAWARE MUTCD.
- 26. WITHIN THE MAINLINE WORK AREA, PERMANENT ADVANCE WARNING SIGNS WITH THE LEGENDS ROAD WORK 1500 FT, ROAD WORK 1000 FT AND ROAD WORK 500 FT SHALL BE INSTALLED IN ADVANCE OF THE WORK AREA IN BOTH DIRECTIONS. AN END ROAD WORK SIGN SHALL BE LOCATED 500 FEET DOWNSTREAM FROM THE WORK AREA. ON INTERSECTING ROADWAYS WITHIN THE PROJECT LIMITS, A ROAD WORK AHEAD SIGN SHALL BE PLACED AT A DISTANCE NOT LESS THAN 500 FEET IN ADVANCE OF THE WORK AREA AND AN END ROAD WORK SIGN SHALL BE LOCATED 500 FEET DOWNSTREAM OF THE WORK AREA. ALL PERMANENT ADVANCE WARNING SIGNS SHALL BE GROUND MOUNTED ON TWO NCHRP-350 OR MASH APPROVED BREAKAWAY POSTS AND SHALL BE MOUNTED IN COMPLIANCE WITH THE DELAWARE MUTCD. PERMANENT ADVANCE WARNING SIGNS SHALL BE MOUNTED AT A HEIGHT OF 7 FEET, MEASURED FROM THE ROADWAY TO THE BOTTOM OF THE SIGN. THE USE OF SKID MOUNTED SIGN SUPPORTS IS NOT ALLOWED UNLESS THE CONTRACTOR CAN DEMONSTRATE THAT A UTILITY CONFLICT EXISTS, WHICH SHALL BE VERIFIED BY THE ENGINEER; OR CONCRETE MEDIANS PREVENT THE INSTALLATION OF THE PERMANENT ADVANCE WARNING SIGNS IN THE APPROPRIATE LOCATION.
- 29. CONTRACTOR TO PROVIDE CERTIFICATION OF COMPLIANCE WITH NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM (NCHRP) REPORT 350 FOR TRAFFIC CONTROL DEVICES OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH).
- 30. LOOP DETECTORS: ADVANCE NOTICE TO BE PROVIDED TO DELDOT FOR CONSTRUCTION IN THE AREAS OF LOOP DETECTORS AT SIGNALIZED INTERSECTIONS. E.S.N.G. AND ITS CONTRACTOR WILL COORDINATE WITH DELDOT FOR LOOP DETECTOR REPAIRS (DELDOT WILL MAKE REPAIRS, AND DELDOT WILL INVOICE E.S.N.G. FOR THE REPAIRS).
- 31. CONTRACTOR SHALL IMMEDIATELY REPAIR ANY DAMAGED EXISTING DRAINAGE TRENCHES OR UNDERDRAINS ENCOUNTERED DURING CONSTRUCTION.
- 32. CONTRACTOR SHALL PROVIDE SHORING TO PROTECT THE ROAD FOR ANY EXCAVATION WITHIN 2 FEET OF THE EDGE OF PAVEMENT, PER DELDOT STANDARDS AND SPECIFICATIONS.
- 33. ALL STORM DRAIN PIPES AND STRUCTURES IMPACTED BY PIPELINE INSTALLATION ARE TO BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE.
- 34. CONTRACTOR SHALL SCHEDULE WITH UTILITY COMPANY TO SHORE/HOLD ALL EXISTING UTILITY POLES WITH IN 5 FEET OF PIPELINE TRENCHING AT CONTRACTORS EXPENSE.
- 35. TEST STATIONS SHALL NOT BE SET IN DITCH LINES OR SLOPES.
- 36. HOT MIX DRIVEWAYS SHALL BE RESTORED WITH 6" GABC AND 2" TYPE "C" HOT MIX OR MATCH EXISTING (WHICHEVER IS GREATER) AND SHALL TIE INTO EDGE OF SHOULDER OF ROADWAY IF PATCHING IS LESS THAN 6 FEET FROM JOINT.
- 37. STONE DRIVEWAYS SHALL BE RESTORED WITH 6" GABC OR MATCH EXISTING (WHICHEVER IS GREATER).
- 38. COMMERCIAL ENTRANCES SHALL BE DIRECTIONAL DRILLED OR AS SHOWN ON THE PLAN.


MAINTENANCE OF TRAFFIC / TEMPORARY TRAFFIC CONTROL PLAN - GENERAL NOTES

- I. ALL WORK SHALL BE PERFORMED IN A MANNER THAT WILL REASONABLY PROVIDE THE LEAST PRACTICABLE OBSTRUCTION TO ROAD USERS, INCLUDING VEHICULAR TRAFFIC, BICYCLE TRAFFIC AND PEDESTRIAN TRAFFIC.
- 2. ALL TEMPORARY TRAFFIC CONTROL AND TEMPORARY TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH: THE CONTRACT DOCUMENTS, THE LATEST EDITION OF THE MANUAL TITLED "STATE OF DELAWARE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD)" (HEREINAFTER REFERRED TO AS THE "DELAWARE MUTCD"), CURRENT STATE OF DELAWARE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, AND SUPPLEMENTAL SPECIFICATIONS, INCLUDING ALL REVISIONS AS OF THE DATE OF THE PERMIT APPROVAL.
- THE DEPARTMENT RESERVES THE RIGHT TO STOP THE CONTRACTOR'S OPERATIONS, IF, IN THE OPINION OF THE DEPARTMENT'S REPRESENTATIVE, THE CONTRACTOR'S OPERATIONS ARE NOT IN COMPLIANCE WITH THE DELAWARE MUTCD, THE SPECIFICATIONS OR THE PLANS OR IF THE CONTRACTOR'S OPERATIONS ARE DEEMED UNSAFE.
- 4. IF THE CONTRACTOR DESIRES TO DEVIATE FROM THE TEMPORARY TRAFFIC CONTROL PLAN (TTCP) PROVIDED IN THE PLAN SET OR DESIRES CHANGES TO THE PHASING OR SCOPE OF THE TTCP, THE CONTRACTOR SHALL SUBMIT A NEW TTCP TO THE DISTRICT SAFETY OFFICER FOR APPROVAL PRIOR TO THE START OF WORK AT EACH AND EVERY LOCATION. THE TTCP SHALL BE PREPARED IN ACCORDANCE WITH ALL APPLICABLE DELDOT STANDARDS, THE TTCP SHALL BE SUBMITTED 14 CALENDAR DAYS IN ADVANCE OF STARTING WORK.
- 5. ALL ROADWAY CLOSURES OR LANE CLOSURES BEYOND THOSE SPECIFIED AND APPROVED IN THE PLANS SHALL BE APPROVED BY THE DISTRICT SAFETY OFFICER A MINIMUM OF TWO WEEKS IN ADVANCE OF THE PROPOSED RESTRICTION.
- 6. TEMPORARY TRAFFIC CONTROL DEVICES SHALL BE MAINTAINED IN GOOD CONDITION IN ACCORDANCE WITH THE BROCHURE ENTITLED "QUALITY GUIDELINES FOR TEMPORARY TRAFFIC CONTROL DEVICES", PUBLISHED BY THE AMERICAN TRAFFIC SAFETY SERVICES ASSOCIATION (ATSSA). ANY TEMPORARY TRAFFIC CONTROL DEVICES THAT DO NOT MEET THE QUALITY GUIDELINES SHALL BE REMOVED AND REPLACED WITH ACCEPTABLE DEVICES. FAILURE TO COMPLY WILL RESULT IN WORK STOPPAGE.
- TEMPORARY TRAFFIC CONTROL DEVICES USED ON ALL ROADWAYS OPEN TO THE PUBLIC IN DELAWARE SHALL CONFORM TO THE DELAWARE MUTCD AND SHALL BE IN NEW OR REFURBISHED CONDITION. ALL DEVICES SHALL BE CRASHWORTHY IN ACCORDANCE WITH THE NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM (NCHRP) REPORT 350 AND/OR IN ACCORDANCE WITH THE LATEST EDITION OF THE MANUAL FOR ASSESSING SAFETY HARDWARE (MASH), PUBLISHED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO). THE CONTRACTOR SHALL SUBMIT CERTIFICATION FOR ALL TEMPORARY TRAFFIC CONTROL DEVICES USED SPECIFICALLY ON THIS PROJECT TO THE DISTRICT SAFETY OFFICER AT OR PRIOR TO THE PRE-CONSTRUCTION MEETING. THE CONTRACTOR SHALL NOT BEGIN WORK OR PLACE ANY TEMPORARY TRAFFIC CONTROL DEVICES UNTIL THE CERTIFICATION OF DEVICES HAS BEEN APPROVED BY THE DISTRICT SAFETY OFFICER.
- 8. ANY DEFICIENCIES RELATED TO TEMPORARY TRAFFIC CONTROL THAT ARE REPORTED TO THE CONTRACTOR IN WRITING SHALL BE CORRECTED WITHIN 24 HOURS OR AS DIRECTED BY THE DISTRICT SAFETY OFFICER, CORRECTIVE ACTIONS ON SEVERE DEFICIENCIES SHALL BE TAKEN IMMEDIATELY. FAILURE TO COMPLY WILL RESULT IN THE SUSPENSION OF WORK UNTIL DEVICES ARE BROUGHT BACK INTO COMPLIANCE.
- 9. ACCESS TO ALL BUSINESSES AND RESIDENCES WITHIN THE PROJECT LIMITS SHALL BE MAINTAINED THROUGHOUT THE DURATION OF THIS CONTRACT. ANY TEMPORARY CLOSURE OF A DRIVEWAY OR ENTRANCE FOR TIE-IN PURPOSES SHALL BE COORDINATED WITH THE ENGINEER AND THE PROPERTY OWNER IN ADVANCE OF THE CLOSURE.
- IO. ACCESS TO ALL TRANSIT STOPS LOCATED WITHIN THE PROJECT LIMITS SHALL BE MAINTAINED UNLESS OTHERWISE DIRECTED BY THE PLANS OR THE ENGINEER. MAINTAINING ACCESS TO THE TRANSIT STOP SHALL INCLUDE MAINTAINING AN AREA FOR THE TRANSIT VEHICLE TO STOP TO PICK-UP AND DISCHARGE PASSENGERS AND ALSO AN ACCESSIBLE PATH FOR PEDESTRIANS TO SAFELY ACCESS THE TRANSIT STOP.
- I. THE CONTRACTOR SHALL PROVIDE ALL PROPERTY OWNERS AND RESIDENTS WHO LIVE ADJACENT TO THE WORK ZONE WITH WRITTEN NOTICE, 48 HOURS IN ADVANCE OF THE START OF CONSTRUCTION WORK. THIS NOTIFICATION SHALL INCLUDE THE SCOPE OF WORK, WORKING HOURS, ANTICIPATED START AND COMPLETION DATES; A SUMMARY OF CONSTRUCTION ACTIVITIES WHICH MAY INTERFERE WITH ACCESS TO THE PROPERTY INCLUDING A SCHEDULE AND ACCESS COORDINATION PLAN, CONTRACTOR'S NAME AND ADDRESS AND A DELDOT CONTACT PHONE NUMBER. FAILURE TO GIVE PROPER NOTICE WILL RESULT IN A SUSPENSION OF THE WORK, UNTIL PROPER NOTICE IS PROVIDED. THE CONTRACTOR SHALL PROVIDE WRITTEN VERIFICATION TO THE ENGINEER THAT THE PROPERTY OWNERS AND RESIDENTS WERE NOTIFIED.
- 12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING THE LOCAL 911 CENTER, LOCAL SCHOOLS AND THE DELDOT PUBLIC INFORMATION CENTER OF ALL ROADS AND LANES TO BE CLOSED A MINIMUM OF SEVEN CALENDAR DAYS BEFORE THE CLOSURE.
- 13. THE CONTRACTOR SHALL NOTIFY THE LOCAL 911 CENTER IF ACCESS TO A FIRE HYDRANT IS TEMPORARILY RESTRICTED.
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT THE TRANSPORTATION MANAGEMENT CENTER IS NOTIFIED EACH AND EVERY DAY WHEN WORK IS BEING PERFORMED IN STATE RIGHT-OF-WAY. THE CONTRACTOR SHALL IDENTIFY THE TYPE OF WORK, ANY LANE(S) OR SHOULDERS CLOSED, THE LENGTH OF TIME FOR WORK, WHEN THE LANE RESTRICTIONS ARE IN PLACE AND WHEN LANE RESTRICTIONS ARE LIFTED, CONTACT PERSON/PHONE NUMBER AND STATE INSPECTOR. THE TRANSPORTATION MANAGEMENT CENTER CAN BE REACHED AT (302) 659-4600.
- 15. AT THE END OF EACH WORKDAY, THE CONTRACTOR SHALL CORRECT ALL VERTICAL DIFFERENCES IN ACCORDANCE WITH TABLE 66-I OF THE DELAWARE MUTCD.
- 16. AT THE END OF EACH DAY'S OPERATION AND BEFORE TRAFFIC IS RETURNED TO UNRESTRICTED ROADWAY USE, TEMPORARY PAVEMENT MARKINGS SHALL BE APPLIED IN ACCORDANCE WITH THE DELAWARE MUTCD AND DELDOT'S TEMPORARY PAVEMENT MARKINGS POLICY.
- 17. WHEN SIDE ROADS INTERSECT THE WORK ZONE, ADDITIONAL TRAFFIC CONTROL DEVICES SHALL BE ERECTED INCLUDING ADVANCED WARNING SIGNS.
- 18. ALL STORAGE OF EQUIPMENT AND MATERIAL SHALL COMPLY WITH SECTION 66.21 OF THE DELAWARE MUTCD.
- 19. ALL FLAGGERS SHALL COMPLY WITH CHAPTER 6E OF THE DELAWARE MUTCD AND MUST BE AMERICAN TRAFFIC SAFETY SERVICES ASSOCIATION (ATSSA) CERTIFIED IN THE STATE OF DELAWARE.
- 20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING HIS/HER WORK WITH OTHER CONTRACTORS IN THE AREA.
- 21. ALL PAVEMENT MARKINGS THAT ARE NO LONGER IN USE AND CONFLICT WITH TEMPORARY PAVEMENT MARKINGS SHALL BE REMOVED AND COMPLETELY OBLITERATED BY A METHOD APPROVED BY THE ENGINEER, PAINTING OVER THE CONFLICTING PAVEMENT MARKINGS WILL NOT BE ACCEPTED AS A METHOD OF REMOVAL.
- 22. THE CONTRACTOR IS RESPONSIBLE FOR THE MAINTENANCE OF EXISTING PAVEMENT WITHIN THE PROJECT LIMITS FOR THE DURATION OF THE CONTRACT OR AS DIRECTED BY THE ENGINEER.
- 23. ALL ROADWAYS AND ENTRANCES NOT OPEN TO TRAFFIC SHALL BE CLOSED USING TYPE III BARRICADES AND SHALL BE INSTALLED PER THE DELAWARE MUTCD. IF THE ROADWAY OR ENTRANCE IS CLOSED FOR MORE THAN ONE MONTH, THE CONTRACTOR SHALL ERECT PERMANENT BARRICADES AS DIRECTED IN PART 3 OF THE DELAWARE MUTCD.
- 24. ALL ROADS LEADING INTO THE WORK ZONE SHALL HAVE "UTILITY WORK AHEAD" AND "END UTILITY WORK" SIGNS.
- 25. STABILIZED CONSTRUCTION ENTRANCES SHALL BE USED TO REDUCE OFF-SITE SEDIMENTATION BY ELIMINATING THE TRACKING OF EXCESS SOIL ONTO PAVED PUBLIC ROADWAYS. ALL ROADWAYS SHALL BE KEPT CLEAN OF SEDIMENT AND DEBRIS. THE CONTRACTOR SHALL UTILIZE A STREET SWEEPER TO MINIMIZE DUST AND SOIL ON ROADWAYS AND ACCESS LOCATIONS SHALL BE SWEPT ONCE EACH DAY AS A MINIMUM.
- 26. INDIVIDUAL CONSTRUCTION ENTRANCE LOCATIONS SHALL BE KEPT TO A MINIMUM AND DETERMINED IN THE FIELD BY THE CONTRACTOR. DELDOT SHALL BE NOTIFIED OF ALL LOCATIONS PRIOR TO INSTALLATION.
- 27. AS AN ADVANCE WARNING, THE TRUCK SYMBOL (WII-IO) SIGN SHALL BE INSTALLED IN EITHER APPROACH DIRECTION FOR EACH STABILIZED CONSTRUCTION ENTRANCE AND REMAIN IN PLACE FOR THE DURATION OF THE DRIVEWAY USE. CONSTRUCTION WARNING SIGNS SHALL BE BLACK LEGEND ON ORANGE BACKGROUND AND WHEN UTILIZED FOR EXTENDED DURATIONS SHALL BE INSTALLED ON BREAKAWAY POSTS PER DELDOT STANDARD CONSTRUCTION DETAIL T-15.
- 28. WORK WITHIN A SIGNALIZED INTERSECTION OR IMPACT TO A SIGNALIZED INTERSECTION SHALL FOLLOW THE DELDOT MUTCD, TEMPORARY TRAFFIC CONTROL INTERIM GUIDANCE "TRAFFIC CONTROL WITHIN INTERSECTIONS", AND WILL REQUIRE A UNIFORMED TRAFFIC OFFICER.
- 29. THE DEPARTMENT RESERVES THE RIGHT TO RESTRICT LANE/SHOULDER CLOSURES IN CASE A SPECIAL EVENT IS SCHEDULED TO CROSS OR PROCEED THROUGH A WORK ZONE. IF SUCH A RESTRICTION IS DEEMED NECESSARY, THE DEPARTMENT SHALL PROVIDE THE PERMIT HOLDER A MINIMUM 2 WEEK ADVANCE NOTIFICATION.

- EXISTING PAYEMENT

— FULL DEPTH SAW CUT (JOINT TO BE SEALED)

- 30. ALL STABILIZED CONSTRUCTION ENTRANCE LOCATIONS SHALL BE APPROVED BY DELDOT PRIOR TO INSTALLATION.
- 30. CONTRACTOR SHALL UTILIZE THE FOLLOWING TRAFFIC CONTROL FROM THE DELAWARE MUTCD MOST CURRENT ADDITION.
- A. TYPICAL APPLICATION 3, FIGURE 6H-3: WORK ON THE SHOULDER OF A TWO LANE ROAD
- 31. MESSAGE BOARDS ARE REQUIRED 10 DAYS IN ADVANCE OF CONSTRUCTION.



1. TEMPORARY PATCHES FROM WINTER MONTHS SHALL BE PERMANENTLY RESTORED BY MAY 15.

2. IN LIEU OF GABC, ROTOMILLINGS OR CRUSHED CONCRETE CAN BE USED IF THE FOLLOWING REQUIREMENTS ARE METI3. - ROTOMILLINGS SPECIAL PROVISION 302514 SHOWN IN APPENDIX L.
4. - CRUSHED CONCRETE SUPPLEMENTAL SPECIFICATIONS 302 AND 621.
5. THE BACKFILL MATERIAL SHALL MEET THE REQUIREMENTS FOR BORROW, TYPE C AS PER SECTION 209 OF THE STANDARD SPECIFICATIONS.
6. COMPACTION SHALL MEET THE REQUIREMENTS AS PER SECTION 209 OF THE STANDARD SPECIFICATIONS.
7. FLOWABLE FILL IS ALLOWABLE AS A BACKFILL MATERIAL. FLOWABLE FILL SHALL MEET THE REQUIREMENTS OF SPECIAL PROVISION 208500 AS SHOWN IN APPENDIX F.
8. ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL MEET THE REQUIREMENTS SET FORTH IN THE CURRENT DELAWARE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGES CONSTRUCTION.

(SOURCE: DELDOT UTILITIES MANUAL - FIGURE 2-3)
MINIMUM DESIGN REQUIREMENTS
(DISTRICT ENGINEER MAY CHANGE
REQUIREMENTS IN SPECIAL CASES)

MATCH EXISTING) - SEE NOTE 2

(JOINT TO BE SEALED)

8° (MIN) CLASS A CONCRETE OR 12° (MIN)
BCOC PLACED IN TWO 6° LIFTS

BACKFILL BORROW TYPE C PLACED IN 6°
LIFTS LODGE MEASUREMENT AND COMPACTED PER DELDOT SPECIFICATIONS

SEE D-8 IN THE DELDOT STANDARD CONSTRUCTION
DETAILS HANNAL FOR PIPE BEDDING

NOTES.

1. PATCH HIDTHS ARE MEASURED ALONG THE ROADWAY CENTERLINE AND SHALL BE THE
PLAL HIDTH OF THE LANG CR LAWED DISTINGED.

2. THIS IS A MINIM PATCH, IF THE EXISTING ROADWAY HAS A HEAVIER CROSS SECTION.
THAN SHOWN HERE, IT WILL BE REPLACED WITH THAT CROSS SECTION, OR AS DIRECTED
BY THE BIOINEER.

PERMANENT PATCH

SOURCE: DELDOT STANDARD CONSTRUCTION DETAIL

7'-0" PLUS OUTSIDE DIAMETER OF PIPE (MIN.) LONGITUDINAL: FULL WIDTH OF LANE(S) DISTURBED

2" (MIN.) TYPE C HOT MIX (THICKNESS TO

REVISIONS

NO. DATE DESCRIPTION BY

EN

MORRIS & RITCHIE ASSOCIATES, INC.
ENGINEERS, PLANNERS, SURVEYORS AND
LANDSCAPE ARCHITECTS

111 RUTHAR DRIVE
NEWARK, DE 19711
(302) 326-2200

500 ENERGY LANE, SUITE 200 DOVER, DE 19901
TELEPHONE (302) 734-6710 - FAX (302) 734-6745

MRAGTA.COM

© 2025 MORRIS & RITCHIE ASSOCIATES INC

8" PROPOSED PIPELINE
ROUTE 40 REPLACEMENT
NEW CASTLE COUNTY, DE
ESNG PROJ. CODE: DATE: 8/19/20:


ESNG PROJ. CODE: DATE: 8/19/2025


MRA PROJECT NO: 23289 SCALE: N/A

DESIGN/CHECK BY: JTH/CWB SHEET: 6 OF 16

TRAFFIC CONTROL DETAILS

FULL DEPTH SAW OUT -





NOTE:

- I. CONTRACTOR SHALL VERIFY VERTICAL AND HORIZONTAL LOCATIONS OF ALL EXISTING FACILITIES PRIOR TO TIE-IN FABRICATION.
- 2. EXCAVATE WITH CAUTION!!! EXACT LOCATION OF EXISTING UNDERGROUND PIPES & UTILITIES IS UNKNOWN.
- 3. CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS PRIOR TO FABRICATION.

REVISIONS NO. DATE DESCRIPTION BY

MORRIS & RITCHIE ASSOCIATES, INC.
ENGINEERS, PLANNERS, SURVEYORS AND
LANDSCAPE ARCHITECTS

111 RUTHAR DRIVE
NEWARK, DE 19711

(302) 326-2200


MRAGTA.COM
© 2025 MORRIS & RITCHIE ASSOCIATES, INC.

EASTERN SHORE 500 ENERGY LANE, SUITE 200 DOVER, DE 19901 TELEPHONE (302) 734-6710 - FAX (302) 734-6745

8" PROPOSED PIPELINE ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE

WEST TIE-IN

| ESNG PROJ. CODE: | | DATE: | 8/19/2025 |
|------------------|---------|--------|-----------|
| MRA PROJECT NO: | 23289 | SCALE: | AS SHOWN |
| DESIGN/CHECK BY: | JTH/CWB | SHEET: | 7 OF 16 |



NOTE:

- I. CONTRACTOR SHALL VERIFY VERTICAL AND HORIZONTAL LOCATIONS OF ALL EXISTING FACILITIES PRIOR TO TIE-IN FABRICATION.
- 2. EXCAVATE WITH CAUTION!!! EXACT LOCATION OF EXISTING UNDERGROUND PIPES & UTILITIES IS UNKNOWN.
- 3. CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS PRIOR TO FABRICATION.

NO. DATE DESCRIPTION BY

MORRIS & RITCHIE ASSOCIATES, INC.
ENGINEERS, PLANNERS, SURVEYORS AND
LANDSCAPE ARCHITECTS

111 RUTHAR DRIVE
NEWARK, DE 19711
(302) 326-2200

MRAGTA.COM

© 2025 MORRIS & RITCHIE ASSOCIATES, INC

EASTERN SHORE

NATURAL GAS


500 ENERGY LANE, SUITE 200 DOVER, DE 19901
TELEPHONE (302) 734-6710 - FAX (302) 734-6745

8" PROPOSED PIPELINE ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE

ESNG PROJ. CODE: DATE: 8/19/2025

MRA PROJECT NO: 23289 SCALE: AS SHOWN

DESIGN/CHECK BY: JTH/CWB SHEET: 8 OF 16



| | | BILL OF MATERIALS- SSD INSTALLATION DETAIL #1 |
|-----|----------|---|
| NO. | QUANTITY | DESCRIPTION |
| 1 | 1 | SSD CONDUCTORS, MTL-6-36-B-X, - #6 AWG WIRE, FURNISHED WITH COMPRESSION TERMINALS |
| 2 | 1 | DAIRYLAND SOLID-STATE DECOUPLER SSD-(-3/+1)-1.2-100 |
| 3 | 2 | M8 THREADED STUD PIN BRAZING KIT, BAC PART #278-190-0430 |
| 4 | 2 | CERAMIC FERRULE FOR THREADED PINS |
| 5 | 1 | HEX NUT, M8-1.25, 316-SS OR APPROVED EQUIVALENT |
| 6 | 1 | FLAT WASHER, 5/16" DIAMETER, 316-SS OR APPROVED EQUIVALENT |
| 7 | 1 | SSD MOUNTING HARDWARE, DAIRYLAND STUD MOUNTING KIT: HCN-M8 |
| 8 | 1 | HEX NUT, 3/8-16, 316-SS OR APPROVED EQUIVALENT |
| 9 | 1 | FLAT WASHER, 3/8" DIAMETER, 316-SS OR APPROVED EQUIVALENT |
| 10 | 1 | STUD, 3/8"-16, 316-SS OR APPROVED EQUIVALENT |

STRANDED COPPER WIRE

-(WITH THWN OR HMWPE

INSULATION)

∼STARTING POWDER

-METAL POWDER

STRIP INSULATION FROM WIRE

STEP 2

- M8 PINS TO BE PIN-BRAZED ONTO PIPE, NO CLOSER THAN 3" FROM ANY WELD. SSD BRACKET TO BE MOUNTED ON PINS. CONDUCTORS TO BE CUT TO SHORTEST LENGTH POSSIBLE & RUN IN THE MOST DIRECT MANNER BETWEEN THE SSD
- TERMINAL AND THE CONNECTION POINT. CONNECT THE NEGATIVE TERMINAL OF THE DECOUPLING DEVICE TO CATHODICALLY PROTECTED PIPE AND THE

-CADWELD PLUS PACKAGE

IGNITION STRIP

POSITIVE TERMINAL TO STATION SIDE PIPE.

HANDLE

GRAPHITE

GRAPHITE

INSERT CADWELD PLUS PACKAGE INTO MOLD (MAY REQUIRE USE OF COVER/BAFFLE)

ATTACH CONTROL UNIT TERMINATION CLIP TO IGNITION STRIP


PRESS AND HOLD CONTROL UNIT SWITCH AND WAIT FOR IGNITION

STEP 3 (FOR ELECTRONIC IGNITION)

THERMITE WELD DETAILS

COVER


- EXACT ORIENTATION OF SSD IS TO BE DETERMINED IN THE FIELD.
- SURFACE IS TO BE PREPPED AND PAINTED ACCORDING TO ESNG SPECIFICATIONS FOR ANY PIN-BRAZING.
- 6. ALL CRIMPED RING TERMINALS ON CONDUCTORS ARE TO BE COVERED WITH HEAT SHRINK WRAP.



COATING APPLICATION FOR DENSO TAPE COATING

<u>PLAN</u>

ELEVATION



I. VERIFY PIPE TEMPERATURE IS AT LEAST 5° F ABOVE THE DEW POINT

BEFORE CLEANING OF PIPE. (IF APPLICABLE). 2. POWER BRUSH OR ABRASIVE BLAST PIPE UNTIL FREE OF RUST, DIRT, AND

OTHER FOREIGN MATTER (NEAR WHITE; SSPC-SP-10; NACE No.2 FINISH).

3. CLEAN TOTAL OF 18" TO 27" SECTION OF PIPE.

AREA OF THE PIPE.

4. APPLY CANUSA-CPS HBE-95-BG COATING TO THE FRESHLY CLEANED






COATING APPLICATION FOR RISER

NOT TO SCALE

- FINISHED GRADE

COATING APPLICATION FOR HBE-95-BG OR ESNG APPROVED EQUIVALENT NOT TO SCALE


BURIED ELBOW







<u>ELEVATION</u>

BURIED TEE







| <u>ELEVA</u> <u>BURIED I</u> | | | | Ē |
|---------------------------------|-----|-----|-----|---|
| NOMINAL PIPE SIZE | "A" | "B" | "C" | |
| 2" | 12" | 12" | 6" | |
| 3" | 12" | 12" | 6" | |
| 4" | 12" | 12" | 6" | |
| 6" | 18" | 18" | 9" | |
| 8" | 18" | 18" | 9" | |
| 10" | 24" | 24" | 12" | |
| 12" | 24" | 24" | 12" | |
| 14" | 30" | 30" | 18" | |
| 16" | 30" | 30" | 18" | |
| 18" | 36" | 36" | 18" | |
| 20" | 36" | 36" | 18" | |
| | | | | |

GENERAL NOTES:

- I. CONTRACTOR TO FURNISH ALL MATERIALS.
- 2. CLEAN, COAT AND WRAP FITTINGS AND PIPE WHICH WILL COME IN CONTACT WITH CONCRETE.
- 3. PIPE AND FITTINGS SHALL BE WRAPPED WITH "CONWED PIPE SAVER" OR EQUAL POLYETHYLENE MESH.
- 4. CONCRETE TO BE POURED TO CENTERLINE OF PIPING.
- 5. NO BACKFILL SHALL BE PLACED ON TOP OF CONCRETE UNTIL THE CONCRETE HAS HAD TIME TO SET UP.
- 6. BOTTOM OF CONCRETE SHALL BE PLACED ON SOLID FOOTING.
- 7. RIGID FORM WORK WILL NOT BE REQUIRED.
- 8. THIS SUPPORT IS NOT DESIGNED NOR INTENDED FOR A THRUST
- 9. CONTRACTOR TO USE 4000 PSI PLAIN CONCRETE OR "QUIKCRETE".

CONCRETE FOOTER DETAILS NOT TO SCALE

MRAGTA.COM © 2025 MORRIS & RITCHIE ASSOCIATES, INC.

24" 42" 42" 24"

CONSTRUCTION DETAILS

REVISIONS NO. DATE DESCRIPTION

NOTE: CONTRACTOR TO SUPPLY ALL

MATERIAL REQUIRED TO FABRICATE


SUPPORTS ON THIS DRAWING.

MORRIS & RITCHIE ASSOCIATES, INC ENGINEERS, PLANNERS, SURVEYORS ÁND LANDSCAPE ARCHITECTS 111 RUTHAR DRIVE NEWARK, DE 19711 (302) 326-2200

EASTERN SHORE 500 ENERGY LANE, SUITE 200 DOVER, DE 19901 TELEPHONE (302) 734-6710 - FAX (302) 734-6745

8" PROPOSED PIPELINE ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE

| ESNG PROJ. CODE: | | DATE: | 8/19/2025 |
|------------------|---------|--------|-----------|
| MRA PROJECT NO: | 23289 | SCALE: | AS SHOWN |
| DESIGN/CHECK BY: | JTH/CWB | SHEET: | 9 OF 16 |



1. THERMITE WELDS MADE TO GAS MAIN SHALL BE COATED WITH TWO PART EPOXY OR THREE PART WAX TAP OR APPROVED EQUAL.

HOLD GRAPHITE MOLD FIRMLY OVER ADAPTER SLEEVE WITH

OPENING AWAY FROM OPERATOR - IGNITE STARTING POWDER

2. REPAIR PIPE COATING IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.

SSD INSTALLATION DETAIL#1 **INSTALLATION ACROSS A HORIZONTALLY** INSTALLED MONOLITHIC INSULATOR

NOT TO SCALE

HANDLE

GRAPHITE

GRAPHITE MOLD

COVER

STEP 3 (FOR MANUAL IGNITION)

CLEAN SURFACE TO BRIGHT METAL AT

- WELD LOCATION BY MECHANICAL

POWER BRUCH OR FILE


STRIP INSULATION FROM WIRE

STEP 1


GRAPHITE


OPENING -


MOLD



NOTES:








DETAIL #3 EXTERIOR CONDUIT TO BUILDING INSTALLATION (NOT TO SCALE)

GROUNDING DETAILS CADWELD TAP CONNECTION TYPICAL

| CABL | E SIZE | CADWELD C | CONNECTION | |
|------|--------|------------------------|-------------|--|
| RUN | TAP | MOLD NUMBER WELD METAL | | |
| #2/0 | #2/0 | TAC-2G2G | #90 | |
| #2/0 | #2 | TAC-2G1V | #4 5 | |
| | | | | |



NOTES:

NO. DATE


DIRECT BURIAL ORANGE ELECTRICAL CAUTION TAPE (TYP.) BACKFILL WITH POWER & INSTRUMENTATION CONDUIT (TYP.) NOTES:

1. CABLE/CONDUIT TO BE PLACED AT BOTTOM OF TRENCH UNLESS SOIL CONDITIONS DICTATE OTHERWISE.

FINISHED GRADE

DETAIL #2 UNDERGROUND CABLE/CONDUIT BURIAL (NOT TO SCALE)

Material Schedule Item # Quantity Units SERIES 503S116 UTILITY MARKER W/ ESNG GRAPHIC #2622, 3" OD X 72" LENGTH, BISON 11-TERMINAL STAINLESS STEEL TEST STATION AND CAP #CTCUL303B5YEL 2 40 FT WIRE NO. 8 AWG STRANDED COPPER BLACK, THHN 4 | 2 | EA | THERMITE CARTRIDGE No. 15 MAX, OR PIN BRAZE



TEST STATION TS-02A

- I) No. 8 AWG STRANDED COPPER WIRES THERMITE WELDED (MAX SIZE No. 15 CARTRIDGE) OR PIN BRAZED TO STEEL
- CARRIER PIPE. 2) WELD TO BE COATED WITH 2-PART EPOXY, 3-PART WAX TAPE OR COMPANY APPROVED EQUIVALENT.
- 3) ALL TEST WIRES TO EXTEND 2' BEYOND TOP OF TEST BOX. 4) WIRES TO BE PLACED AT A NOMINAL DEPTH OF 3' FROM GRADE AND PROTECTED BY 3/4" CONDUIT PROVIDED BY ESNG.

MOUND EXCESS MATERIAL TO ALLOW FOR SETTLEMENT. CONTRACTOR SHALL RESTORE ALL LANDSCAPING TO PRE-EXISTING CONDITIONS AND IN COORDINATION WITH LANDOWNER LINE LIST DISTANCE MAY VARY 3rd LIFT MAX. 12" OR LESS <u>FINAL LIFT</u> TOPSOIL WHEELED IN WITH TRACK MACHINE INSTALL 6" WIDE DITCH -2nd LIFT TAPE 24" ABOVE PIPE USE CLEAN EXCAVATED Ist LIFT SUBSOIL THAT WILL NOT DAMAGE PIPE COATING VARIES SPACE FOR PADDING OR SAND BAGS SAND BAGS OR FIRM BACKFILL -FREE OF STONE OR ROCK 36.0000 MIN.

I. BELL HOLES AND BORE PITS TO BE MECHANICALLY TAMPED ONCE 24-INCHES OF BACKFILL MATERIAL COVERS PIPE. 2. CONTRACTOR SHALL FOLLOW STATE OR LOCAL REQUIREMENTS FOR BACKFILL WITHIN STATE OR LOCAL

RIGHT-OF-WAY OR RAILROAD PROPERTY. TRENCH BACK FILL DETAIL FOR AGRICULTURAL OR RESIDENTIAL APPLICATION

CONSTRUCTION DETAILS

| REVISIONS | | 1171 | MORRIS & RITCHIE ASSOCIATES, INC. | |
|-------------|----|----------------------------------|------------------------------------|---|
| DESCRIPTION | BY | ▎█▗ ♥ ₄▐▗ ▗ ▗▃ | ENGINEERS, PLANNERS, SURVEYORS ÁND | |
| | | | LANDSCAPE ARCHITECTS | EASTERN SHORE |
| | | | 111 RUTHAR DRIVE | NATURAL GAS |
| | | | NEWARK, DE 19711 (302) 326-2200 | |
| | |]/ | (, | 500 ENERGY LANE, SUITE 200 DOVER, DE 19901 TELEPHONE (302) 734-6710 - FAX (302) 734-6745 |
| | | 1 | MRAGTA COM | 1 E E E 1 1 10 NE (002) 104-01 10 - 1700 (002) 104-0140 |

© 2025 MORRIS & RITCHIE ASSOCIATES, INC.

8" PROPOSED PIPELINE ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE

ESNG PROJ. CODE: DATE: 8/19/2025 MRA PROJECT NO: 23289 SCALE: AS SHOWN 10 OF 16 JTH/CWB SHEET: DESIGN/CHECK BY:

EXISTING MAINLINE PIPING AND INSTRUMENTATION DETAILS

NO. DATE DESCRIPTION BY

MORRIS & RITCHIE ASSOCIATES, INC.
ENGINEERS, PLANNERS, SURVEYORS AND
LANDSCAPE ARCHITECTS

111 RUTHAR DRIVE
NEWARK, DE 19711
(302) 326-2200

MRAGTA.COM
© 2025 MORRIS & RITCHIE ASSOCIATES, INC.

500 ENERGY LANE, SUITE 200 DOVER, DE 19901 TELEPHONE (302) 734-6710 - FAX (302) 734-6745

**BROPOSED PIPELINE ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE ESNG PROJ. CODE: DATE: 8/19/202

ESNG PROJ. CODE:

MRA PROJECT NO:

23289

SCALE:

AS SHOWN

DESIGN/CHECK BY:

JTH/CWB

SHEET:

11 OF 16

PROPOSED MAINLINE PIPING AND INSTRUMENTATION DETAILS

NO. DATE DESCRIPTION BY

MORRIS & RITCHIE ASSOCIATES, INC.
ENGINEERS, PLANNERS, SURVEYORS AND
LANDSCAPE ARCHITECTS

111 RUTHAR DRIVE
NEWARK, DE 19711
(302) 326-2200

MRAGTA.COM
© 2025 MORRIS & RITCHIE ASSOCIATES, INC.

EASTERN SHORE

500 ENERGY LANE, SUITE 200 DOVER, DE 19901
TELEPHONE (302) 734-6710 - FAX (302) 734-6745

8" PROPOSED PIPELINE ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE

ESNG PROJ. CODE:

MRA PROJECT NO:

23289

SCALE:


AS SHOWN

DESIGN/CHECK BY:

JTH/CWB

SHEET:

12 OF 16




INSTRUMENT IDENTIFICATION LETTERS

NOTE 1


| | FIRST-LETTER | | | SUCCEEDING-LETTER | S |
|---|------------------------------------|------------------------|-----------------------------|---|-------------------------|
| | MEASURED OR INITIATING VARIABLE | MODIFIER | READOUT OR PASSIVE FUNCTION | OUTPUT FUNCTION | MODIFIER |
| Α | ANALYSIS | | ALARM | | |
| В | BURNER, COMBUSTION | | USER'S CHOICE | USER'S CHOICE | USER'S CHOICE |
| С | USER'S CHOICE | | | CONTROL | CLOSE |
| D | USER'S CHOICE | DIFFERENTIAL | | | |
| E | VOLTAGE | | SENSOR (PRIMARY ELEMENT) | | |
| F | FLOW RATE | RATIO (FRACTION) | | | |
| G | USER'S CHOICE | | GLASS, VIEWING DEVICE | | |
| Н | HAND | | | | HIGH |
| I | CURRENT (ELECTRICAL) | | INDICATE | | |
| J | POWER | SCAN | | | |
| K | TIME, TIME SCHEDULE | TIME RATE OF CHANGE | | CONTROL STATION | |
| L | LEVEL | | LIGHT | | LOW |
| М | USER'S CHOICE | MOMENTARY | | | MIDDLE, INTERMEDIATE |
| N | UNIT | | USER'S CHOICE | USER'S CHOICE | USER'S CHOICE |
| 0 | USER'S CHOICE | | ORIFICE, RESTRICTION | | OPEN |
| Р | PRESSURE, VACUUM | | POINT (TEST) CONNECTION | | |
| Q | QUANTITY | INTEGRATE, TOTALIZE | | | |
| R | RADIATION | | RECORD | | |
| s | SPEED, FREQUENCY | SAFETY | | SWITCH | |
| T | TEMPERATURE | | | TRANSMIT | |
| U | MULTIVARIABLE | | MULTIFUNCTION | MULTIFUNCTION | MULTIFUNCTION |
| ٧ | VIBRATION, MECHANICAL ANALYSIS | | | VALVE, DAMPER, LOUVER | |
| W | WEIGHT, FORCE | | WELL | | |
| X | STATION | X AXIS | UNCLASSIFIED | UNCLASSIFIED | UNCLASSIFIED |
| Y | EVENT, STATE OR PRESENCE | Y AXIS | | RELAY, COMPUTE, CONVERT | |
| Z | POSITION, DIMENSION | Z AXIS | | DRIVER, ACTUATOR, FINAL CONTROL ELEM | |

INSTRUMENT TAG NUMBER LEGEND



| INSTRUMENT | IDENTIFICATION LETTER EXAMPLES |
|--------------------|---|
| ALARM DIFFERENTIAL | PRESSURE JTT TEMPERATURE JTT TEMPERATURE JTT POSITION JTT SAFETY INDICATING TRANSMITTER SWITCH CLOSED |

MISCELLANEOUS




- 1. REFERENCE ISA STANDARD, "INSTRUMENTATION SYMBOLS AND IDENTIFICATION". ANSI/ISA-S5.1 (LATEST EDITION).
- 2. EQUIPMENT SYMBOLS SHOWN DO NOT COVER MAJOR ENGINEERED EQUIPMENT.
- 3. SEE TO ISA STANDARD REFERENCED IN NOTE 1 FOR COMPLETE LISTING OF FUNCTION DESIGNATIONS.
- 4. HIGH HIGH AND LOW LOW ALARMS TRIP SHUTDOWNS AND ARE GIVEN SHUTDOWN SYSTEM DESIGNATIONS PER TABLE 18.
- 5. EQUIPMENT TAG NUMBERS SEQUENCED BY DIVISIONS OF 10 OR MORE TO

GENERAL INSTRUMENT OR FUNCTION SYMBOLS

| LOCATION/ACCESSIBILITY | DISCRETE INSTRUMENTS | SHARED DISPLAY AND CONTROL (DCS) | PROGRAMMABLE LOGIC CONTROL (PLC) | COMPUTER FUNCTION (RTU) |
|---|-------------------------|--|---|-------------------------------|
| FIELD MOUNTED | | | | |
| PRIMARY LOCATION NORMALLY ACCESSIBLE TO AN OPERATOR | | | | |
| PRIMARY LOCATION NORMALLY INACCESSIBLE TO AN OPERATOR | | | FÚNC TAG | FUNC TAG |
| AUXILIARY LOCATION NORMALLY ACCESSIBLE TO AN OPERATOR | FUNC | FUNC | FÚNC TAG | FUNC TAG |
| AUXILIARY LOCATION NORMALLY INACCESSIBLE TO AN OPERATOR | FUNC TAG | FUNC TAG | FÚNC TAG | FUNC TAG |
| L/LL, H/HH-INSTRUMENTS WIT LIGHTS OR INTERLOCK WITH O | | | | |


COMPUTED OR RELAY FUNCTION DESIGNATIONS

| | TABLE 20 | | |
|---------------------------------|------------------------------|-------------|--------------------------------------|
| FUNCTION DESIGNATIONS NOTE 3 | | CONVERT DES | SIGNATIONS |
| > = HIGH SELECTOR | X ⁿ = EXPONENTIAL | INPUT | ☐ ☐ OUTPUT |
| <pre></pre> | f(x) = CHARACTERIZE | (PY XXX | |
| SUMMING | = EXTRACT SQUARE ROOT | | |
| = ROOT EXTRACTION | % = PERCENT | DESIGNATION | <u>SIGNAL</u> |
| 2:1 = PROPORTIONAL | ? = BIAS (+ OR -) | A B D | ANALOG BINARY DIGITAL |
| = INTEGRAL | 1:1 = BOOST | E H | VOLTAGE HYDRAULIC |
| △ = DIFFERENTIAL | 1:3 = GAIN | 0 | CURRENT (ELECTRICAL) ELECTROMAGNETIC |
| AVE = AVERAGE | 1/dt = DERIVATIVE | Р | OR SONIC PNEUMATIC |
| I)= INTERLOCK | REV = REVERSE | R | RESISTANCE (ELECTRICAL) |
| I/P = CURRENT TO PNEUMATIC | | | |



EQUIPMENT TAGGING LEGEND

| | CATEGORY | | Y TYPE | |
|--------------------------------|--|--|--|-------------------------|
| FIRST ETTER(S) SIGNATION | DESCRIPTION | FIRST OR SUCCEEDING LETTER(S) DESIGNATION | DESCRIPTION | TAG NUMBER SERIES |
| NONE | CAVERNS | CV | CAVERNS | |
| NONE | ROTATING EQUIPMENT | | | |
| | | В | BLOWERS | |
| | | С | COMPRESSORS | |
| | | М | MOTOR, ELECTRIC | |
| | | F | FANS | |
| | | G | GENERATOR, ELECTRICAL | |
| | | GT | GAS TURBINES | |
| | | Р | PUMPS | |
| | | RE | RECIPROCATING ENGINE | |
| | | ST | STEAM TURBINES | |
| | PRESSURE VESSELS | | CIE/W ICKENIE | |
| | THEOGRE VEGGEG | A | ACCUMULATOR | |
| | | C | COALESCER | |
| | | D | | |
| | | | DRIERS/DEHYDRATORS | |
| | | F | FILTERS | |
| | | FC | FILTER/COALESCER | |
| | | FS | FILTER SEPARATOR | |
| | | ко | KNOCKOUT | |
| | | PC | PACKED COLUMN/TOWER | |
| | | PD | PULSATION DAMPENERS | |
| | | RX | REACTOR | |
| | | S | SEPARATOR | |
| | | SC | SCRUBBER | |
| | | SL | SLUG CATCHER | |
| | | SP | SPHERES | |
| | | | STORAGE/SURGE TANKS | |
| | | ST | (PRESSURE RETAINING) | |
| | | тс | TRAYED COLUMN/TOWER | |
| | | V | VESSELS | |
| | HEAT EXCHANGERS | <u> </u> | | |
| | TIETT EXOLUTION | NONE | SPACE HEATER | |
| | | <u> </u> | AIR COOLED | |
| | | AC | | |
| | | DP | DOUBLE PIPE | |
| | | MT | MULTI-TUBE | |
| | | PF | PLATE & FRAME | |
| | , | ST | SHELL AND TUBE | |
| F | FIRED EQUIPMENT | | | |
| | | В | BOILER | |
| | | ВН | ВАТН | |
| | | CA | CATALYTIC HEATER | |
| | | СН | COIL HEATER | |
| | | EL | ELECTRIC HEATER | |
| | | F | FURNACE | |
| | | <u>'</u> | 1 01417/OE | |
| | | Ev. | FORCED AIR SPACE LEATER | |
| | | FA L | FORCED AIR SPACE HEATER | |
| | | Н | HEATER | |
| | | H IN | HEATER INCINERATOR | |
| | | H IN L | HEATER INCINERATOR FLARE | |
| | | H IN L TH | HEATER INCINERATOR FLARE THERMOXIDIZER | |
| | | H IN L | HEATER INCINERATOR FLARE | |
| T | TANKS | H IN L TH | HEATER INCINERATOR FLARE THERMOXIDIZER | |
| | (ATMOSPHERIC PRESSURE) | H IN L TH | HEATER INCINERATOR FLARE THERMOXIDIZER | |
| T M | | H IN L TH WH | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER | |
| | (ATMOSPHERIC PRESSURE) | H IN L TH WH | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR | |
| | (ATMOSPHERIC PRESSURE) | H IN L TH WH | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER | |
| | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT | H IN L TH WH | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR | |
| М | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED | H IN L TH WH A J S | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN—LINE MIXER | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER | |
| М | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED | H IN L TH WH A J S ALL | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN—LINE MIXER ALL | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN—LINE MIXER ALL FLAME ARRESTOR | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN—LINE MIXER ALL FLAME ARRESTOR BUILDING | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN—LINE MIXER ALL FLAME ARRESTOR | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL FA BD | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN—LINE MIXER ALL FLAME ARRESTOR BUILDING | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL FA BD L | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN-LINE MIXER ALL FLAME ARRESTOR BUILDING LAUNCHER/SCRAPER TRAP | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL FA BD L MR | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN-LINE MIXER ALL FLAME ARRESTOR BUILDING LAUNCHER/SCRAPER TRAP METER RUNS | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL FA BD L MR O | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN—LINE MIXER ALL FLAME ARRESTOR BUILDING LAUNCHER/SCRAPER TRAP METER RUNS ODERIZER PROVERS | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL FA BD L MR O PV R | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN-LINE MIXER ALL FLAME ARRESTOR BUILDING LAUNCHER/SCRAPER TRAP METER RUNS ODERIZER PROVERS RECEIVER/SCRAPER TRAP | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL FA BD L MR O PV R S | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN—LINE MIXER ALL FLAME ARRESTOR BUILDING LAUNCHER/SCRAPER TRAP METER RUNS ODERIZER PROVERS RECEIVER/SCRAPER TRAP SILENCER | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL FA BD L MR O PV R S STR | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN-LINE MIXER ALL FLAME ARRESTOR BUILDING LAUNCHER/SCRAPER TRAP METER RUNS ODERIZER PROVERS RECEIVER/SCRAPER TRAP SILENCER STRAINER | |
| M SK | (ATMOSPHERIC PRESSURE) MIXING EQUIPMENT SKIDDED/PACKAGED EQUIPMENT | H IN L TH WH A J S ALL FA BD L MR O PV R S | HEATER INCINERATOR FLARE THERMOXIDIZER WATER HEATER AGITATOR JET MIXER STATIC IN—LINE MIXER ALL FLAME ARRESTOR BUILDING LAUNCHER/SCRAPER TRAP METER RUNS ODERIZER PROVERS RECEIVER/SCRAPER TRAP SILENCER | |



EQUIPMENT SYMBOLS

<u>EQUIPMENT TAGGING EXAMPLE</u>

| | VS | <u>C</u> – | ## | ## |
|--------------------------|----|------------|----|----|
| FIRST LETTER - | | | | |
| SUCCEEDING LETTERS —— | | 2 | | |
| TAG NUMBER - | | | | |

REVISIONS

DESCRIPTION

NO. DATE

P&ID SYMBOLS AND LEGENDS

8" PROPOSED PIPELINE



© 2025 MORRIS & RITCHIE ASSOCIATES, INC.

| ROUTE 40 REPLACEMENT | | | |
|-----------------------|-------|--------|-----------|
| NEW CASTLE COUNTY, DE | | | |
| ESNG PROJ. CODE: | | DATE: | 8/19/2025 |
| MRA PROJECT NO: | 23289 | SCALE: | AS SHOWN |

JTH/CWB

DESIGN/CHECK BY:

SHEET:

14 OF 16

ROUTE 40 RMV PIPING & INSTRUMENTATION PLAN

REVISIONS

NO. DATE DESCRIPTION BY

EN

MORRIS & RITCHIE ASSOCIATES, INC.
ENGINEERS, PLANNERS, SURVEYORS AND
LANDSCAPE ARCHITECTS

111 RUTHAR DRIVE
NEWARK, DE 19711
(302) 326-2200

MRAGTA.COM
© 2025 MORRIS & RITCHIE ASSOCIATES, INC.

EASTERN SHORE

500 ENERGY LANE, SUITE 200 DOVER, DE 19901
TELEPHONE (302) 734-6710 - FAX (302) 734-6745

8" PROPOSED PIPELINE ROUTE 40 REPLACEMENT NEW CASTLE COUNTY, DE

ESNG PROJ. CODE:

MRA PROJECT NO:

23289

SCALE:

AS SHOWN

DESIGN/CHECK BY:

JTH/CWB

SHEET:

15 OF 16

