



January 17, 2024

3002/24

Via Electronic Mail

Department of Natural Resources
and Environmental Control
Division of Water, SWDS
89 Kings Highway
Dover, DE 19901



RE: Project No. 15737
Chandler Street Pumping Station

Dear DNREC Representative:

On behalf of the Artesian Wastewater Management, we are submitting an *Application for the Construction of Wastewater Collection and Conveyance Systems* for the referenced project.

This package includes the following items:

1. Completed Application for the Construction of Wastewater Collection and Conveyance Systems
2. Narrative summary
3. One set of final construction plans signed and sealed by a Delaware Registered Professional Engineer.
4. One set of draft technical specifications.
5. One electronic copy of the Construction Plans and technical specifications.
6. Calculations and pump/performance curves for the proposed pumping station.
7. A check made payable to the State of Delaware for \$825.00 for the permit review fee.
8. A check made payable to the State of Delaware for \$300.00 for the public notice fee.

We trust this information is sufficient for your review of the project application. If you need further information, please contact me at 302-489-2353 or at scondron@verdantas.com

Very truly yours,

VERDANTAS LLC

Shaun M. Condrón
Project Manager

SMCL:rk
Z:\Project Files\AA-BZ\ArtesiaWst\15737 - Artesian Front Street Pump Station Drywe\Working\Permits\DNREC\Application Letter 2024-01-17.docx



Department of Natural Resources
and Environmental Control
89 Kings Hwy
Dover, DE 19901
dnrec.delaware.gov

Division of Water
Commercial and Government Services Section

Phone: (302) 739-9946
Fax: (302) 739-8369

INSTRUCTIONS FOR COMPLETING THE PERMIT APPLICATION FOR THE CONSTRUCTION OF WASTEWATER COLLECTION AND CONVEYANCE SYSTEMS

The following items must accompany the application. **Please note that incomplete application packages will be returned in their entirety and not reviewed until such time as all required information is received.**

- 1. A narrative summary of the intended purpose and design of the proposed facilities.
- 2. One (1) set of final construction plans and specifications, if applicable, signed and sealed by a Delaware-registered Professional Engineer, or a Delaware-registered Professional Land Surveyor for gravity systems only. One (1) electronic copy of final Plans.
- 3. One (1) electronic copy of final Plans.
- 4. The final plans must be drawn to scale showing slopes, inverts, pipe types and sizes, existing and proposed ground surfaces, tops of manholes, water lines, stormwater and stream crossings, encasements shown in plan and profile, and other information if pertinent or requested.
- 5. For pump/lift stations and force mains, include all calculations and pump/performance curves.
- 6. A check made payable to the State of Delaware for eight hundred twenty-five dollars (\$825.00), the non-refundable permit review fee. This fee covers the initial review and one follow-up review of any corrections or changes made to address the Division's comments. An additional eight hundred twenty-five dollars (\$825.00) non-refundable review fee must be submitted for resubmission of the plans if changes are made to the project which trigger a complete review of the permit application.
- 7. Your permit will have a public notice requirement if your system includes force mains or pump/lift stations. Include a check made payable to the State of Delaware for three hundred dollars (\$300.00) for the reimbursement of legal notices if the system has a force main connection or a pump/lift station.
- Please submit the completed application package, as outlined above, to DE DNREC, Division of Water, Commercial and Government Services Section, 89 Kings Highway, Dover, DE 19901. Please note, a new application, including the review fee, must be submitted if the Division's comments are not addressed or if requested supplemental information is not provided within one (1) year of the comment or request date.
- The following items must be submitted prior to permit issuance:
 - 8. Verification from the appropriate county or municipal planning authority that the project has the proper zoning approval. N/A - Project involves improvements to an existing pumping station
 - 9. A letter from the owner/operator of the wastewater facilities to which the proposed collection and conveyance facilities connect. The letter must include confirmation that the owner/operator has approved the project, that the owner/operator will take responsibility for treating and disposing of the wastewater to be conveyed and that the downstream facilities have the capacity to manage the additional flows without causing or contributing to violations of Delaware's Environmental Protection Act (7 Del. C., Chapter 60) and the regulations promulgated thereafter. This includes, but is not limited to, unauthorized discharges such as overflows at manholes and violations of the treatment system's operating permit (for example, the National Pollutant Discharge Elimination System (NPDES) permit).

- Visit us on the web at: <https://dnrec.alpha.delaware.gov/water/surface-water/>

N/A owner/operator of wastewater facilities is the applicant

**APPLICATION FOR THE CONSTRUCTION OF
WASTEWATER COLLECTION AND CONVEYANCE SYSTEMS**

Application must be complete, typewritten or clearly printed

Date Application Submitted _____

PROJECT INFORMATION			
Project Name and Location/ Address Chandler Street Lift Station Chandler Street, Milton, DE			
Tax Parcel Number(s) 235-14.19-179.00			
County <input type="checkbox"/> Kent <input type="checkbox"/> New Castle <input checked="" type="checkbox"/> Sussex		Watershed (www.dnrec.delaware.gov/swc/wa/Pages/WatershedAssessment.aspx) <input type="checkbox"/> Chesapeake Bay <input checked="" type="checkbox"/> DE Bay/Estuary <input type="checkbox"/> Inland Bays/Atl Ocean <input type="checkbox"/> Piedmont	
Sewer District or Interceptor Artesian Wastewater Management, Inc.		Wastewater Treatment/Disposal Facility Name Milton Wastewater Treatment Plant	
Anticipated Construction Start Date June 2024		Treatment/Disposal Facility Owner and Operating Permit Number Artesian Sussex Regional Recharge Facility	
Please note, construction permits expire three (3) years from the date of permit issuance.			
Are you requesting plan review and comment or WPCC Construction Permit issuance? (circle one)			
Design Flow (gallons/day) Average 250,000		Peak 1,000,000	Peak Factor 4
Basis of Design Artesian & 10 State Standards			
Description Wastewater pumping and conveyance system for an upgraded pumping station; refer to project narrative.			
OWNER/DEVELOPER			
Company Name Artesian Wastewater Management, Inc.			
Mailing Address 664 Churchmans Road			
City Newark		State DE	Zip 19702
Contact Name Mark Addison, P.E.			
E-Mail Address MAddison@artesianwater.com			
Telephone (302) 357-8721		Cell	Fax

ENGINEER

Company Name

Verdantas LLC.

Mailing Address

1060 S. Governors Ave. Suite 101

City

Dover

State

DE

Zip

19904

Contact Name

Steven H. Lewandowski, P.E.

E-Mail Address

slewandowski@verdantas.com

Telephone

(302) 489-2354

Cell

Fax

GRAVITY SEWER INFORMATION

Ownership

Public Private

Type of Sewer System

If Other, list below

Type of Pipe

Velocity (ft/sec)

NO GRAVITY SEWER IS PROPOSED WITH THIS APPLICATION

Minimum Pipe

manholes (ft)

Minimum ten foot vertical separation

Yes No

Explain any special conditions (e.g., etc.)

, etc.)

Comments

PUMP/LIFT STATION INFORMATION				
Ownership <input type="checkbox"/> Public <input checked="" type="checkbox"/> Private		Type of Wastewater <input checked="" type="checkbox"/> Residential <input type="checkbox"/> Commercial <input type="checkbox"/> Industrial <input type="checkbox"/> Other?		If Other, list below
Pump Station Flows (gallons/day) Design 1,000,000		Average 250,000	Peak 1,000,000	Peak Factor 4
Basis of Design Artesian & 10 State Standards			Pump Type Flygt Submersible	
Will peak flows be accommodated if largest unit fails? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		Pump calc's and pump curves attached? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Cycle Time (minutes) 7.57	Wet Well Detention Time (minutes) 5.69@ADF
Check valves provided on discharge line? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			Gate valves provided on discharge line? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
If not, explain alternate procedure:				
Ventilation provided in wet well? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		Dry Well? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Is an alarm system included? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Alternate source of power? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
What other provisions for emergency operations? Emergency Bypass System				
Height of Influent Above Pump (suction head) (ft) 1 ft		Height of Effluent Above Pump (discharge head) (ft) 45		Friction Loss (ft) 97.1
Pump Design Point 700 gpm @142.1' TDH	Pump Operating Point 704 gpm @143' TDH	Static Head (ft) 45	Total Head (ft) 142.1 TDH	Required Motor Horsepower (hp) 50
FORCE MAIN INFORMATION				
Type of Pipe Ductile Iron and PVC		Length (ft) +/-70 (see comments)		Diameter (in) 8
Hazen-Williams "C" Design Factor C=110, 140	Type of Joints Mechanical Joint, Bell Spigot		Velocity Under Design Conditions (ft/sec) 4.45	Minimum Pipe Cover (ft) 3.5
Air relief valves specified? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Clean-outs provided? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		Maximum distance between clean-outs (ft) N/A(see comments)	
Minimum ten foot (10') horizontal & eighteen inch (18") vertical separation from water lines maintained? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		If not, explain provisions to prevent cross-contamination:		
Comments Force main information only provided for the proposed partial main improvements within the pump station footprint. The continuation of the force main and its alignment is being prepared by the owner under a separate permit application.				

Chandler Street Pumping Station

Narrative Summary of Proposed Facilities

The Chandler Street Lift Station Upgrade project aims to enhance the efficiency and resilience of the existing wastewater conveyance system in the north side of Town. Currently, wastewater from this area flows to the Milton wastewater treatment plant. The wastewater treatment plant will be abandoned, and the wastewater redirected to Artesian Sussex Regional Recharge Facility. The proposed upgrade involves redirecting flow from the Front Street Pumping Station to the Chandler Street Lift Station through an existing force main across Wagamons Pond.

I. DESIGN STANDARDS

The wastewater pumping and conveyance system is designed in conformance with the following standards:

- A. Artesian Construction Standards.
- B. Recommended Standards for Wastewater Facilities ("Ten State Standards"), 2014 edition.

II. DEVELOPMENT DESIGN STANDARDS

1. **Demolition Work:** The existing pump station is a triplex configuration. The existing 3 pumps will be removed and replaced with 2 pumps(1 duty, 1 standby). The existing wet well will remain in use, the existing piping will be reconfigured, and a new valve vault installed adjacent to the existing structure.
2. **Improvements and Installations:**
 - o Repair and inspection of concrete surfaces within the station, including the management of any identified spalling.
 - o Sealing of any floor penetrations and the modification of floors for the installation of new systems.
 - o The introduction of two new submersible pumps in the wet well, which are controlled based on water levels.
 - o Installation of new valves, flow meters, and piping. Many of these will be situated in a below-ground enclosure outside of the lift station.

- Electrical upgrades which include new enclosures and a transfer switch, elevated to consider flood risks. A new generator will also be installed at the Elevated Water Storage Tank.
- An elevated platform, approximately 3-4 feet above the current ground level will be installed to withstand the risks associated with a 100-year flood event and will be connected to the existing platform through a walkway.



Project No. Milton Tie-in to SRRF
Project: Chandler St. Pump TDH
Subject: Milton Pump Sizing Scenario 4b: Chandler Pump Station to SRRF with total flow from Milton

By: IMKA
Date: 9/20/2023

Router: Zigzag thru Milton to RT 16 to RT 30 to SRRF
 Revised wet well water levels


Assumptions: Peak Factor = 3.7
 Assume separate pipeline for this flow, 1 duty pumps + 1 standby
 Neglect other flows in this pipeline
 Wire to Water Efficiency = 60%

SPECIFIED CONDITIONS	Comments
Pressure (ambient)	14.7 psia sea level
Inlet Pressure (P1)	0.00 psig
Inlet Temperature	68 F
Relative Humidity	36 %
Discharge Pressure (P2)	0.00 psig
Fluid	Water
Discharge Density	62.4 lb/cf
Inlet Density	62.4 lb/cf
Inlet Flow Rate, Max	835 GPM
Inlet Flow Rate, Design	700 GPM
Mass Flow Rate, Max	6964.84 lb/min
Vapor Pressure of Water	0.33889 psia

System Curve				2 Pumps on		
Flow Pt. Q (GPM)	TDH (ft)	NPSHA (ft)	HP Req'd	Q (GPM)	TDH (ft)	
1	160	50.5	35.2	5	200	241.0
2	250	57.8	35.2	7.5	400	220.0
3	340	68.3	35.2	10	600	204.0
4	430	81.9	35.3	20	800	190.0
5	520	98.8	35.3	25	1000	178.0
6	610	118.8	35.4	40	1200	161.0
7	700	142.1	35.5	50	1400	143.0
8	835	182.9	35.6	60	1600	128.0
9	900	205.1	35.7	100	1800	109.0
10	990	238.6	35.8	125	2000	86.0

50 HP 230V Flygt NP-3202.095

Flow Pt. Q (GPM)	TDH (ft)	Speed	Hz
1	100	71.2%	42.72
2	200		
3	300		
4	400		
5	500		
6	600		
7	700		
8	800		
9	900		
10	1000		



Pump & System Curves

Well 1 sp.cap.* =	0.0	gpm/ft	Motor Speed Control
Flow Pt.	7	60%	41.9
η	60%	41.9	50
BHP	50	65	460
Motor HP	50	65	460
FLA	50	65	460
Voltage	460	77.7	3
Phase	3	460	77.7
Pump	3	460	97.5
Pump	3	460	97.5
Misc	1	120	125
20% F.S.			34.1
Total			204.4
Next available size			225
			KVA

1. Confirm η & FLA for selected pump
2. Some pumps require 1.5*FLA for VFD applications- confirm w/ manf.

NP 3202 SH 3~ 275


Patented self cleaning semi-open channel impeller, ideal for pumping in waste water applications. Modular based design with high adaptation grade.



Technical specification



Curves according to: Water, pure Water, pure [100%], 39.2 °F, 62.42 lb/ft³, 1.6891E-5 ft²/s



Configuration

Motor number N3202.095 30-19-2AA-W 50hp	Installation type P - Semi permanent, Wet
Impeller diameter 200 mm	Discharge diameter 4 inch

Configuration

Pump information

Impeller diameter 200 mm
Discharge diameter 4 inch
Inlet diameter 150 mm
Maximum operating speed 3560 rpm
Number of blades 2
Max. fluid temperature 40 °C

Material

Impeller
Hard-Iron™

Project
Block

Created by AJ Wilson
Created on 1/9/2023 **Last update** 1/9/2023

NP 3202 SH 3~ 275

Technical specification



Motor - General

Motor number N3202.095 30-19-2AA-W 50hp	Phases 3~	Rated speed 3560 rpm	Rated power 50 hp
ATEX approved FM	Number of poles 2	Rated current 58 A	Stator variant 60
Frequency 60 Hz	Rated voltage 460 V	Insulation class H	Type of Duty S1
Version code 095			

Motor - Technical

Power factor - 1/1 Load 0.91	Motor efficiency - 1/1 Load 88.1 %	Total moment of inertia 3.54 lb ft ²	Starts per hour max. 30
Power factor - 3/4 Load 0.89	Motor efficiency - 3/4 Load 87.0 %	Starting current, direct starting 500 A	
Power factor - 1/2 Load 0.84	Motor efficiency - 1/2 Load 83.8 %	Starting current, star-delta 167 A	

Project
Block

Created by AJ Wilson
Created on 1/9/2023 **Last update** 1/9/2023

NP 3202 SH 3~ 275

Performance curve




Duty point

Flow
704 US g.p.m.

Head
143 ft

Curves according to: Water, pure [100%], 39.2 °F, 62.42 lb/ft³, 1.6891E-5 ft²/s



AJ Wilson


Created on 1/9/2023 Last update 1/9/2023

NP 3202 SH 3~ 275

VFD Curve



Curves according to: Water, pure, 39.2 °F, 62.42 lb/ft³, 1.6891E-5 ft²/s




Project
Block

Created by AJ Wilson
Created on 1/9/2023 Last update 1/9/2023

NP 3202 SH 3~ 275

Dimensional drawing



Project
Block

Created by AJ Wilson
Created on 1/9/2023 Last update

1/9/2023

RECEIPT

January 18, 2024

4

RCVD FROM TESI dba Artesian Wastewater \$825.00
FOR Eight Hundred twenty-five dollars and 00/100 DOLLARS
Plan review fee WPCC 3002/24 Chandler Street Lift Station

ACCT	\$	825.00
PAYMENT	\$	825.00
	\$	-

<input checked="" type="checkbox"/>
<input type="checkbox"/>
<input type="checkbox"/>

CHECK # 2103

CASH

OTHER BY Kevin Bronson

DNREC, Surface Water Discharges Section, 89 Kings Hwy, Dover, DE 19901

RECEIPT

January 18, 2024

5

RCVD FROM TESI dba Artesian Wastewater \$300.00
FOR Three Hundred Dollars and 00/100 DOLLARS
WPCC Legal Notice Reimbursement 3002/24

ACCT	\$	300.00
PAYMENT	\$	300.00
	\$	-

<input checked="" type="checkbox"/>
<input type="checkbox"/>
<input type="checkbox"/>

CHECK # 2102

CASH

OTHER BY Kevin Bronson

DNREC, Surface Water Discharges Section, 89 Kings Hwy, Dover, DE 19901