

### ISO 9001:2015 CERTIFIED

Engineers · Planners · Scientists · Construction Managers

614 N. Dupont Highway • Dover, DE 19901 • Phone 302-7+7-5999

To: Mr. Derrick Caruthers

**DNREC** 

State of Delaware 89 Kings Highway Dover, DE 19901



Date: June 21, 2024

Re: Simons Corner Pump Station Permit Application for

Construction of Wastewater Collection and Conveyance Systems

☐We are submitting	⊠Herewith	Sent via: Hand Delivered
☐We are forwarding	☐Under separate cover	
☐We are returning		

Qty.	Description
1	Application for Construction Wastewater Collection & Conveyance System
2	Checks: (1) \$825.00 payable to State of Delaware (2) \$300.00 payable to the
	State of Delaware
1 ea	Letter, Design Information & Calculations, Ltr dated 5/27/2020 to Mr. Jamie
	Winfield, Ltr dated 6/5/24 to Mr. Aaron Whitenight, KCI Technologies
1 ea	Drawings and Specifications

☐ In accordance with your request	⊠For your use
□For your review	☐For revision by you
☐ For processing	☐Please call when ready
□Plans reviewed and accepted	□Please return to this office
☐Plans reviewed and accepted as noted	☐Approval requested
Conference requested at your convenience	e

If you have any questions or for additional information, please contact me.

Aaron Whitenight, PE 302.318.1066
Aaron.whitenight@kci.com

# ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS 1352 Marrows Road, Suite 100 • Newark, DE 19711 • Phone 302-731-9176 • Fax 302-731-7807

June 6, 2024

TECHNOLOGIES

Delaware Dept. of Natural Resources & Environmental Control Division of Water Commercial and Government Services Section 89 Kings Hwy Dover, DE 19901

Attn: Mr. Derrick Caruthers

Subject: Simons Corner Pump Station Permit Application for the Construction of Wastewater

**Collection and Conveyance Systems** 

Dear Mr. Caruthers:

The purpose of this letter is to provide a narrative summary of the intended purpose and design of the proposed facilities. In summary, this permit application is for a new wastewater pumping station that will be owned and operated by the Town of Smyrna following final completion and acceptance of construction. The new Simons Corner Pump Station (SCPS) is intended to be installed in conjunction with an apartment complex project (Simons Corner Apartments) that will be under a separate permit application. This SCPS permit application is only for the pump station site, not the upstream conveyance system or downstream discharge force main. The SCPS is designed to convey flow from approximately 500 total equivalent dwelling units at ultimate buildout, of which 103 are existing and 397 are future proposed connections. This station will serve both commercial and residential customers within the Town of Smyrna.

Currently the Simons Corner Commercial shopping center is served by an onsite pumping station that conveys flow into the Town of Smyrna's gravity sewer network. The existing commercial gravity conveyance system will be realigned as part of the Simons Corner Apartments Project and be connected to the new SCPS. The existing pump station will be demolished following completion of the SCPS. As part of the overall Simons Corner Apartments Project new gravity sewer will be installed to serve several proposed apartment buildings, and the SCPS force main will be installed. The SCPS will discharge into the same manhole at Streamside Circle as the existing commercial pump station currently discharges into which is within the Town of Smyrna gravity sewer system. The SCPS basis of design is a Smith and Loveless packaged recessed pump station, with 4" DIP internal piping and 689' of 6" PVC force main piping, additional information regarding the design calculations and equipment cutsheets are provided in the permit application submission.

If you have any questions, please contact me at (302) 318-1066.

Sincerely,

KCI Technologies, Inc. Aaron Whitenight, P.E.

Design Engineer

WWW.KCL.COM



Department of Natural Resources and Environmental Control 89 Kings Hwy Dover, DE 19901 dnrec.delaware.gov

Division of Water Commercial and Government Services Section

# INSTRUCTIONS FOR COMPLETING THE PERMIT APPLICATION FOR THE CONSTRUCTION OF WASTEWATER COLLECTION AND CONVEYANCE SYSTEMS

The following items must accompany the application. Please note that incomplete application packages will be returned in their entirety and not reviewed until such time as all required information is received.

1.	A narrative summary of the intended purpose and design of the proposed facilities.
reg	One (1) set of final construction plans and specifications, if applicable, signed and sealed by a Delaware-registered Professional Engineer, or a Delaware-registered Professional Land Surveyor for gravity systems only. le (1) electronic copy of final Plans.
3.	One (1) electronic copy of final Plans.
gro	The final plans must be drawn to scale showing slopes, inverts, pipe types and sizes, existing and proposed bund surfaces, tops of manholes, water lines, stormwater and stream crossings, encasements shown in plan and offile, and other information if pertinent or requested.
5.	For pump/lift stations and force mains, include all calculations and pump/performance curves.
ref cha non	A check made payable to the State of Delaware for eight hundred twenty-five dollars (\$825.00), the non-fundable permit review fee. This fee covers the initial review and one follow-up review of any corrections or larges made to address the Division's comments. An additional eight hundred twenty- five dollars (\$825.00) in-refundable review fee must be submitted for resubmission of the plans if changes are made to the project which trigger a complete review of the permit application.
Inc	Your permit will have a public notice requirement if your system includes force mains or pump/lift stations. Clude a check made payable to the State of Delaware for three hundred dollars (\$300.00) for the mbursement of legal notices if the system has a force main connection or a pump/lift station.
Co	case submit the completed application package, as outlined above, to DE DNREC, Division of Water, immercial and Government Services Section, 89 Kings Highway, Dover, DE 19901. Please note, a new plication, including the review fee, must be submitted if the Division's comments are not addressed or if quested supplemental information is not provided within one (1) year of the comment or request date.
Th	e following items must be submitted prior to permit issuance:
	Verification from the appropriate county or municipal planning authority that the project has the oper zoning approval.
con con con reg	A letter from the owner/operator of the wastewater facilities to which the proposed collection and inveyance facilities connect. The letter must include confirmation that the owner/operator has approved the oject, that the owner/operator will take responsibility for treating and disposing of the wastewater to be inveyed and that the downstream facilities have the capacity to manage the additional flows without causing or intributing to violations of Delaware's Environmental Protection Act (7 Del. C., Chapter 60) and the gulations promulgated thereafter. This includes, but is not limited to, unauthorized discharges such as erflows at manholes and violations of the treatment system's operating permit (for example, the National Illutant Discharge Elimination System (NPDES) permit).

• Visit us on the web at: https://dnrec.alpha.delaware.gov/water/surface-water/

Document last revised: January 11, 2023

Phone: (302) 739-9946

Fax: (302) 739-8369

# APPLICATION FOR THE CONSTRUCTION OF WASTEWATER COLLECTION AND CONVEYANCE SYSTEMS

Application must be complete, typewritten or clearly printed

Date Application Submitted	6/6/2024

PROJECT INFORMATION						
Project Name and Location/ Address Simons Corner Pump 499 Jimmy Drive Smyrna, DE 19977		1				
Tax Parcel Number(s) 1-17-01900-01-7502-0	0001					
County		Watershed (www.dnrec.o	delaware.gov/swc/wa	/Pages/	Watersh	nedAssessment.aspx)
X Kent □ New Castle □ Su	ssex	☐ Chesapeake Bay 🗵	DE Bay/Estuary [	□ Inla	nd Bay	s/Atl Ocean  Piedmont
Sewer District or Interceptor		Wastewater Treatment/D	isposal Facility Name	e		
Town of Smyrna		Kent County Trea 139 Milford Necl		a, DE	E 1996	53
Anticipated Construction Start Dat	te	Treatment/Disposal Facil	lity Owner and Opera	ting Pe	rmit Nu	mber
Q3 - 2024 Kent County Permit # DE 0020338						
Please note, construction permi	ts expire	e three (3) years from the	e date of permit issu	iance.		
Are you requesting plan review	and co	mment o WPCC Constr	uction Permit issua	nce?	circle o	ne)
Design Flow (gallons/day) Average	Peak		Peak Factor			Basis of Design Town of Smyrna Standards and Specs & Ten State
150,000	327,	000	2.18			Standards
Description An 8" gravity sewer (by other proposed Smith & Loveless retake the flow along the west s Christina Apartments subdivis	ecessed ide of P	pump station (by KCI)	alongside Pondsid	de Driv	ve. A 6	" force main (by others) will
	148	OWNER/DI	EVELOPER	11	Hou	
Company Name Town of Smyrna Dela	ware					
Mailing Address  27 S Market Street Pla						
City	Za		State		Zip	
Smyrna		DE			977	
Contact Name						
Jason McNatt, Director of Public Works						
E-Mail Address jmcnatt@smyrna.delaware.gov						
Telephone Cell Fax Office 302-389-2343						

	ENGINEER							
Company Name								
KCI Technologi	es, Inc.							
Mailing Address								
1352 Marrows I	Road, Suite 10	00						
City		State		Zip				
Newark		DE		19711				
Contact Name								
Ryan Flickinger, P.E.								
E-Mail Address								
ryan.flickinger	@kci.com							
Telephone		Cell			Fax			
(302) 318-1070								
GRAVITY SEWER INFORMATION								
Ownership	Type of Sewer S	ystem			If Other, list below			
☑ Public ☐ Private	🛛 Residential I	X Commercia	ıl 🗆 Ind	ustrial   Other?				
Type of Pipe	Length (ft)	Diameter (in)	) Join	t Specification	Min.	Slope (ft/ft)	Min. Velocity (ft/sec)	
PVC SDR 26	10	8	be	ll and spigot		0.005	1.77	
PVC SDR 26 & DIP CL. 52	2,880	8	be	ell and spigot		0.005	1.77	
Minimum Pipe Cover (ft)	Number of M	fanholes	Drop m	anholes provided?	Maximum Distance Between Manholes (ft)			
5	24 *		🗵 Yes	□ No	250			
Minimum ten foot (10') he vertical separation from w			If no	ot, explain provision	s to pre	vent cross-contai	mination:	
⊠ Yes □ No								
Explain any special challe	Explain any special challenges (for example, stream, highway and/or railroad crossings, directional drilling, elevated sewers, etc.)						ted sewers, etc.)	
						_		
Comments This pumping station will be	o roplosina on ovisi	ting poorby pur	an station	However due to are	anacad (	arowth in the area	a this station is being sized	

This pumping station will be replacing an existing nearby pump station. However, due to proposed growth in the area this station is being sized larger in anticipated for development. All gravity piping and force main piping outside of the PS site will be constructed as part of a separate project for a new apartment complex (Simons Corner Apartments Project), or is existing piping within the commercial shopping center and will be redirected to the new PS as part of the Simons Corner Apartments Project. This PS is being constructed as a stand alone project, and will include approximately 10' of gravity piping from an upstream manhole into the wet well. The provided gravity sewer information is inclusive of the piping inside of the station's fencing connecting the final gravity manhole to the wet well (10') and the currently proposed upstream piping planned for installation as part of the larger separate Simons Corner Apartments Project (2,880' & 24 MHs). The actual linear footage is subject to change based on revisions to the Simons Corner Apartments Project as it continues through the plan review and permit submittal processes.

\* Piping and manholes to be installed as part of a separate Simons Corner Apartment Project.

PUMP/LIFT STATION INFORMATION										
Ownership *	Type of V	astew	ater					If Other, list below		
☑ Public ☐ Private	☐ Residential ☐ Commercial ☐ Industrial ☐ Other?				Other?					
Pump Station Flows (gallons/day)						Peak Factor				
Design	Average	0			Peak					
327,000	150,00	U		247	32	7,000		2.18		
Basis of Design Town of Smyrna Standa	rds and Sp	ecs &	Ten State	e Stan	dard	Pump Type Suct	ion Li	ft		
Will peak flows be accommand largest unit fails?	nodated if		p calc's ar es attached		ıp	Cycle Time (mi	inutes) .59		Wet Wel	Il Detention Time 17.17
X Yes □ No		X Y	es □ No	)		(time pump on wi		).5*Qout)	(cycle operat	time + time to fill ing volume at Qin = 0.5*Qout)
Check valves provided on d	lischarge lin	e?**				Gate valves pro	vided or	discharg	e line? **	*
⊠ Yes □ No						☑ Yes ☐ No				
If not, explain alternate production	cedure:									
Ventilation provided in wet	well?	Dry \	Well?			Is an alarm syst	tem inclu	ided?	Alternat	e source of power?
☑ Yes □ No		XY	es 🗆 No	,		☑ Yes □ No			▼ Yes  ▼ Yes  ▼ Yes  ▼ The second of t	□ No
What other provisions for emergency operations? Alarms will be utilized for notification of high levels, low levels, pump failure, etc. Emergency bypass quick connections will be permanently installed.										
Height of Influent Above P (suction head) (ft)	ump			of Effluent Above Pump ge head) (ft)			Friction Loss (ft)			
-15.92	2			7.93			6.69			
Pump Design Point	Pump Ope	rating	Point	Static	Hea	nd (ft)	Total Head (ft)			Required Motor
227 GPM @ 31' TDH	227 GPM	1@3	I' TDH	:	23.	85	3	30.54 Horsepower		Horsepower (hp)
			FOR	CE M	1AI	N INFORMAT	TION	v High		Steam Administration of
Type of Pipe						Length (ft) Diameter (in)			er (in)	
PVC SDR 18						689			6	
Hazen-Williams "C" Desig Factor	n Type o	f Joint	3			Velocity Under Design I Conditions (ft/sec)		Minimu	Minimum Pipe Cover (ft)	
130	bell	and	spigot			2.5				
Air relief valves specified?	Clean-	outs pr	ovided?		Maximum distance between clean-outs (ft)					
☐ Yes ☒ No ****	□ Ye	S 🖾 N	Го			N/A				
Minimum ten foot (10') horizontal & eighteen inch (18") vertical separation from water lines maintained?				If not	t, ex	olain provisions t	o preven	t cross-co	ontaminatio	on:
⊠ Yes □ No										
Comments  * Pump station is to be conveyed to the Town of Smyrna for owernship and maintenance following final acceptance of completion.  ** Check valves are included as part of the packaged Smith & Loveless Station.  *** Isolation plug valves are included in the force main flow meter and valve vault.										
**** Force main profile is planned for consistent uphill angle so no ARVs are specified.  The FM alignment and profile is within the scope of work of the Simons Corner Apartments Project.										

### 1. Design Information

Date: 6/4/2024

Simons Corner Pump Station Project:

Smyrna, Kent County, DE

Contact: Aaron Whitenight, P.E.

KCI Technologies, Inc. 1352 Marrows Road, Suite 100

Newark, DE 19711 Phone: 302.318.1066

Component: **Simons Corner Pump Station** 

Calculation By: Aaron Whitenight

Description: This calculation is to design the pump station serving the Simons Corner Apartments. The gravity sewer and force

main are to be designed by others as part of the Simons Corner Apartments Project. It is planned that ductile iron will be used for the piping within the PS and the FM will be PVC. The design flow criteria are based on Town of Smyrna Standard Specifications and Details for Water Mains, Sanitary Sewers, Storm Drains, Streets, Roads, and Electric, and 2014 Edition of Recommended Standards for Wastewater Facilities by the Great Lakes - Upper Mississippi River

Board of State and Provincial Public Health and Environmetnal Managers.

### 2. Design Basis

	EDUS	
Simons Corner Apartments	270	*Proposed
Simons Corner Commerical	103	*Existing
Liborio North Property	127	*Proposed
Total	500	

### Design Characteristics and Notes:

Pump Station and valve vault piping will be 4" DIP

Force main piping after the meter vault will be increased to 6" PVC

Basis of Design for the pumps are Smith & Loveless 4B2D\*1, 1170 RPM, 3HP

K values for fitting losses were estimated based on Table 8-4 of Fluid Mechanics Fundemntals and Applications 3rd Edition

The 6" force main discharge piping will be 689 LF discharging into an existing manhole at invert 33.33'

The gravity and pressure piping outside of the PS site will be designed and permitted seperately by First State Engineering.

### **PUMPING STATION & FORCE MAIN CALCULATION SHEET**

### A. Calculate Peak Design Flow:

Qavg = 150,000 gpd 104.17 gpm

Peak Factor 2.18

Qpeak = 327,000 gpd 227.08 gpm

227.08	Flow Rate (gom)		
0.51	Flow Rate (cfs)		

130 C -Factor (pvc)

### Analyze Pipe Diameters:

\* PVC DR-18

Pipe Diameter (in)	Actual Inside Pipe Diameter (in)	X - Sectional Area (soft)	Flow Rate (cfs)	Velocity (fps)	hL (ft/100ft)
4.00	4.23	0.10	0.51	5.18	2.627
6.00	6.09	0.20	0.51	2.50	0.446
8.00	7_98	0.35	0.51	1.46	0.120

Design Flow (gpm)

6.09 for a Velocity (V) =

Choose Pipe Diameter (in)

Pump Station Friction Losses

\* DIP - Class 52 - 4\* Pipe

Actual Diameter of Discharge Piping (inches)

\* Discharge piping includes the pipe from the pump to the connection with the 6" PVC force main

Fittings
Tee (Line Flow)
Isolation Valve (Fully Open)
Check Valve
90 deg. Elbow
45 deg. Elbow

K Value	Qty	Ktot	I.D. (in)	Size (ft)	V (ft/s)	Hloss (H.)
0.2	2	0.4	4.100	0,34	5.52	0.19
0,2	2	0.4	4.100	0,34	5.52	0.19
2	1	2	4.100	0.34	5.52	0.95
0.7	1	0.7	4.100	0.34	5,52	0.33
0.4	- 3	0.4	4.100	0.34	5.52	0.19
	K Total	3.5			7	

227

2.50

Increaser/Reducer

<u>d (in)</u>	<u>d (ft)</u>	D (in)	D (ft)	Qty	K Value	V (ft/s) H	less (ft.)
4.10	0.34	6.09	0.51	1	0.31	5.52	0.15

Pipe Length - Discharge

Size (inch)	Leg (ft)	Qty	Lea (ft)	Friction Loss (ft)	
4.10	1	40	40	1.22	

Total PS Losses (ft)

3.22

Force Main Friction Losses

6.09 Diameter of Force Main Piping (inches)

\* PVC DR-18

<u>Fittings</u> 45 deg bends Check Valve Plug Valve

K Value	Qty	<u>K</u> tot		I.D. (in)	Size (ft)	V (ft/s)	H <sub>loss</sub> (ft.)
0.	4 6		2.4	6.09	0.51	2.50	0.23
1.	5 1		1.5	6.09	0.51	2,50	0.15
0.2	7 1		0.27	6.09	0.51	2,50	0.03
	K Tot	al	4.17				

Pipe Length

Size (inch)	Lea (ft)	Qty.	Leg (ft)	Friction Loss (ft)
6.09	1	689	689	3.07

Total FM Losses (ft)

3.48

Static Head Loss:

33,33	High Point in System (ft)
9.48	"Pump Off" Elevation (ft)

<-- elevation of invert at discharge MH per Simons Comer Apartments Major Site Plan

23.85 Static Head

<u>Calculate Total Dynamic Head:</u>
\* Summation of PS Friction Losses, Force Main Friction Losses, and Static Head

3.215	Pump Station Fricton Losses (ft)
3,478	Force Main Friction Losses (ft)

Design Point:

30.54	TDH (ft)
227.08	Design Flow Rate (gpm)

\* This Flow and TDH is the desired operating point

### SYSTEM CURVE:


			Velocity in					
		Loss in P5 Pipe	PS Piping		Velocity in FM	Loss in FM	Loss in FM Pipe	
GPM	Static Loss	(ft)	(fps)	Loss in PS Fittings (ft)	Piping (fps)	Fittings (ft)	(ft)	Total
0	23,85	0.00	0.00	0.00	0.00	0.00	0.00	23,85
40	23.85	0.05	0.97	0.05	0.44	0.01	0.12	24.09
80	23.85	0.18	1.94	0.21	0.88	0.05	0.45	24,73
120	23.85	0.38	2.92	0.46	1.32	0.11	0.94	25,75
160	23.85	0.64	3.89	0.82	1.76	0.20	1,61	27.12
200	23.85	0.97	4.86	1.28	2.20	0.31	2.43	28.84
240	23.85	1,35	5.83	1.85	2.64	0.45	3.40	30,91
280	23.85	1,80	6.80	2,52	3,08	0.62	4.53	33.31
320	23.85	2,31	7.78	3.29	3,52	0.80	5.80	36.04
360	23.85	2,87	8.75	4.16	3,97	1.02	7,21	39.10
400	23.85	3,49	9.72	5.14	4.41	1,26	8,76	42.48
440	23.85	4.16	10.69	6.21	4.85	1.52	10.45	46.19
480	23.85	4.88	11.66	7.39	5,29	1.81	12.27	50.21
520	23.85	5,66	12.64	8.68	5.73	2.12	14,23	54.54
560	23.85	6,50	13.61	10.06	6,17	2.46	16,32	59.19
600	23.85	7.38	14.58	11.55	6.61	2.83	18.54	64.15

### B. Wet Well Volume

### Pump Off Elevation:

33.33	High Point in System (ft)	< elevation of invert at discharge MH per Simons Corner Apartments Major Site Plan
32,5	Ground Elevation at Wet Well (ft)	
0.83	Difference in Elevations (ft)	
14.14	Influent Invert Wet Well Elevation (ft)	
12.14	High Water Elevation (ft)	
11.64	Lag Pump On Elevation (ft)	
11,14	Lead Pump On Elevation (ft)	
9.48	Pump Off Elevation (ft)	< lead pump on elevation minus actual operating depth
8.98	Low Water Elevation (ft)	
8.48	Pump Intake Elevation (ft)	
7.94	Bottom of Wet Well (ft)	
25.40	Elevation of Pump	
16.92	Pump Suction Pipe Length (ft)	
16,46	Height of Wet Well (ft)	
-15.92	Height of influent water above Pump (ft)	
7.93	Height of Effluent Discharge Above Pump (ft)	

General Guideline Equation: Vmin = (Tmin X Qp) / 4; Tmin = 10 minutes



\*Tmin is the cycle time between pump starts, 6 starts per hour

\*Represents the peak flow rate

# of gallons in operating range

### Alternate Wet Well Volume Calcs: change to size wetwell for minimum pump run time -> when Qi = 1/2 Qo

Tmin 📗	10	
Qin	113.54	*Qin is Qout (Qpeak) divided by 2, simulating best conditions for minimum time
Qout	227.08	*Qout is Opeak because Opeak is output of wastewater at peak conditions
9:		
VmIn =	567.71	gallons
	75.90	cuft

10	Choose Wet Well Diameter, in feet
78.50	CuFt per 1' vertical in 10' dia MH
587,18	Gal per 1' vertical in 10' dia MH

0.97	Required Operating Depth
1.66	Actual Operating Depth
974.72	Actual Operating Volume (gal)

<sup>\*</sup> Note that a larger operating depth was selected than the minimum required.

<sup>\*</sup> This additional volume was added to help provide extra storage in the event of extreme peak flows and provide operators with more flexability in control settings

18.92

### C. Ventilation

\* Ventilation fans must be positive pressure feeds per Smyrna Standards

Fan Type (Intermittent(0)/Constant(1))

Volume of wet well (L\*H) = Smyrna flow rate changes/hr variable = 0,00 1,292,11 Cu. Ft

<-- height of wet well taken from Simons Corner Pump Station Plans

646.06 CFM

### Net Positive Suction Head (NPSH) & Cavitation:

\*\*Barometric Pressure of water column =

\*\*Vapor Pressure of Liquid =

\*\*Entrance Losses = Transport Friction Losses =

Pump Off Elevation =

Pump Intake CL Elevation =

Static Head =

33.90 ft 0.21 ft 1.00 ft 0.58 ft 26.61 ft -17.13 ft C Factor 130.00 Pipe Diameter: 4,10 <u>Fittings</u> Leq (ft) Size (inch) Leg (ft) 4.10 16.92 16.92 Intake Losses 4.10

Total Leq (ft)

Design NPSHr =

Actual NPSHa =

\* Actual NPSH should be no lower than

7,00 14.98

\* This value is the specified operating NPSH given by the pump manufacturer


\* Due to uncertainties, this value must 20% greater than NPSH Required (Refer below for determining safety factor.)

### Basis of Design for Pump:

Pump Make, Model, Power S&L 4B2D\*1, 1170 RPM, 3HP 8-5/8" Impeller GPM Head (ft) 0 20 36.5 40 35.5 60 80 34.5 100 140 160 180 200 31.5 220 30,75 240 260 29.25 280 300 27.8 320 340 360 380 400 420 440 460 480

500

### Simon's Corner PS - Pump & System Curve





14040 Santa Fe Trail Drive Lenexa, KS 66215 smithandloveless.com

**TOTAL STATION FULL LOAD AMPS** 

97.0

121.0

149.0

173.0

EVERLAST™
Wet Well Mounted Pump Station
Design Factors
Electrical Service Data

48.5

60.5

74.5

86.5

110.5 136.5

# ELECTRICAL SERVICE DATA EVERLAST™ WET WELL MOUNTED PUMP STATION

# MAIN PUMP MOTOR SIZE

15

20 25

30

40

50

**208 VOLT 230 VOLT 460 VOLT** RATED HP EACH 10.7 1 21.4 23.6 1-1/2 27.6 25.0 12.5 29.4 26.6 13.3 2 3 35.6 32.2 16.1 5 47.8 43.4 21.7 7-1/2 62.8 57.0 28.5 69.0 34.5 10 76.0

106.8

133.2

164.0


190.4

### ASSUMING 3 KVA LOAD FOR CONTROLS

NOTE: Refer to applicable station drawing for size of electrical conduit connection.

# Pump Curve





Kent



County

## Department of Public Works

Engineering Division
Wastewater Facilities Division

(302) 744-2430 Fax (302) 736-2100 (302) 335-6000 Fax (302) 335-0365 555 Bay Rd., Dover, DE 19901 139 Milford Neck Rd., Milford, DE 19963

June 5, 2024

Aaron Whitenight, P.E. KCI Technologies, Inc. 1352 Marrows Road Suite 100 Newark, DE 19711

RE: Town of Smyrna - Simons Corner Pump Station (PS) Project

Dear Mr. Whitenight:

In response to your e-mail request to our Office, dated May 30, 2024, please be advised there is adequate sanitary sewer transmission and treatment capacity in the Kent County system for this Project.

As you indicated in this same e-mail, this Project and the local collection/transmission systems are the responsibility of the Town of Smyrna.


Please contact me at phone no. (302) 744-2430, if you have any questions.

Sincerely,

Brian L. Hall

Engineering Project Manager II

NPSHR Curve Non-Clog Pump 4B2D – 1170 RPM January, 2012





May 27, 2020

Simons Corner Apartments, LLC c/o Jamie Winfield 301 N. Ashview Lane Wilmington, DE 19807

Dear Mr. Winfield,

At their monthly meeting held on May 27, 2020, the Smyrna Planning Commission granted Preliminary Major Site Plan approval for the construction of ten (10) three-story apartment buildings totaling 270 units, a 7,040 sq. ft. community/office building, three 10-stall parking garages, and associated site improvements, but subject to the following conditions:

- 1.) That the applicant obtain a variance from the Board of Adjustment for seven of the proposed apartment buildings to be constructed greater than the allowable 15 ft. front setback along one of the streets.
- 2.) That the applicant obtain a variance from the Board of Adjustment to exceed on twelve instances the maximum allowable ten parking spaces in a row without a landscaped island.
- 3.) That marked pedestrian crosswalks be provided at the entrances to the proposed off-street parking lots.
- 4.) That two additional patio areas (minimum of 400 sq. ft. in size) be provided behind the two 24-unit apartment buildings closest to the traffic circle.
- 5.) That the proposed dumpsters be screened by a brick masonry enclosure.
- 6.) That at least 15,434.05 sq. ft. of open space amenities be provided on the site; and if feasible, the expansion of the proposed dog park.
- 7.) That parking lot lights with acorn-shaped luminaires be provided in all off-street parking lots.
- 8.) That street lights be provided at minimum every 60 linear feet on center along thoroughfares and boulevards.
- 9.) That at a minimum eight (8) bicycle racks are provided, with at least one situated at each parking area of 20 parking spaces.

GERALD L. BROWN VALERIE M. FORBES · TABITHA J. GOTT · MARGARET B. MANN · WILLIAM D. PRESSLEY SR. · MICHAEL A. RASMUSSEN 27 SOUTH MARKET STREET PLAZA · P.O. BOX 307 · SMYRNA, DELAWARE 19977

If you have any questions or concerns related to this letter (or the conditions outlined thereto) place contact Jeremy Rothwell, Senior Planner, at <a href="mailto:jrothwell@smyrna.delaware.gov">jrothwell@smyrna.delaware.gov</a>, or by phone at (302) 389-2332.

Warm regards.

George DeBenedictis

Manager, Department of Building & Inspections

H
Ш
C

	June 24	th, 2024				67		
RCVD FROM	KCI Tec	hnologies, INC.	\$825.00					
	Eight H	undred twenty-f	DOLLARS					
FOR	Plan review fee WPCC 3049/24 Simons Corner Pump Station							
ACCT	\$	825.00	х	CHECK#	666360	3360		
PAYMENT	\$	825.00		CASH				
	\$			OTHER	ву	Kevin Bronson		

DNREC, Commercial & Government Services Section, 89 Kings Hwy, Dover, DE 19901

# RECEIPT

	June 24	th, 2024				68	
RCVD FROM	KCI Tec	hnologies, INC.	\$300.00				
	Three H	lundred Dollars a	DOLLARS				
FOR	WPCC Legal Notice Reimbursement 3049/24						
ACCT	\$	300.00	х	CHECK #	666359		
PAYMENT	\$	300.00		CASH			
	\$	-		OTHER	BY	Kevin Bronson	

DNREC, Commercial & Government Services Section, 89 Kings Hwy, Dover, DE 19901