

CARROLL BANK STABILIZATION PROJECT OCEAN VIEW, DE INLAND BAY WATERSHED LORD BALTIMORE HUNDRED

PROJECT LOCATION:

The project is located at 805 Hickman Drive in Whites Creek Manor, Ocean View, Delaware. The parcel has a conjoining parcel boundary approximately 90.0 linear ft. with Whites Creek. This parcel is the primary residence for Anges M. Carroll, TM# 134-12.00-875.00. The project latitude and longitude coordinates area as follows: 38.552409, -75.099951.

PROJECT SCOPE:

The project will involve stabilizing 90.0 linear feet of Whites Creek bank by using R6 riprap. This will be accomplished by first establishing the necessary erosion and sediment control device for the project. The bank will be cleared and grubbed of vegetation prior to re-grading to the design slope. Geotextile will be placed on the slope and covered with R6 riprap. The riprap will extend channelward of mean high tide approximately 12.0ft to establish the revetment toe. The riprap will be placed approximately 29" thick over the slope and toe. All upland areas will be finished grades and stabilized with grass seed and mulched using crimped straw. All unsuitable material and vegetation will be removed and disposed of in a DNREC appropriate manner.

All comments provided from the Regional General Conditions notification process have been incorporated into the plan construction notes.

The material being placed will not result in a statistically significant reduction, accounting for natural variations, in biological, chemical, or habitat quality as measured or predicted using appropriate assessment protocols.

The District has concurrently submitted to the State of Delaware for wetland fill impacts and is waiting for their response.

23818 SHORTLY ROAD, GEORGETOWN, DE 19947 • office: 302.856.2105 • fax: 302.856.0951 • SUSSEXCONSERVATION.ORG

PREPARE, PROTECT, PRESERVE.

Enclosed you will find the following items for your consideration:

- ACOE application
 PDF Project plan link
- Google Earth directions to the site location.
 Websoil Survey soil mapping results.
 PCN submittal emails and their results

- 6. IPAC Report

VICINITY MAP:



WETLANDS AND SUBAQUEOUS LANDS SECTION PERMIT APPLICATION FORM

For Subaqueous Lands, Wetlands, Marina and 401 Water Quality Certification Projects

State of Delaware Department of Natural Resources and Environmental Control Division of Water

Wetlands and Subaqueous Lands Section



APPLICATION FOR APPROVAL OF SUBAQUEOUS LANDS, WETLANDS, MARINA AND WATER QUALITY CERTIFICATION PROJECTS

PLEASE READ THE FOLLOWING INSTRUCTIONS CAREFULLY

Application Instructions:

- 1. Complete each section of this basic application and appropriate appendices as thoroughly and accurately as possible. Incomplete or inaccurate applications will be returned.
- 2. All applications must be accompanied by a scaled plan view and cross-section view plans that show the location and design details for the proposed project. Full construction plans must be submitted for major projects.
- 3. All applications must have an original signature page and proof of ownership or permitted land use agreement.
- 4. Submit an original and two (2) additional copies of the application (total of 3) with the appropriate application fee and public notice fee* (prepared in separate checks) to:

Department of Natural Resources and Environmental Control Wetlands and Subaqueous Lands Section 89 Kings Highway Dover, Delaware 19901

*Application and public notice fees are non-refundable regardless of the Permit decision or application status.

5. No construction may begin at the project site before written approval has been received from this office.

Helpful Information:

| 1. | Tax Parcel Information: | New Castle County | (302) 395-5400 |
|----|-------------------------|-------------------|----------------|
| | | Kent County | (302) 736-2010 |
| | | Sussex County | (302) 855-7878 |
| 2. | Recorder of Deeds: | New Castle County | (302) 571-7550 |
| | | Kent County | (302) 744-2314 |
| | | Sussex County | (302) 855-7785 |

- 3. A separate application and/or approval may be required through the Army Corps of Engineers. Applicants are strongly encouraged to contact the Corps for a determination of their permitting requirements. For more information, contact the Philadelphia District Regulator of the Day at (215) 656-6728 or visit their website at: <u>http://www.nap.usace.army.mil/Missions/Regulatory.aspx</u>.
- For questions about this application or the Wetlands and Subaqueous Lands Section, contact us at (302) 739-9943 or visit our website at: <u>http://www.dnrec.delaware.gov/wr/Services/Pages/WetlandsAndSubaqueousLands.aspx</u>. Office hours are Monday through Friday 8:00 AM to 4:30 PM, except on State Holidays.

APPLICANT'S REVIEW BEFORE MAILING

DID YOU COMPLETE THE FOLLOWING?

| Х | Yes | BASIC APPLICATION |
|---|------|---|
| Х | Yes | SIGNATURE PAGE (Page 3) |
| Х | Yes | APPLICABLE APPENDICES |
| Х | Yes | SCALED PLAN VIEW |
| Х | Yes | SCALED CROSS-SECTION OR ELEVATION VIEW PLANS |
| Х | _Yes | VICINITY MAP |
| X | Yes | COPY OF THE PROPERTY DEED & SURVEY |
| Х | _Yes | THREE (3) COMPLETE COPIES OF THE APPLICATION PACKET |
| X | Yes | APPROPRIATE APPLICATION FEE & PUBLIC NOTICE FEE (Separate checks made payable to the State of Delaware) |

Submit 3 complete copies of the application packet to:

Department of Natural Resources and Environmental Control Wetlands and Subaqueous Lands Section 89 Kings Highway Dover, Delaware 19901

Before signing and mailing your application packet, please read the following:

The Department requests that the contractor or party who will perform the construction of your proposed project, if other than the applicant, sign the application signature page along with the applicant in the spaces provided. When the application is signed by the contractor as well as the applicant, the Department will issue the Permit to both parties. For Leases, the contractor will receive a separate construction authorization that will make them subject to all of the terms and conditions of the Lease relating to the construction

Section 1: Applicant Identification

- 1. Applicant's Name: Agnes Carroll Mailing Address: B05 Hickamn Drive Ocean View, DE 19970
- 2. Consultant's Name: <u>Jim Elliott</u> Mailing Address: <u>23818 SHORTLY ROAD</u> Georgetown, DE 19947
- 3. Contractor's Name: Matt Messina Mailing Address: 23818 SHORTLY ROAD Georgetown, DE 19947

| Telephone #: | 302-228-5326 |
|-------------------|---------------|
| Fax #: | |
| E-mail: carrollag | nes@amail.com |

Company Name: Sussex Conservation District Telephone #: 302-856-2105 Fax #: 302-856-0951 E-mail: jim.elliott@sussexconservation.org

Company Name: <u>Sussex Conservation</u> District Telephone #: 302-856-210! Fax #: 302-856-0951 E-mail: matt.messina@sussexconservation.org

Section 2: Project Description

- 4. Check those that apply:
- New Project/addition to existing project? Repair/Replace existing structure? (If checked, must answer #16)
- 5. Project Purpose (attach additional sheets as necessary): See attached project narrative.
- 6. Check each Appendix that is enclosed with this application:

| A. Boat Docking Facilities | | G. Bulkheads | N. Preliminary Marina Checklist |
|---------------------------------|--------------|---------------------------------|---------------------------------|
| B. Boat Ramps | | H. Fill | O. Marinas |
| C. Road Crossings | \checkmark | I. Rip-Rap Sills and Revetments | P. Stormwater Management |
| D. Channel Modifications/Dams | | J. Vegetative Stabilization | Q. Ponds and Impoundments |
| E. Utility Crossings | | K. Jetties, Groins, Breakwaters | R. Maintenance Dredging |
| F. Intake or Outfall Structures | \square | M. Activities in State Wetlands | S. New Dredging |

Section 3: Project Location

7. Project Site Address: 805 Hickamn Drive Ocean View, DE 1997

| County: | \square N.C. | Kent | Sussex | |
|-------------------|----------------|----------|-------------|--|
| Site owner name | (if differ | ent from | applicant): | |
| Address of site o | wner: | | | |

8. Driving Directions: see attached Google Earth Driving instructions

(Attach a vicinity map identifying road names and the project location)

9. Tax Parcel ID Number: 134-12.00-875.00

Subdivision Name: Whites Creek Manor

| WSLS Use | e Only: | Permi | t #s: | | | | | | _ |
|--|------------|-------|---------------|-------------|------------|------|------|------|------|
| Туре | SP 🗆 | SL 🗆 | SU 🗆 | WE 🗆 | WQ 🗆 | LA 🗆 | SA 🗆 | MP 🗆 | WA 🗆 |
| Corps Permit: SPGP 18 		20 		Nationwide Permit #: Individual Permit # Received Date: Project Scientist: | | | | | | | | | |
| Fee Receiv | ved? Yes 🗆 | No 🗆 | Amt: \$ | | Receipt #: | | | | |
| Public No | tice #: | | Public Notice | e Dates: ON | | OFF | 1 | | |

| Section 3: Project Locat | ion (Continued) | | | | | |
|--|--|--|----------------------|----------------|------------------------|--|
| 10. Name of waterbody at Project Location: Whites Creek waterbody is a tributary to: Indian River Bay | | | | | | |
| 11. Is the waterbody: | 🗸 Tidal 🛛 Non-tidal 🦳 Wate | rbody width at mean low o | r ordinar | y high wa | ter_100ft | |
| 12. Is the project: | On public subaqueous lands? In State-regulated wetlands? | ☐ On private subaqueous ✓In Federally-regulated v | lands?* wetlands? | | | |
| *If the project is on privat | e subaqueous lands, provide the nan | ne of the subaqueous lands | owner: | | | |
| (Written permission from | the private subaqueous lands owner | must be included with this | applicati | on) | | |
| 13. Present Zoning: | ☐ Agricultural √Residential | 🗆 Commercial 🛛 Indu | ıstrial | C Other | | |
| Section 4: Miscellaneous | | | | | 498 | |
| A. List the names an project (attach addition Daniel Collins, 803 Hickman Drive, Oc James F nagel III, 3698 Culer Court, 8 | nd complete mailing addresses of th onal sheets as necessary): Stewartstown, PA 1736 | he immediately adjoining | property | owners o | on all sides of the | |
| 15. Provide the names of I Matt Jones - DNREC | DNREC and/or Army Corps of Engine | ers representatives whom yo | u have di | scussed th | e project with: | |
| A. Have you had a St B. Has the project be *If yes, what was | ate Jurisdictional Determination perf en reviewed in a monthly Joint Perm s the date of the meeting? | ormed on the property? it Processing Meeting? | | □ Yes □ Yes | √No √No | |
| 16. Are there existing stru *If yes, provide t | tetures or fill at the project site in sul he permit and/or lease number(s): | baqueous lands? | 🗌 Yes | √No | | |
| *If no, were strue | ctures and/or fill in place prior to 196 | 59? 🗌 Yes | 🗆 No | | | |
| 17. Have you applied for□ No | or obtained a Federal permit from th ng Issued Denie | e Army Corps of Engineer d Date: sumitted to va | s? ious agenci | es for regior | nal conditions1/3/2024 | |
| Type of Permit: <u>NWP 13 Bar</u> | k Stablization | Federal Permit or ID #: | | | | |
| 18. Have you applied for ↓ No □ Pendi | permits from other Sections within I ng | DNREC? d Date: | _ Permi | t or ID #: | | |
| Type of permit (circle all | that apply): Septic Well N | VPDES torm Water | | | | |
| Other: Standard Plan | | | | | | |

Section 5: Signature Page

19. Agent Authorization:

If you choose to complete this section, all future correspondence to the Department may be signed by the duly authorized agent. In addition, the agent will become the primary point of contact for all correspondence from the Department.

| I do not wish to authorize an agent to act on my beha | lfX | | | |
|---|--|--|--|--|
| I wish to authorize an agent as indicated below X | | | | |
| I, Agnes Carroll , hereby | y designate and authorize Jim Elliott | | | |
| to act on my behalf in the processing of this applicati | (Name of Agent) on and to furnish any additional information requested by the | | | |
| | | | | |
| Authorized Agent's Name: Jim Elliott | Telephone #: 302-856-2105 EXT 105 | | | |
| Mailing Address: 23818 Shortly Roac Fax #: | | | | |
| Georgetown, DE 19947 | E-mail: jim.elliott@sussexconservation.org | | | |

20. Agent's Signature:

I hereby certify that the information on this form and on the attached plans are true and accurate to the best of my knowledge. I further understand that the Department may request information in addition to that set forth herein if deemed necessary to appropriately consider this application.

Agent's Signature

1/24/2024

21. Applicant's Signature:

I hereby certify that the information on this form and on the attached plans are true and accurate to the best of my knowledge and that I am required to inform the Department of any changes or updates to the information provided in this application. I further understand that the Department may request information in addition to that set forth herein if deemed necessary to appropriately consider this application. I grant permission to authorized Department representatives to enter upon the premises for inspection purposes during working hours.

Applicant's Signature arroll 05

1-15-24 Date

22. Contractor's Signature:

I hereby certify that the information on this form and on the attached plans are true and accurate to the best of my knowledge, and that I am required to inform the Department of any changes or updates to the information provided in this application. I further understand that the Department may request information in addition to that set forth herein if deemed necessary to appropriately consider this application.

ESSINA

Print Name

1/24/2024 Date

Rip-Rap Sills and Revetments

Please respond to each question. Questions left blank may result in the application being returned as incomplete. In addition, the answers to all of the questions in this Appendix must correspond accurately to the information on the plan and section view drawings for the project.

1. Will the project be:

X New Construction (un-stabilized shoreline)

____ Repair or Replacement of an Existing Rip-Rap Structure or Rubble

____ Repair or Replacement of an Existing Bulkhead

(If repair or replacement, submit photographs of the entire existing structure).

2. How many linear feet of shoreline are proposed to be stabilized? 90.0FT

3. Is the project a: X Standard rip-rap revetment ____ Free-standing sill

4. Describe the existing shoreline:

The existing shoreline consist of phragmites, which has been treated in the summer 2023 by using an aquatic herbicide. There is evidence of active erosion with Spartina Alternaflora present intermittently at the bottom of the slope and a couple mature trees at the top of bank.

- 5. What is the total number of cubic yards of rip-rap that will be used? <u>199.34CY</u>
- What is the number of cubic yards of rip-rap per running foot of shoreline? <u>2.21 CY/FT</u>
 (See page 4 for a guide to calculating total cubic yards and cubic yards per running foot).
- 7. What will be the average weight of the stone used for the:

Armor stone: <u>165 LBS.CF</u> Core stone: <u>165 LBS/CF</u> [If material other than stone, such as prefab geo-grid or other similar product is proposed, please describe here and include photographs or a brochure. The Department strongly discourages the use of broken concrete, cinderblocks or other materials that are less dense than stone, more apt to move off site due to currents or wave action, and/or are not aesthetically pleasing or in keeping with the natural environment.] Describe:

| 8. | For Standard Revetments answer A–F, below: (for Sill projects, skip to Question #9) A. How many linear feet will the structure extend channelward of: Mean High Water: <u>12.51FT</u> Mean Low Water: <u>0.0FT</u> Ordinary High Water: (for non-tidal waters) | | | | | | | | |
|----|---|--|--|--|--|--|--|--|--|
| | B. How many square feet of the structure will be located: Channelward of Mean High Water: <u>1105.34SF</u> Channelward of Mean Low Water: <u>0.0SF</u> Channelward of Ordinary High Water: <u>969.4 sf</u> (for non-tidal waters) On vegetated wetlands: | | | | | | | | |
| | C. If y | Will the revetment be backfilled? Yes \underline{X} No ves, complete Appendix H and include it in your application. | | | | | | | |
| | D. | Will filter cloth be used behind the rip-rap structure? X Yes No | | | | | | | |
| | E. | What is the average slope of the existing bank? 2.3 | | | | | | | |
| | F. | What is the proposed slope of the rip-rap revetment? <u>2.3</u> (See page 3 for a guide to calculating slopes). | | | | | | | |
| 9. | Sill Pro | ojects: | | | | | | | |
| | А. | What is the base width of the proposed structure: | | | | | | | |
| | В. | What is the top width of the proposed structure: | | | | | | | |
| | С. | How many square feet of the structure will be located: | | | | | | | |
| | | Channelward of Mean High Water: Channelward of Mean Low Water: Channelward of Ordinary High Water: (for non-tidal waters) On vegetated wetlands: | | | | | | | |
| | D. | What will be the average height of the structure: | | | | | | | |
| | E. | How much of the structure (in inches) will extend vertically above: | | | | | | | |
| | Me | ean High Water: Ordinary High Water: (for non-tidal waters) | | | | | | | |
| | F. G. | Are breaks or notches proposed in the sill to allow for greater flushing? Yes No Will fill material be placed behind the sill? Yes No If yes, complete appropriate appendix. | | | | | | | |
| | | | | | | | | | |

H. Will wetland vegetation be planted behind the sill? ____ Yes ____ No If yes, complete Appendix H and include it in your application.

10. Construction Techniques (Complete for both Revetment and Sill Projects):

A. Will any dredging be required? ____ Yes \underline{X} No

If yes, please include appropriate dredging Appendix with your application).

B. Please describe the sequence of construction and any techniques that will be utilized to minimize adverse impacts on the aquatic environment, and to preserve existing vegetation (particularly woody vegetation) along the shoreline:

The material being placed will not result in a statistically significant reduction, accounting for natural variations, in biological, chemical, or habitat quality as measured or predicted using appropriate assessment protocols.

CALCULATIONS

RUN = Base width of the structure (in feet) RISE = Vertical height of the structure (in feet)

I. How to calculate total cubic yards:

0.5 * RUN * RISE * Linear feet of shoreline stabilized/27 = Total Cubic Yards

II. How to calculate cubic yards per running foot of shoreline:

Total # Cubic Yards/ Linear feet of shoreline = Cubic yards per running foot

III. How to calculate slope: Slope = RUN/RISE

EXAMPLE:

If we propose to stabilize 100 linear feet of shoreline with a rip-rap revetment that has a basewidth of 6 feet and a height of 3 feet:

0.5 * 6 * 3 * 100/27 = 33.33 Total Cubic Yards

- II. 33.33/ 100= 0.333 Cubic Yards per running foot
- III. 6/3= Slope of 2

Google Maps

DE-1, Delaware to 805 Hickman Dr, Millville, DE 19970

Drive 53.8 miles, 1 hr 12 min

CARROLL SHORELINE REVETMENT PROJECT



Map data ©2024 Google

5 mi L

DE-1 Delaware

Follow DE-1 S/Bay Rd and US-113 S/N Dupont Blvd to Cricket St in Sussex County

| 1 | 1. | Head north on DE-1 N |
|---|----|--|
| | | 1.5 mi |
| 7 | 2. | Take exit 91 for DE-9 toward Kitts Hummock/Little Creek |
| ← | 3 | 0.2 mi |
| | 0. | 0.3 mi |
| * | 4. | Merge onto DE-1 S/Bay Rd |
| | | 12.0 mi |
| Х | 5. | Use the right lane to take the US-113 S/DE-1BUS ramp to Milford/Georgetown |
| | | 0.3 mi |

Continue onto DE-1 BUS S/US-113 S/N Dupont Blvd
Continue to follow US-113 S/N Dupont Blvd
Pass by AutoZone Auto Parts (on the right in 27.6 mi)

```
28.8 mi
```

Take State Rd 20 and DE-26 E to Harbor Rd

| _ | 7 | | 19 min (10.9 mi) |
|----------------|----------|--|------------------|
| 5 | 7. | Turn left onto Cricket St | |
| ر ا | 8. | Turn right onto State Rd 20 | 0.1 mi |
| 5 | 9. 1 | Slight left onto DE-26 E/Vines Creek F Continue to follow DE-26 E | 2.2 mi Rd |
| ← | 10. | Turn left onto Rd 351/Clubhouse Rd | 7.5 mi |
| с) | 11. | Turn right onto Old Mill Rd | 0.4 mi |
| ← | 12. | Turn left onto Bridge Ln | 0.1 mi |
| ¢ | 13. 1 | Turn right onto Harbor Rd Destination will be on the right | 0.2 mi |
| | | | 0.4 mi |

VIC MAP



Communities

Tax Parcels



Map data © OpenStreetMap contributors, Microsoft, Facebook, Inc. and its affiliates, Esri Community Maps contributors, Map layer by Esri, Sussex County Government



PLAN INDEX MAP

SHEET INDEX

| <u>Sheet no.</u> | TITLE |
|------------------|---|
| C-000 | COVER SHEET |
| C-100 | SITE PLAN |
| C-200 | PROFILE / SECTION VIEW CONSTRUCTION DETAIL |
| C-300 | SECTION VIEW PLAN |
| C-700 | EROSION & SEDIMENT CONTROL PLAN |
| C-701 | EROSION & SEDIMENT CONTROL DETAILS & NOTES |
| C-702 | EROSION & SEDIMENT CONTROL DETAILS & NOTES |
| C-703 | EROSION & SEDIMENT CONTROL DETAILS & NOTES |
| EX-1 | WETLAND SITE PLAN EXHIBIT |
| EX-2 | WETLAND PROFILE / SECTION VIEW DETAILS PLAN EXHIBIT |
| EX-3 | WETLAND SECTION VIEW PLAN EXHIBIT |

REGIONAL CONDITION FOR NWP (13) BANK STABILIZATION

CONDITION A ANY PCN TO THE CORPS OF ENGINEERS THAT DOES NOT UTILIZE A NON-STRUCTURAL BANK STABILIZATION METHODS (E.G. VEGETATION OR COMBINATION OF VEGETATION AND ROCK) MUST INCLUDE AN ANALYSIS DEMONSTRATING THAT SUCH MEASURES WERE NOT PRACTICABLE AND/OR APPROPRIATE.

CONDITION B THIS NWP MAY NOT BE USED TO AUTHORIZE ANY STABILIZATION ACTIVITY WHERE NO DEMONSTRABLE EROSION IS EVIDENT.

CONDITION C A PCN SHALL BE PROVIDED TO THE CORPS FOR ALL IN-WATER STRUCTURES, SUCH AS BIOENGINEERING, BREAK WATERS, SILLS, GABION BASKETS, WAVE ATTENUATION DEVICES, OR ANY COMBINATION OF BANK STABILIZATION TECHNIQUES, PLACED OFFSHORE OF THE BANKS FOR THE PURPOSE OF EROSION CONTROL OR PREVENTION.

THE PROJECT IS LOCATED IN FEMA FLOOD ZONE AE (ELEV. 7), FEMA MAP # 10005C0511K

CARROLL SHORELINE REVETMENT PROJECT

WHITES CREEK / INLAND BAY WATERSHED OCEAN VIEW, DELAWARE

LEGE

| EXISTING | |
|--|-----------------------------------|
| BUILDING | |
| BRIDGE | |
| BOTTOM WIDTH LEFT | |
| BOTTOM WIDTH RIGHT | |
| CENTERLINE DITCH | |
| CENTERLINE DITCH STATION MAJOR | 0+00 |
| CENTERLINE DITCH STATION MINOR | 0+50 |
| CENTERLINE ROAD | т |
| CONTOUR MAJOR | 10 |
| CONTOUR MINOR | 10 |
| CONCRETE | |
| EASEMENT | |
| EDGE OF PAVEMENT | |
| EDGE OF GRAVEL | |
| FENCELINE | |
| GEOMORPHOLOGY FEATURE | |
| HYDROLOGIC DRAINAGE AREA | |
| | |
| HYDROLOGIC SOIL TYPE | |
| HYDROLOGIC SOIL GROUP | |
| HYDROLOGIC TIME OF CONCENTRATION MAILBOX | 0 |
| MARSHLINE | |
| ORDINARY HIGH WATER | |
| PROPERTY LINE | |
| RAILROAD TRACKS | |
| RIPRAP | |
| SHEETPILE | |
| SIDEWALK | |
| SIGN | |
| STORMWATER PIPE | |
| STORMWATER STRUCTURE | |
| TAX DITCH RIGHT-OF-WAY | |
| TAX DITCH SPECIAL RIGHT-OF-WAY | |
| TOP OF BANK RIGHT | |
| TOP OF BANK I FET | |
| | |
| TEXT | TEXT |
| ITTI ITY COMMINICATION CARLE | TI ICI |
| | |
| | -0- |
| | R.E.S.A.A |
| UTILITY: ELECTRIC | EU>00 |
| UTILITY: GAS | CV (G) - GAS - GAS - GAS - |
| UTILITY: SANITARY SEWER | S 55 |
| UTILITY: WATER | Š ^{H.} ₩ |
| WATERSHED DRAINAGE AREA | ♥ ↓↓ |
| WETLAND | |
| WOODSLINE | |
| | |

| GEND | |
|---------------------------------------|--|
| PROPOSED | |
| BUILDING | |
| BRIDGE | |
| BOTTOM WIDTH LEFT | |
| BOTTOM WIDTH RIGHT | |
| CENTERLINE DITCH | |
| CENTERLINE DITCH STATION MAJOR | 0+00 + |
| CENTERLINE DITCH STATION MINOR | 0+50 + |
| CONTOUR MAJOR | 10 |
| CONTOUR MINOR | 10 |
| CONCRETE | |
| EASEMENT | |
| EDGE OF PAVEMENT | |
| EDGE OF GRAVEL | |
| FENCELINE | |
| GEOMORPHOLOGY FEATURE | |
| GRADE PROFILE | |
| HYDROLOGIC DRAINAGE AREA | |
| HYDROLOGIC DRAINAGE AREA | |
| HATCH HYDROLOGIC DRAINAGE AREA | |
| LANDUSE HYDROLOGIC TIME OF | |
| CONCENTRATION NORMAL WATER SURFACE | |
| ELEVATION RIPRAP | |
| SIDEWALK | |
| SIGN | - 0 - |
| STORMWATER PIPE | |
| STORMWATER STRUCTURE | |
| TAX DITCH RIGHT-OF-WAY | |
| TAX DITCH SPECIAL RIGHT-OF-WAY | |
| TOP OF BANK LEFT | |
| TOP OF BANK RIGHT | |
| TREE | |
| TEXT | TEXT |
| WATERSHED DRAINAGE AREA | |
| WOODSLINE | |
| ESTIMATED CUT | |
| ESTIMATED FILL | |
| COMPOST LOG | |
| LIMIT OF DISTURBANCE | |
| TEMPORARY CONSTRUCTION - | TCE TCE TCE TCE TCE TCE |
| SILT FENCE | SF S |
| SUPER SILT FENCE | SSF SSF SSF SSF SSF SSF |
| PLANTING AREA | |
| SEEDING AREA | |
| | |
| | ٨ |
| | /\ |





LOCATION MAP

PERMITTEE CERTIFICATION:

I, THE UNDERSIGNED, CERTIFY THAT ALL LAND CLEARING AND CONSTRUCTION SHALL BE DONE PURSUANT TO THE APPROVED PLAN AND THAT RESPONSIBLE PERSONNEL (I.E., BLUE CARD HOLDER) INVOLVED IN THE LAND DISTURBANCE WILL HAVE A CERTIFICATION OF TRAINING PRIOR TO INITIATION OF THE PROJECT, AT A DNREC SPONSORED OR APPROVED TRAINING COURSE FOR THE CONTROL OF EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION. IN ADDITION, I GRANT THE DEPARTMENT OR DELEGATED INSPECTION AGENCY THE RIGHT TO CONDUCT ON-SITE INSPECTIONS, AND I UNDERSTAND MY RESPONSIBILITIES UNDER THE NPDES CONSTRUCTION GENERAL PERMIT.

NAM

SIGNATURE

TITLE

DATE



'ERSHEE

TRIC

SUSSEX

Div

REC



File Location: G:\Equipment Section\Projects\CARROLL COASTLINE REVETMENT, 23-245\DWG\CARROLL BASE REVET ALT 2.dwg Layout:SITE PLAN C100 User: james.elliott Plot time: 12-28-23 @ 1:10pm





File Location: G:\Equipment Section\Projects\CARROLL COASTLINE REVETMENT, 23-245\DWG\CARROLL BASE REVET ALT 2.dwg Layout:Profile (2) User: james.elliott Plot time: 12-28-23 @ 1:11pm



CONSTRUCTION NOTES:

- 1. R6 RIPRAP SHALL BE USED FOR THE SHORELINE REVETMENT.
- 2. THE REVETMENT SHALL BE 30" THICK.
- AND TRANPORTED IN SEALED TRUCKS.
- 5. ALL RIPRPAP SHALL BE PLACED OVER A GEOTEXTILE UNDER-LAYMENT MIRAFI 600X.
- 6. THE GEOTEXTILE UNDER-LAYMENT SHALL BE KEYED IN AT THE TOP OF BANK.

3. CLEAR AND GRUB THE SLOPE AND DISPOSE OF SPOILS IN A DNREC APPROVAL OFFISTE LOCATION. 4. ANY SPOILS GENERATED FROM THE THIS PROJECT SHALL BE REMOVED AND DISPOSED IN A DNREC APPROVED LOCATION

| | DATE REVISIONS DATE DESCRIPTION | |
|------|---|--|
| | | Conservation district PREAME. ROTECL. RESERVE. |
| | SUSSEX CONSERVATION DISTRICT 23818 SHORTLY RD., GEORGETOWN, DE 19957 PHONE: (302)-856-2105 FAX: (302-856-0951 | DNREC - Division of Watershed Stewardship Drainage Program Dover Office Georgetown Office 285 Beiser Blvd., Suite 102 Phone:(302) 739-9921 21309 Berlin Rd. Unit 6 Phone:(302) 855-1930 Dover DE, 19901 Fax:(302) 739-6724 Georgetown DE, 19947 Fax:(302) 677-7059 |
| | NEL AWART | MOD TATIVATION OF NATIONAL CONTRACTOR |
| | CARROLL SHORELINE REVETMENT PROJECT | WHITE'S CREEK / INLAND BAY WATERSHED OCEAN VIEW, DELAWARE PROFILE / SECTION VIEW CONSTRUCTION DETAIL PLAN |
| | PREP FOR | MINARY ONLY |
| 150' | Date: 12/2 Designed: Planned: Drawn: | 20/2023 JLE, WA JLE, WA, MM JLE |

SCALE: 1" = 50'



File Location: G:\Equipment Section\Projects\CARROLL COASTLINE REVETMENT, 23-245\DWG\CARROLL BASE REVET ALT 2.dwg Layout:SECTION VIEW C300 User: james.elliott Plot time: 12-28-23 @ 1:11pm





| Constructio | n Site Pol | lution Prevention |
|--|--|---|
| Delawar General Permit for Di | e NPDES Disc scharge of Stormwater | harge Permit from Construction Activities |
| ((Project Name)) | | |
| ((NOI Permit Numbe | r)) | |
| ((Agency Plan Appro | val ID)) | |
| ((Contact Name & Nu | umber for Additional Si | te Information)) |
| ((Contact Name & Nu | umber to Obtain Copy | of Approved Plan)) |
| lf you obs in the disch DNRE | erve indicators of storr arge or in the receiving C Spill Notification 24 | nwater pollutants waterbody, call the HR Hotline at |
| | 1-800-662-880 | 2 |
| Example | e Construction General F | ermit (CGP) Signage |
| NOTES: 1. Minimum sign size 2' x 2' 2. Minimum text size 1" 3. Sign must be posted at 4. Sign must be visible fron 5. Signs posted within a De with all local and/or State | a safe, publicly accessib 1 the public road nearest 2DOT or other public road requirements in regards | e location close to construction site the active construction site d right-of-way (ROW) must be in accord to safety, location, orientation, etc. |
| Source: Delaware ESC Handbook | Symbol: | Detail No. DE-ESC-3.6.1 Sheet 1 of 4 |





| | | Soil Stockpile |
|--|--|---|
| Construction Note | 2 S: | |
| Locate stockpiles so that wetland or waterbody. R approved erosion and se | they are 50 feet from any st edirect any concentrated flo diment control measure. | torm drain inlet, open channel, w around the stockpile using an |
| 2. Secure the perimeter of t perimeter device. | he stockpile with an approve | ed erosion and sediment control |
| If stockpile is to remain in vegetated. Follow the ter last the duration of the sto vegetation dies or erosion | active for more than 14 cale mporary vegetation specifica ockpile; the stockpile shall b n results. | endar days, the stockpile must be ations. The vegetation chosen shall e restabilized if the temporary |
| | | |
| | | |
| | | |
| | | |
| | | |
| burce: | Symbol: | Detail No. |
| Adapted from blorado Urban Storm Drain- | SP | DE-ESC-3.7.3 Sheet 2 of 2 |



| | Construction Notes (cont.) e. Prominently post con Free Number. | Standard Det Standard Det Site Pollution tact information for reporting spille | tail & Specifications on Prevention | ATE REVISIONS DESCRIPTION |
|---|--|---|---|--|
| | 6. Education a. Include Best Manage of regular progress r b. Information regarding should be prominent DNREC 24-Hour Toll F DNREC Solid & Hazard | ment Practices (BMPs) for constr neetings. waste management, equipment ly posted in the construction trai CONTACT INFORMATIC ree Number dous Waste Management Sec | ruction site pollution control as part t maintenance and spill prevention ler. 800-662-8802 tion 302-739-9403 | |
| | Source: Adapted from USEPA Pub. 840-B-92-002 | Symbol: | Detail No. DE-ESC-3.6.1 Sheet 4 of 4 Effective July 2023 | SSEX CONSERVATION DISTRICT 23818 SHORTLY RD., GEORGETOWN, DE 19957 PHONE: (302)-856-2105 FAX: (302-856-0951 C - Division of Watershed Stewardship Drainage Program |
| Construction Notes: Prior to installation, clear bedding area of obstructions including rocks or debris larger than 1 inch and fill in any sharp depression areas. If socks are prepared on-site, fill the sock fabric using a pneumatic blower so that the logs are rigid and do not deform. Terminate at the desired length. For tranched applications, excavate 2 to 4 inches below grade along the width and length of the compost filler log. Install the compost filler logs perpendicular to the flow direction and parallel to the slope with the beginning and end of the installator pointing up the slope a minimum of 11 foot elevation difference. On slice where this is not possible, upturn at a minimum for 01 of at a 30 degree angle to prevent nunoff bypass. For unrenched applications, bow or hand pack soil, mulch, or compost on the upslope side of the log, filling the bottom void area. Stake the filled log every 10 feet maximum through the center of the sock. If located on a slope greater than 81, the stake shall be argical downskope at a 45 degree angle to prevent the force of the water from diskliging to log. When the length of the compost filler log needed exceeds the evaliable compost filter sock length, the next sock shall be available and of the book. Remove accumulated sediment when it has reached half of the effective height of the log. Inspect weekly and after rain event. If sock is degrading or the sock is failing, vegetate to secure the compost, the log shall be replaced or reinforced with an additional compost filter log. Source: <u>Adapted from</u> <u>MoD Side & Specs for ESC & Sprittor. <u>Sprittor</u> </u> | | | | SUS DNREG |
| 4. Install the compost filter logs perpendicular to the flow direction and parallel to the slope with the beginning and end of the installation pointing up the slope a minimum of 1 foot elevation difference. On sites where this is not possible, upturn at a minimum length of 10° at a 30 degree angle to prevent runoff bypass. 5. For untrenched applications, blow or hand pack soil, mulch, or compost on the upslope side of the log, filling the bottom void area. 6. Stake the filled log every 10 feet maximum through the center of the sock for trenched applications, or every 8 feet for untrenched. The stake shall be a 2" by 2" hardwood. It should extend 12" below grade and protude at least 3" above the top of the sock. If located on a slope greater than 8:1, the stake shall be angled downslope at a 45 degree angle to prevent the force of the water from dislodging to log. 7. When the length of the compost filter log needed exceeds the available compost filter sock length, the next sock shall be overlapped a minimum of 12" before being filled, and a stake placed through both socks at the overlap. 8. Remove accumulated sediment when it has reached half of the effective height of the log. 9. Inspect weekly and after rain event. If sock is degrading or the sock is failing, vegetate to secure the compost, replace the log, or reinforces with an additional log. If the log has been crushed due to construction equipment, it can be "fluffed" back to its effective height 1 the effective height can no longer be restored, the log shall be replaced or reinforced with an additional compost filter log. Source: Symbol: Detail No. CFL | | Standard D | etail & Specifications | SUS |
| | Construction N 1. Prior to installation, clear and fill in any sharp depre 2. If socks are prepared on- and do not deform. Term 3. For trenched applications compost filter log. | Standard D Comp lotes: bedding area of obstructions includ ssion areas. site, fill the sock fabric using a pneu inate at the desired length. , excavate 2 to 4 inches below grad | Detail & Specifications DOST Filter Log ling rocks or debris larger than 1 inch umatic blower so that the logs are rigid de along the width and length of the | SUS |

JLE, WA, MM

JLE

C-701

anned

| Ve | getative | Sta | abil | ĪZ | ati | or | | | | |
|---|---|--|---|--|--|---|---|--|--|-------------------------|
| | ТЕМР | ORARY S | EEDING | BY F | RATES | 6, DEF | THS | AND C | DATES | ; |
| Mix # | Species ⁵ | Seedii | Seeding Rate | | O ptimum | ptimun Planting | n Seed Period; Perio | ling Da A = Acc | a tes ¹ ceptable | Plantin |
| | | | | Co | astal P | lain | P | iedmo | nt | A |
| | Certified Seed | lb/Ac.4 | lb/1000 sq.ft. | 2/1- 4/30 | ² 5/1- 8/14 | 8/15- 10/31 | 3/1- 4/30 | ² 5/1- 7/31 | 8/1- 10/31 | 10/: 2/ |
| 1 | Barley | 125 | 4 | 0 | A | 0 | 0 | A | 0 | |
| 2 | Oats | 125 | 4 | 0 | A | A | 0 | A | A | |
| 3 | Rye | 125 | 4 | 0 | A | 0 | 0 | A | 0 | A |
| 4 | Perennial Ryegrass | 125 | 4 | 0 | A | 0 | 0 | A | 0 | |
| 5 | Annual Ryegrass | 125 | 4 | 0 | A | 0 | 0 | A | 0 | A |
| 6 | Winter Wheat | 125 | 4 | 0 | A | 0 | 0 | A | 0 | A |
| 7 | Foxtail Millet | 30 PLS | 0.7 | | 0 | | | 0 | | |
| 8 | Pearl Millet | 20 PLS | 0.5 | | 0 | | | 0 | | |
| | | | | | | | | | | |
| May be Applica Use va Use va Warm : per acr | a planted throughout summ able on slopes 3:1 or less. rieties currently recommen season grasses such as f re. Good on low fertility ar DTE: Alternative seed m | ner if soil m nded for De Millet may t nd acid area ixes may b | oisture is laware. C oe used be as. Seed e used w | adequa contact etween after fro | ate or s a Cour 5/1 and ost thro r appro | eeded hty Exte d 9/1 if ugh su oval fro | area ca ension desired mmer a m the l | an be ir Office f d. See at a dep Depart | rigated. or inform d at 3-5 oth of 0. ment o | 5 lbs. .5". r Del |
| Source: Delawa | re ESC Handbook | Syn | nbol: | | | | | [| Detail | No. |

File Location: G: Lequipment Section (Projects) CARROLL COASTLINE REVETMENT, 23-245 (DWG) CARROLL BASE REVET ALT 2.dwg Layout: ESC Details-2 User: james.elliott Plot time: 12-28-23 @ 1:11 pm



| Standard Detail & Sp | ecifications | | | Standa | rd Detail & Spec |
|---|---|--|--|---|--|
| Mulching | | | | | Μι |
| Materials and Amounts Straw - Straw shall be unrotted 90 pounds (two bales) per 1,00 be free of noxious weeds such hand or mechanically. For unit 1,000 square feet sections and Wood chips - Apply at the rate of available and when feasible. The chips are used, increase the applied of 10-10-10 or 66 pounds of 33 Hydraulically applied mulch - The i. Definitions: | I small grain straw applied at the rate of 0 square feet. Mulch materials shall b as; thistles, Johnsongrass, and quack form distribution of hand spread mulch d place 70-90 pounds (two bales) of r fapproximately 6 tons per acre or 275 p nese are particularly well suited for uti plication rate of nitrogen fertilizer by 20 0-0-0 per acre). he following conditions apply to hydra shall consist of specially prepared we ackaged for sale as a hydraulic mul- nisists of a minimum of 70% virgin or r nd additives. ch shall consist of any hydraulic mul- aper component must consist of spec form fibrous state and is packaged fo ding equipment. atrix (BFM) consists of long strand, sp sed to a uniform state held together b in no paper (cellulose) mulch but m enhance performance. 1.5a for conditions and limitations of us aulically applied mulches shall be pre- ce. Field mixing of the mulch compone nendations to ensure the proper resu e applied with a viable seed and at mate accessary based on site conditions. ulches and additives shall be mix ry shall only be used when hydraulicall ediment and Stormwater Plan, or sup o obtained in writing for a specific area | of 1-1/2 to 2 tons per acre, or 70 to e relatively free of weeds and shall grass. Spread mulch uniformly by th, divide area into approximately nulch in each section. wounds per 1,000 square feet when ity and road rights-of-way. If wood pounds of N per acre (200 pounds aulically applied mulch: bod that has been processed to a ch for use with hydraulic seeding ecycled wood fiber combined with th that contains greater than 30% ally prepared paper that has been r sale as a hydraulic mulch for use becially prepared wood fibers that y a water resistant bonding agent. ay contain small percentages of the for each of the above categories -packaged by the manufacturer to hts is acceptable, but must be done tts. nufacturer's recommended rates. ed according to manufacturers yapplied mulch has been specified plemental approval from the plan a. | v. Application: a. Apply divert b. Do no c. Durin hydra togett direct d. Durin the for S e. Minim achie tempo vi. Recommende standard and areas with ba d. Compost blanket covers the soil wit applying the appro- on slopes less that Compost blanket covers the soil wit applying the appro- on slopes less that Anchoring mulch - M done by one of the fol Crimping - A crimp (2) inches of soil. equipment can op possible. Tracking - Trackin equipment that ru be done up and d Liquid mulch bind at crests of banks: have a uniform ap binding and shoul Paper fiber - The f shall be mixed witt 100 gallons. Nettings - Biodegr the manufacturer | A product to geotechnically stable slot trunoff away from the face of the slot of apply to saturated soils, or if preci- ing the spring (March 1 to May 31) ar aulic mulches may be applied in a on- her in single-tank loads. It is recomm tions to achieve optimum soil covera g the summer (June 1 to August 31) ar allowing two-step process is required to a provide the summer (June 1 to August 31) ar allowing two-step process is required to a provide the summer (June 1 to August 31) ar allowing two-step process is required to a provide the summer (June 1 to August 31) ar allowing two-step process is required to a provide the summer (June 1 to August 31) ar allowing two-step process is required to a provide the summer (June 1 to August 31) ar a seeded surfaces. Apply from coverage. num curing temperatures exceeding 60° F erature, low humidity conditions on a specification rates are for informat specification shall be performance- tre soil showing shall be top dressed tree soil showing shall be applied with a pneum the sole applied with a pneum the sole and requires no mulch anchorin Aulch must be anchored immediately llowing methods, depending upon si per is a tractor drawn implement desi This practice affords maximum ero perate safely. On sloping land, crim is the process of cutting mulch (usi ins on cleated tracks. Tracking is usi lown the slope with cleat marks runn fers - Applications of liquid mulch bin and other areas where the mulch will b pplication of binder. The use of sym is be proted at the rates recommen fiber binder shall be applied at a net d h water, and the mixture shall contair tradable nettings may be used to securits the such and the mixture shall con | pes that have been designer pitation is anticipated within d fall (September 1 to Nov e-step process where all co ended that the product be a ige. and winter (December 1 to For the second second second second poposing directions to act C). The best results and m (15°C). Curing times may be dry soils. ational purposes only. Co based and requires 100% until full coverage is achieven atic blower so that a 1" comp can be used with seed to pro- lown compost. The compost g. / to minimize loss by wind o ze of area, erosion hazard, gned to punch and anchor m sion control but is limited to main generate the soil usin ed primarily on slopes 3:1 o ing across the slope. ders should be heavier at e be moved by wind or water. A thetic binders is the preferr ded by the manufacturer. ry weight of 750 lbs/ac. The a maximum of 50 lbs. of wo re straw mulch. Install and se ble or synthetic nettings are to be portion and section of the state of the time to the soil using of the time to the soil using across the slope. |
| Delewere ESC Hendbeck | | DE-ESC-3.4.5 | Delaware ESC Handl | book | DE |
| & Filtrexx [™] International | | Sheet 1 of 3 | & Filtrexx [™] Internatio | onal | Sh Effect |





| Standard Detail & Specifications | Standard Detail & Specifications | 6 |
|--|---|---|
| Stabilized Construction Entrance | Topsoiling | |
| Equipment wheel track + 2' | Construction Notes: | |
| | 1. Site Preparation (Where Topsoil is to be adde | d) |
| Metal bars set in reinforced conc. Provide space for drainage | <u>Note</u> : When topsoiling, maintain needed erosid diversions, grade stabilization structures, berma | on and sediment control practices such as s, dikes, waterways and sediment basins. |
| ther approved equiv. may be substituted) | a. Grading - Grades on the areas to be topsoile shall be maintained. | ed which have been previously established |
| Construction Notes: | b. Liming - Where the topsoil is either highly limestone shall be spread at the rate of 4-8 to | acid or composed of heavy clays, ground ns/acre (200-400 pounds per 1,000 square |
| 1. <u>Stone size</u> - Use DE #3 stone. | in conjunction with tillage operations as des | er designated areas and worked into the soil acribed in the following procedures. |
| 2. <u>Length</u> - As required, but not less than 50 feet (except on a single residence lot where a 30 foot minimum length would apply). | c. Tilling - After the areas to be topsoiled have b to dumping and spreading the topsoil, the su | een brought to grade, and immediately prior ubgrade shall be loosened by discing or by |
| 3. <u>Thickness</u> - Not less than size (6) inches. | scarifying to a depth of a least 3 inches to perm by passing a bulldozer up and down over th | nit bonding of the topsoil to the subsoil. Pack e entire surface area of the slope to create |
| 4. Width - Ten (10) foot minimum, but not less than the full width at points where ingress or egress occurs. | horizontal erosion check slots to prevent to | osoil from sliding down the slope. |
| 5. <u>Geotextile</u> - Type GS-I; placed over the entire area prior to placing of stone. | 2. Topsoil Material and Application | |
| <u>Surface vyater</u> - All surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 5:1 slopes will be permitted. | <u>Note</u> : Topsoil salvaged from the existing site may | y often be used but it should meet the same |
| <u>Maintenance</u> - The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights-of-way must be removed immediately. | standards as set form in these specifications. shall be no more than the depth described as a type as described in the soil survey published by Agricultural Experimental Station. | representative profile for that particular soil / USDA-SCS in cooperation with Delaware |
| Washing - Vehicle wheels shall be cleaned to remove sediment prior to entrance onto public rights- of-way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device. | | |
| 9. <u>Inspection</u> - Periodic inspection and needed maintenance shall be provided after each rain. | | |
| Adapted from VA ESC Handbook | Source: Symbol: | Detail No. DE-ESC-3.4.1 Sheet 1 of 2 |
| Effective July 2023 | | Effective July 2023 |

| | | IONS SCRIPTION | |
|--|--|--|--|
| Standard Detai | & Specifications Topsoiling | REVISI | |
| A. Materials - Topsoil shall be a loam, sandy loam, clay loam, loamy sand or other soil as approved by an agronomist or sia a mixture of contrasting textured subsoil and contain no mo of cinders, stones, slag, coarse fragment, gravel, sticks, roor materials larger than 1-1/2 inches in diameter. Topsoil must of bermudagrass, quackgrass, Johnsongrass, nutsedge, p as specified. All topsoil shall be tested by a reputable la content, pH and soluble salts. A pH of 6.0 to 7.5 and an org 1.5 percent by weight is required. If pH value is less than 6 incorporated with the topsoil to adjust the pH to 6.5 or higher salts greater than 500 parts per million shall not be used. | , silt loam, sandy clay loam, oil scientist. It shall not have re than 5 percent by volume ts, trash or other extraneous befree of plants or plant parts boison ivy, thistles, or others boratory for organic matter anic content of not less than 3.0 lime shall be applied and r. Topsoil containing soluble | DATE | DISERVATION district har. protect. preserve. |
| chemicals used for weed control until sufficient time has elapsed materials. b. Grading - The topsoil shall be uniformly distributed and com (4) inches. Spreading shall be performed in such a manner proceed with a minimum of additional soil preparation and till surface resulting from topsoiling or other operations shall be the formation of depressions or water pockets. Topsoil sh frozen or muddy condition, when the subgrade is excessive may otherwise be detrimental to proper grading and seedt <u>Note</u>:Topsoil substitutes or amendments as approved by a scientist, may be used in lieu of natural topsoil. Compost m percentage of organic matter shall be provided by a certified s Compost amendments that are intended to meet specific post-consment goals shall further meet the requirements of Appendix Stormwater Management BMP Standards and Specifications ments. | to permit dissipation of toxic pacted to a minimum of four that sodding or seeding can age. Any irregularities in the corrected in order to prevent nall not be placed while in a ely wet, or in a condition that bed preparation. qualified agronomist or soil aterial used to improve the supplier. struction stormwater manage- t 3.06.2 Post Construction 5. Section 14.0 Soil Amend- | RVATION DISTRICT ,, GEORGETOWN, DE 19957 6-2105 FAX: (302-856-0951 | f Watershed Stewardship ge Program Georgetown Office 921 21309 Berlin Rd. Unit 6 Phone:(302) 855-1930 |
| USDA - NRCS | Detail No. DE-ESC-3.4.1 Sheet 2 of 2 Effective July 2023 | SUSSEX CONSE 23818 SHORTLY RD PHONE: (302)-85 | DNREC - Division o Draina Dover Office 85 Beiser Blvd., Suite 102 Phone: (302) 739- |
| | | CONTRACTOR OF CO | THE REAL PROVINCE AND A DECEMBER OF NATURAL PROVINC |
| | | CARROLL SHORELINE REVETMENT PROJECT WHITP'S CREEK / INLAND BAY WATERSHED | ocean view, delaware Erosion & Sediment control |
| | | PRELIM PRELIM FOR PER FOR PER Date: 12/20/2 Designed: | NARYONI INFW 1023 |

JLE, WA, MM

JLE

neet No. **C-703**

anned:

Source:

GRADING NOTES:

- 1. BEDDING REQUIREMENTS SPECIFIED HEREIN ARE TO BE CONSIDERED AS MINIMUMS FOR RELATIVELY DRY, STABLE EARTH CONDITIONS. ADDITIONAL BEDDING SHALL BE REQUIRED FOR ROCK TRENCHES AND WET AREAS. CONTRACTOR SHALL HAVE THE RESPONSIBILITY TO PROVIDE SUCH ADDITIONAL BEDDING AS MAY BE REQUIRED TO PROPERLY CONSTRUCT THE WORK.
- 2. COMPACTION OF THE BACKFILL OF ALL TRENCHES SHALL BE COMPACTED TO THE DENSITY OF 95% OF THEORETICAL MAXIMUM DRY DENSITY (ASTM D698). BACKFILL MATERIAL SHALL BE FREE FROM ROOTS, STUMPS, OR OTHER FOREIGN DEBRIS AND SHALL BE PLACED IN LIFTS NOT TO EXCEED 8 INCHES IN COMPACTED FILL THICKNESS. CORRECTION OF ANY TRENCH SETTLEMENT WITHIN A YEAR FROM THE DATE OF APPROVAL WILL BE THE RESPONSIBILITY OF THE CONTRACTOR. MATERIAL THAT CANNOT BE COMPACTED AS REQUIRED SHALL BE BROUGHT TO THE ATTENTION OF A GEO-TECHNICAL ENGINEER, OVER EXCAVATED, AND THEN REPLACED WITH SUITABLE FILL
- 3. THE CONTRACTOR WILL INSURE THAT POSITIVE AND ADEQUATE DRAINAGE IS MAINTAINED AT ALL TIMES WITHIN THE PROJECT LIMITS. THIS MAY INCLUDE, BUT NOT BE LIMITED TO, REPLACEMENT OR RECONSTRUCTION OF EXISTING DRAINAGE STRUCTURES THAT HAVE BEEN DAMAGED OR REMOVED OR REGRADING AS REQUIRED BY THE ENGINEER, EXCEPT FOR THOSE DRAINAGE ITEMS SHOWN AT SPECIFIC LOCATIONS AND HAVING SPECIFIC PAY ITEMS IN THE DETAILED ESTIMATE. NO SEPARATE PAYMENT WILL BE MADE FOR ANY COSTS INCURRED TO COMPLY WITH THIS REQUIREMENT.
- 4. THE CONTRACTOR SHALL PROVIDE ANY AND ALL EXCAVATION AND MATERIAL SAMPLES NECESSARY TO CONDUCT REQUIRED SOIL TESTS. ALL ARRANGEMENTS AND SCHEDULING FOR THE TESTING SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
- 5. SOILS TESTING AND ON-SITE INSPECTION SHALL BE PERFORMED BY AN INDEPENDENT GEO-TECHNICAL ENGINEER. THE SOILS ENGINEER SHALL PROVIDE COPIES OF TEST REPORTS TO THE CONTRACTOR, THE OWNER AND THE OWNER'S REPRESENTATIVE AND SHALL PROMPTLY NOTIFY THE OWNER, HIS REPRESENTATIVE AND THE CONTRACTOR, SHOULD WORK PERFORMED BY THE CONTRACTOR FAIL TO MEET BUILDING STANDARDS.
- 6. CONTRACTOR SHALL FURNISH AND MAINTAIN ALL NECESSARY BARRICADES AROUND THE WORK AREA AND SHALL PROVIDE PROTECTION AGAINST WATER DAMAGE AND SOIL EROSION.
- 7. VERTICAL ELEVATIONS ARE BASED ON NAVD 88.
- 8. ALL SLOPES MAXIMUM 3:1 UNLESS OTHERWISE NOTED.
- 9. HDPE PIPE SHALL COMPLY WITH AASHTO M252, M294, MP7, AND ASTM 3350. PIPE SHALL BE INSTALLED PER ASTM D2321 AND AS RECOMMENDED BY THE MANUFACTURER. ALL HDPE SHALL HAVE SOIL TIGHT CONNECTIONS.
- 10. DRAINAGE INLETS SHALL BE MANUFACTURED IN ACCORDANCE WITH THE LATEST STANDARDS OF DELDOT'S STANDARD CONSTRUCTION DETAILS UNLESS NOTED OTHERWISE ON THE PLANS.
- 11. ALL HDPE PIPE SHALL MEET OR EXCEED THAT AASHTO M-330 PIPE SPECIFICATION.
- 12. CONTRACTOR IS RESPONSIBLE FOR REMOVING AND DISPOSING OF EXCESS DIRT FROM THE SITE. THIS CAN BE COORDINATED WITH OWNER TO DETERMINE IF LONG TERM STORAGE ON SITE IS APPLICABLE.
- 13. CONTRACTOR IS RESPONSIBLE TO ENSURE POSITIVE DRAINAGE AND PREVENT PONDING FOR ALL PROPOSED IMPROVEMENTS ALONG WITH NOT NEGATIVE IMPACTING EXISTING CONDITIONS.
- 14. CONTRACTOR MUST DISCUSS WITH THE DNREC, SCD, AND DESIGN ENGINEER IF FIELD ISSUES ARISE. HE IS NOT TO PROCEED UNTIL THE ISSUE HAS BEEN RECTIFIED.

15. CONTRACTOR IS RESPONSIBLE FOR PROJECT STAKE OUT.

CONSTRUCTION NOTES:

- 1. THE SITE SHALL BE GRADED TO THE FINAL ELEVATIONS SHOWN ON THE STORMWATER MANAGEMENT, GRADING, EROSION AND SEDIMENT CONTROL PLAN PREPARED BY SCD. THE CONTRACTOR SHALL PERFORM GRADING TO PROVIDE POSITIVE DRAINAGE AND PRECLUDE PONDING OF WATER.
- 2. THE CONTRACTOR WILL BE RESPONSIBLE FOR CLEARING AND GRADING AND GRUBBING THE SITE TO LIMITS SHOWN ON THE PLANS. THIS WILL INCLUDE THE REMOVAL AND DISPOSAL OF ANY EXISTING PAVEMENT, FENCES, BUILDING DEBRIS AND TRASH ON THE SITE. DISPOSAL WILL BE OFFSITE IN ACCORDANCE WITH ALL FEDERAL, STATE AND LOCAL REGULATIONS; AND AT THE CONTRACTOR'S EXPENSE.
- 3. THE CONTRACTOR SHALL EXERCISE CARE AND CONSIDERATION IN CONSTRUCTION IN THE VICINITY OF ADJACENT PROPERTY OWNERS.
- 4. ALL DISTURBED R.O.W. / PROPERTY CORNER MONUMENTS ARE TO BE VERIFIED BY A PROFESSIONAL ENGINEER OR A REGISTERED PROFESSIONAL LAND SURVEYOR AT THE CONTRACTOR'S EXPENSE AND REPLACED/RESET IF NEEDED.
- 5. RIPRAP ROCK SHALL AS A MINIMUM: D50 STONE SIZE = 6". DEPTH = 18".
- 6. DUST CONTROL DURING DEMOLITION AND CONSTRUCTION CONTRACTOR IS RESPONSIBLE FOR WETTING DUST GENERATING DEBRIS FROM TIME OF FIRST CONTACT UNTIL PLACING INTO APPROPRIATE WASTE OR HAULING CONTAINERS OR TRUCKS. DEBRIS SHALL NOT BE ALLOWED TO DRY BEFORE REMOVED FROM SITE. REFER TO DETAIL DE-ESC 3.4.8 SHEET CS8502 FOR ADDITIONAL INFORMATION. THIS PRACTICE SHALL ALSO BE FOLLOWED FOR ANY BARE SOIL LEFT EXPOSED PRIOR TO PROPER VEGETATION OCCURS.
- 7. ALL MATERIALS AND WORKMANSHIP WITHIN THE STATE OF DELAWARE RIGHT-OF-WAY SHALL BE IN ACCORDANCE WITH CURRENT STATE OF DELAWARE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, SUPPLEMENTAL SPECIFICATIONS, STANDARD CONSTRUCTION DETAILS, SPECIAL PROVISIONS, PAS MANUAL AND DESIGN GUIDANCE MEMORANDUMS.
- 8. ALL NYLOPLAST BASINS AND INLINE DRAIN BASINS INSTALLED W/IN THE DeIDOT RIGHT-A-WAY SHALL BE INSTALL PER THE NYLOPLAST H-20 TRAFFIC LOADING INSTALLATION DETAIL W/ CONC. COLLAR.
- 9. ALL DRIVEWAYS SHALL BE REPLACED AND OR REPAIRED IN KIND. COORDINATE WITH OWNER TO MAINTAIN ACCESS TO RESPECTIVE PROPERTIES.
- 10. ALL MAILBOXES SHALL BE REPLACED AND OR REPAIRED IN KIND. COORDINATE WITH OWNER TO MAINTAIN MAIL SERVICE DURING CONSTRUCTION.
- 11. ELEVATIONS ARE BASED ON NAVD 88, AND DE STATE PLANE COORDINATE SYSTEM NAD 83 HORIZONTAL DATUM.
- 12. UNLESS SPECIFICALLY STATED OR SHOWN HEREON TO THE CONTRARY, THIS SURVEY IS MADE SUBJECT TO AND DOES NOT LOCATE OR DELINEATE:
- 12.1. RIGHTS OR INTEREST OF THE UNITED STATES OF AMERICA OR STATE OF DELAWARE OVER LANDS NOW OR FORMERLY FLOWED BY TIDEWATER, BUT NO LONGER VISIBLE OR PHYSICALLY EVIDENT, OR LANDS CONTAINING ANY ANIMAL, MARINE OR BOTANICAL SPECIES REGULATED BY OR UNDER THE JURISDICTION OR ANY FEDERAL, STATE, OR LOCAL AGENCY.
- 12.2. BUILDING SETBACK LINES, ZONING REGULATIONS OR LINES ESTABLISHED BY ANY FEDERAL, STATE OR LOCAL AGENCY WHICH MAY AFFECT THE BUILDING OR DEVELOPMENT POTENTIAL OF THE SUBJECT PROPERTY.
- 12.3. ANY SUBSURFACE OR SUBTERRANEAN CONDITION, EASEMENTS OR RIGHTS, INCLUDING, BUT NOT LIMITED TO MINERAL OR MINING RIGHTS, OR THE LOCATION OF OR RIGHTS TO ANY SUBSURFACE STRUCTURES, CONTAINERS OR FACILITIES OR ANY OTHER NATURAL OR MAN-MADE SUBSURFACE CONDITION WHICH MAY OR MAY NOT AFFECT THE USE OR DEVELOPMENT POTENTIAL OF THE SUBJECT
- 13. UTILITY NOTES:

PROPERTY.

13.1. THE LOCATION OF THE EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN HAVE BEEN TAKEN FROM EXISTING UTILITY RECORDS AVAILABLE AT THE TIME THESE PLANS WERE PREPARED AND FROM SURFACE OBSERVATION OF THE SITE. LOCATIONS OF UTILITIES AS SHOWN AND MAY OR MAY NOT BE COMPLETE. THE NATURE AND EXACT LOCATION OF EXISTING UTILITIES SHOULD BE VERIFIED PRIOR TO INITIATING ANY ACTIVITY THAT MAY AFFECT THEIR USE OR LOCATION.

13.2. COMPLETENESS OR ACCURACY OF LOCATION AND DEPTH OF UNDERGROUND UTILITIES AND STRUCTURES IS NOT GUARANTEED.

- 13.3. BEFORE ANY EARTHWORK OR EXCAVATION TAKES PLACE, THE CONTRACTOR SHALL CALL MISS UTILITY AT 811 OR 1.800.282.8555 AT LEAST 48 HOURS PRIOR TO CONSTRUCTION, TO HAVE ALL EXISTING UTILITIES MARKED ONSITE...
- 13.4. THE CONTRACTORS SHALL TEST PIT TO VERIFY LOCATIONS AND DEPTHS OF ALL UNDERGROUND UTILITIES AND STRUCTURES BEFORE THE START OF WORK.
- 13.5. IF CONFLICTS ARE FOUND THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER AND DESIGN ENGINEER FOR INSTRUCTION BEFORE PROCEEDING WITH WORK.

14. STATE WETLAND FLAG SHOWN WAS PER DNREC DRAINAGE SECTION DELINEATION.

REFERENCE:

- 15. EXISTING CONDITIONS SURVEY PERFORMED BY DNREC/KCD.
- 16. THE PARCEL BOUNDARY LINES ARE FROM BEST AVAILABLE GIS DATA.

EROSION AND SEDIMENT CONTROL SEQUENCE OF CONSTRUCTION:

- PERIMETER CONTROLS.
- DISTURBANCE OR CONSTRUCTION.

- NO SLOPE, AND STABILIZED ONCE INACTIVE.

- REMAINING CONSTRUCTION SITE CONTROLS.

EROSION AND SEDIMENT CONTROL GENERAL NOTES:

- BY DNREC.

- LOGS OF THESE INSPECTIONS.

1. NOTIFY THE DNREC DRAINAGE PROGRAM IN WRITING AT LEAST FIVE (5) DAYS PRIOR TO THE START OF CONSTRUCTION. FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLAN.

2. PRIOR TO ANY CLEARING, INSTALLATION OF SEDIMENT CONTROL MEASURES, OR GRADING, A PRE-CONSTRUCTION MEETING MUST BE CONDUCTED WITH THE CONSTRUCTION SITE REVIEWER. THE LANDOWNER, CONTRACTOR AND CERTIFIED CONSTRUCTION REVIEWER ARE REQUIRED TO BE IN ATTENDANCE AT THE PRE-CONSTRUCTION MEETING; THE DESIGNER IS RECOMMENDED TO ATTEND.

3. INSTALL THE STABILIZED CONSTRUCTION ENTRANCE(S) AS INDICATED ON THE PLAN, FOLLOWED BY THE PERIMETER CONTROLS (I.E., BERMS, SILT FENCE, COMPOST LOGS) AND INLET PROTECTION ON ANY EXISTING INLETS. MARK THE LIMITS OF SENSITIVE AREAS, SUCH AS PRESERVED TREES, INFILTRATION AREAS, AND OTHER SECTIONS THAT ARE NOT TO BE DISTURBED WITH A PHYSICAL BARRIER. ONLY CLEAR WOODS THAT ARE NEEDED TO INSTALL THE

4. SCHEDULE A PERIMETER CONTROL REVIEW WITH THE DNREC CONSTRUCTION SITE REVIEWER.

5. ALL PERIMETER CONTROLS ARE TO BE REVIEWED BY THE DNREC CONSTRUCTION SITE REVIEWER AND APPROVED PRIOR TO PROCEEDING WITH FURTHER SITE

6. THE CONTRACTOR SHALL AT ALL TIMES PROTECT AGAINST SEDIMENT LADEN RUNOFF OR WIND FROM LEAVING THE SITE. PERIMETER CONTROLS SHOULD BE CHECKED DAILY AND ADJUSTED AND/OR REPAIRED TO FULLY CONTAIN AND CONTROL SEDIMENTATION ON THE SITE. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED HALF OF THE EFFECTIVE CAPACITY OF THE CONTROL. IN ADDITION, THE CONTRACTOR MAY NEED TO ADJUST, REPAIR OR ALTER MEASURES IN TIMES OF ADVERSE WEATHER CONDITIONS, OR AS DIRECTED BY THE DNREC CONSTRUCTION SITE REVIEWER.

7. CLEAR AND GRUB THE CONSTRUCTION PROJECT LOD AREA AFTER COORDINATING WITH LANDOWNER ON ITEMS TO BE REMOVED.

8. STOCKPILE TOPSOIL AND EXCAVATED SUBSOILS. STOCKPILES SHOULD BE SURROUNDED WITH A PERIMETER CONTROL, LOCATED ON LAND WITH SLIGHT TO

9. ALL SPOILS SHALL BE REMOVED FROM THE SITE IN SEALED TRUCKS AND DISPOSED OF IN A DNREC APPROVED MANNER.

10. INSTALL R6 RIPRAP REVETMENT TO THE DETAILS SHOWN IN THE PROFILE, SECTION VIEW AND DETAILS.

11. FINAL GRADE ALL DITCHES AND DISTURBED AREAS AND APPLY PERMANENT SEEDING AND STABILIZATION AS SOON AS FINAL GRADE IS ACHIEVED.

12. THE EROSION AND SEDIMENT CONTROL DEVICES SHOULD BE REMOVED ONLY AFTER WORK IN AN AREA HAS BEEN COMPLETED AND STABILIZED, WITH WRITTEN APPROVAL FROM THE DNREC CONSTRUCTION SITE REVIEWER. COORDINATE THE INSPECTION, AND AFTER THE WRITTEN APPROVAL, REMOVE THE

13. TERMINATE COVERAGE OF THE CONSTRUCTION GENERAL PERMIT, WHICH REQUIRES SUBMISSION AND ACCEPTANCE OF THE POST CONSTRUCTION VERIFICATION DOCUMENTS, INCLUDING FINAL STABILIZATION THROUGHOUT THE SITE, ALL ELEMENTS OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN IMPLEMENTED, ACCEPTANCE OF THE FINAL OPERATION AND MAINTENANCE PLAN, AND SUBMITTAL OF THE NOTICE OF TERMINATION.

1. THE DNREC SEDIMENT AND STORMWATER MANAGEMENT PROGRAM MUST BE NOTIFIED IN WRITING FIVE (5) DAYS PRIOR TO COMMENCING WITH CONSTRUCTION. FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLAN.

2. REVIEW AND OR APPROVAL OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN SHALL NOT RELIEVE THE CONTRACTOR FROM HIS OR HER RESPONSIBILITIES FOR COMPLIANCE WITH THE REQUIREMENTS OF THE SEDIMENT AND STORMWATER REGULATIONS, NOR SHALL IT RELIEVE THE CONTRACTOR FROM ERRORS OR OMISSIONS IN THE APPROVED PLAN.

3. IF THE APPROVED PLAN NEEDS TO BE MODIFIED, ADDITIONAL SEDIMENT AND STORMWATER CONTROL MEASURES MAY BE REQUIRED AS DEEMED NECESSARY

4. FOLLOWING SOIL DISTURBANCE OR RE-DISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED FOR ALL PERIMETER SEDIMENT CONTROLS, SOIL STOCKPILES, AND ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE WITHIN 14 CALENDAR DAYS UNLESS MORE RESTRICTIVE FEDERAL REQUIREMENTS APPLY, OR IF A MORE RESTRICTIVE REQUIREMENT'S NOTED ON THE PLANS.

3. ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL COMPLY WITH THE DELAWARE EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION.

4. AT ANY TIME A DEWATERING OPERATION IS USED, IT SHALL BE PREVIOUSLY APPROVED BY THE AGENCY CONSTRUCTION SITE REVIEWER FOR A NON-EROSIVE POINT OF DISCHARGE, AND A DEWATERING PERMIT SHALL BE APPROVED BY THE DNREC WELL PERMITTING BRANCH. 5. APPROVED PLANS REMAIN VALID FOR 5 YEARS FROM THE DATE OF APPROVAL.

6. THE NOTICE OF INTENT FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY UNDER A NPDES GENERAL PERMIT FOR THIS PROJECT IS #_____ . AT ANY TIME THE OWNERSHIP FOR THIS PROJECT CHANGES, A TRANSFER OF AUTHORIZATION OR A CO-PERMITTEE APPLICATION MUST BE SUBMITTED TO DNREC. THE PERMITTEE OF RECORD SHALL NOT BE RELIEVED OF THEIR RESPONSIBILITIES UNTIL A NOTICE OF TERMINATION HAS BEEN PROCESSED BY DNREC. [OR] A NOTICE OF INTENT IS NOT REQUIRED FOR THIS PROJECT SINCE DISTURBANCE IS LESS THAN 1 ACRE.

7. THE OWNER SHALL BE FAMILIAR WITH AND COMPLY WITH ALL ASPECTS OF THE NPDES CONSTRUCTION GENERAL PERMIT ASSOCIATED WITH THE PROJECT, INCLUDING, BUT NOT LIMITED TO, PERFORMING WEEKLY SITE INSPECTIONS DURING CONSTRUCTION AND AFTER RAIN EVENTS, AND MAINTAINING WRITTEN

8. THE CONTRACTOR SHALL AT ALL TIMES PROTECT AGAINST SEDIMENT OF DEBRIS LADEN RUNOFF OR WIND FROM LEAVING THE SITE. PERIMETER CONTROLS SHALL BE CHECKED DAILY AND ADJUSTED AND/OR REPAIRED TO FULLY CONTAIN AND CONTROL SEDIMENT FROM LEAVING THE SITE. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED HALF OF THE EFFECTIVE CAPACITY OF THE CONTROL. IN ADDITION, THE CONTRACTOR MAY NEED TO ADJUST OR ALTER MEASURES IN TIMES OF ADVERSE WEATHER CONDITIONS, OR AS DIRECTED BY THE AGENCY SITE REVIEWER.

9. BEST AVAILABLE TECHNOLOGY (BAT) SHALL BE EMPLOYED TO MANAGE TURBID DISCHARGES IN ACCORDANCE WITH REQUIREMENTS OF 7. DEL C. CH 60, REGULATIONS GOVERNING THE CONTROL OF WATER POLLUTION, SECTION 9.1.02, KNOWN AS SPECIAL CONDITIONS FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES AND DEPARTMENT POLICIES, PROCEDURES, AND GUIDANCE.

10. DOCUMENTATION OF SOIL TESTING AND MATERIALS USED FOR TEMPORARY OR PERMANENT STABILIZATION INCLUDING BUT NOT LIMITED TO SOIL TEST RESULTS, SEED TAGS, SOIL AMENDMENT TAGS, ETC, SHALL BE PROVIDED TO THE DEPARTMENT OR DELEGATED AGENCY TO VERIFY THAT THE PERMANENT OR TEMPORARY STABILIZATION HAS BEEN COMPLETED IN ACCORDANCE WITH THE APPROVED PLAN AND THE STANDARDS AND SPECIFICATIONS OF THE DELAWARE EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION. THE DEPARTMENT OF THE DELEGATED AGENCY SHALL HAVE THE DISCRETION TO REQUIRE ADDITIONAL SOIL TESTING AND REAPPLICATION OF PERMANENT OR TEMPORARY STABILIZATION IN ACCORDANCE WITH THE SPECIFICATION PROVIDED WITHIN THE DELAWARE EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION.





File Location: G: Equipment Section Projects CARROLL COASTLINE REVETMENT, 23-245 DWG CARROLL BASE REVET ALT 2.dwg Layout: STATE SECTIONS User: james.elliott Plot time: 12-28-23 @ 1:11pm

File Location: G:\Equipment Section\Projects\CARROLL COASTLINE REVETMENT, 23-245\DWG\CARROLL BASE REVET ALT 2.dwg Layout:STATE SECTIONS 2 User: james.elliott Plot time: 12-28-23 @ 1:11pm

| STAT | 0n | END AREA | Ş. |
|------|----|----------|----|
| 0 | | 9.52 | |
| 10 | | 10.42 | |
| 20 | | 10.81 | |
| 30 | | 11.38 | |
| 40 | | 10.45 | |
| 50 | | 10.3 | |
| 60 | | 11.08 | |
| 70 | | 11.98 | |
| 80 | | 12.24 | |
| 90 | | 13.77 | |

| CUM. VOLUME (CF) | |
|----------------------|---|
| CY | |
| WETLAND FILL (CY/FT) | |
| | - |

Electronically Recorded Document# 2020000059514 BK: 5363 PG: 162 Recorder of Deeds, Scott Dailey On 12/2/2020 at 10:15:00 AM Sussex County, DE Consideration: \$530,000.00 County/Town: \$7,950.00 State: \$13,250.00 Total: \$21,200.00 Doc Surcharge Paid Town: SUSSEX COUNTY

> 1-34 12.00 875.00
> PREPARED BY & RETURN TO: Sergovic Carmean Weidman
> McCartney & Owens, P.A.
> 25 Chestnut Street
> P.O. Box 751
> Georgetown, DE 19947-0751
> File No. RE-11925

THIS DEED, made this <u>A</u> day of November, 2020,

- BETWEEN -

<u>PENNY LYNN DEITH</u> of 30891 Cedar Neck Road, Ocean View, DE 19970, <u>PENNY</u> <u>LYNN DEITH, ATTORNEY-IN-FACT FOR BONITA ANN MCBRIDE</u> of 308 Steamboat Lane, Dagsboro, DE 19939, <u>PENNY LYNN DEITH, ATTORNEY-IN-FACT FOR DONNA</u> <u>LEE NUGENT</u> of 30619 Cedar Neck Road, Unit 1304, Ocean View, DE 19970 and <u>PENNY</u> <u>LYNN DEITH, ATTORNEY-IN-FACT FOR JOANNE MCBRIDE A/K/A JOANN</u> <u>MCBRIDE</u> of 250 S. Whiting Street, Apt, 420, Alexandria, VA 22304, parties of the first part,

- AND -

AGNES M. CARROLL, of 805 Hickman Drive, Ocean View, DE 19970, as sole owner, party of the second part.

WITNESSETH: That the said parties of the first part, for and in consideration of the sum of One Dollar (\$1.00), lawful money of the United States of America, the receipt whereof is hereby acknowledged, hereby grant and convey unto the party of the second part, and her heirs and assigns:

ALL that certain lot, piece or parcel of land situate, lying and being in Baltimore Hundred, Sussex County, Delaware, being known and designated as LOT NUMBER THIRTY-THREE (33), BLOCK A, SECTION ONE (1), WHITE'S CREEK MANOR, as shown on a plot of White's Creek Manor, Section 1, prepared by Mann Associates, Registered Surveyors, dated March 29, 1973, which said plot is filed for record in the Office of the Recorder of Deeds in and for Sussex County, at Georgetown, Delaware, in Plot Book 8, at Page 649, and being more particularly described in accordance with a recent survey prepared by Cotten Engineering LLC, Michael Soule Cotten, Professional Engineer, November 2, 2020, as follows, to wit:

COMMENCING at a concrete monument found, said monument having coordinates in the Delaware State Plane coordinate system of N: 201471.69 and E:746672.91, said monument also being the point and place of **BEGINNING** and a corner for the lands described herein and the lands now or formerly of Daniel Collins and lying on the southeasterly right of way line of Document# 2020000059514 BK: 5363 PG: 163 Recorder of Deeds, Scott Dailey On 12/2/2020 at 10:15:00 AM Sussex County, DE Doc Surcharge Paid

Hickman Drive (40' wide), thence with the lands now or formerly of Collins, having a bearing of South $35^{\circ}29'33''$ East for a distance of 155.00 feet, passing over a concrete monument found at 130.11 feet, said monument being the first point in a tie line, to a point, thence turning and running with the meanderings of White Creek in a southwesterly direction for a distance of 97.29 feet, running approximately parallel to a tie line having a bearing of South $25^{\circ}42'50''$ West for a distance of 91.59 feet, to a point, thence with the lands now or formerly of James F. Nagel III, having a bearing of North $33^{\circ}46'15''$ West for a distance of 210.00 feet, passing over an iron pipe found at 34.49 feet, said pipe being the termination point of the previously mentioned tie line, to a concrete monument found, thence with the right of way line of Hickman Drive, thence with a curve to the left having a chord bearing of North $55^{\circ}25'34''$ East for a distance of 75.00 feet, having a radius of 2,335.00 feet and an arc length of 75.00 feet, to the point and place of **BEGINNING, CONTAINING** 14,160± square feet or 0.325± acres, more or less, together with all of the improvements located thereon.

BEING the same lands conveyed to Byron M. McBride and Barbara A. McBride by Deed of Riley S. Williamson and Doreen S. Williamson dated September 25, 1997 and filed for record in the Office of the Recorder of Deeds, in and for Sussex County at Georgetown, Delaware, in Deed Book 2235, page 263. Barbara A. McBride departed this life June 28, 2008 at which time the property passed unto Bryon M. McBride, in its entirety by right of survivorship. Byron M. McBride departed this life intestate April 14, 2020 at which time the property passed unto his only heirs at law, Penny Lynn Deith, Bonita Ann McBride, Donna Lee Nugent and Joanne McBride under the intestate laws of the State of Delaware.

SUBJECT to any and all restrictions, reservations, conditions, easements and agreements of record in the Office of the Recorder of Deeds, in and for Sussex County, Delaware.

Document# 2020000059514 BK: 5363 PG: 164 Recorder of Deeds, Scott Dailey On 12/2/2020 at 10:15:00 AM Sussex County, DE Doc Surcharge Paid

IN WITNESS WHEREOF, the parties of the first part have hereunto set their hands and seals the day and year first above written.

Signed, Sealed and Delivered in the presence of: (SEAL) 1 m Penny Lynn Deith (SEAL) Bonita Ann McBride by Penny L vnn Deith, AIF R A.IF. (SEAL) $\overline{\varphi}_{\gamma}$ Donna Lee Nugent by Penny Lynn Deith, AIF De Δ. AFO manal Joanne McBride a/k/a Joany McBride by Penny Lynn Deith, ATE AIRE) the DE_, COUNTY OF Sussere : to-wit STATE OF BE IT REMEMBERED, that on November $3 \ge 3$, 2020, personally came before me, the subscriber, Penny Lynn Deith and Penny Lynn Deith, Attorney-in-Fact for Bonita Ann McBride, Donna Lee Nugent and Joanne McBride, party of the first-part to this Indenture, known to me personally to be such, and acknowledged this Indenture to be her act and deed. Given under my Hand and Seal of office the day and year aforesaid. **Shannon Carmean Burton** Altorney **Notary Public** Admitted to the Delawere Bar 12-15-03 Printed Name: Bar ID #004386 Uniform Law on Notarial Acts My Commission Expires: _ Pursuant to 29 Del C Sec. 4323(a)(3)

Document# 2020000059514 BK: 5363 PG: 165 Recorder of Deeds, Scott Dailey On 12/2/2020 at 10:15:00 AM Sussex County, DE Doc Surcharge Paid

